Livestock Facility Siting Application

For

Ledgeview Farms, LLC
3875 Dickinson Road
DePere, WI 54115
Jason's Cell (920) 655-3875
jasonpansier@gmail.com

Prepared by

Roach & Associates, LLC
856 N. Main Street
Seymour, WI 54165

Roach & Associates, LLC

Dairy Business and Management Consulting
Environmental Engineering

856 N Main Street • Seymour, WI 54165 • Phone 920-833-6340 • Fax 920-833-9851

I, Renae Peters, on behalf of the Town of Ledgeview, acknowledge that I have received the following Ledgeview Farm, LLC Livestock Facility Siting Application and processing fee:

- One (1) Livestock Facility Siting Application, with Original signatures
- Four (4) duplicate copies of the Livestock Facility Siting Application
- $1,000.00 check for processing the Livestock Facility Siting Application

Renae Peters — *Signature*

12-6-17 — *Date*

ATCP 51 Appendix 1

Exhibit 1
Area Maps of Livestock Facility 2

Exhibit 2
Site Maps of Livestock Facility 3

Exhibit 3
Employee Training Plan 4

Exhibit 4
Environmental Incident & Emergency Response Plan 5

Exhibit 5
Advanced Odor Management Plan 6

Exhibit 6
Waste Storage Facility Summary 7

Exhibit 7
Well Location & Well Construction Logs 8

Exhibit 8
Construction Timeline 9

Exhibit 9
Other Laws & Permits 10

Exhibit 10
Cluster A Odor Scores Documentation 11

Exhibit 11
Cluster B Odor Score Documentation 12

Table of Contents

Livestock Facility Siting Application

- Permit Application Narrative
- ATCP 51 Appendix A
  - Application Form
  - Area Maps of Livestock Facilities (Exhibit 1)
  - Site Maps of Livestock Facilities (Exhibit 2)
  - Employee Training Plan (Exhibit 3)
  - Environmental Incident Response Plan (Exhibit 4)
  - Odor Management Plan (Exhibit 5)
  - Worksheets
    - Worksheet 1 - Animal Units
    - Worksheet 2 – Odor Management
    - Worksheet 3 – Waste and Nutrient Management (Exhibit 6)
    - Worksheet 4 – Waste Storage Facilities (Exhibit 6)
    - Worksheet 5 – Runoff Management (Exhibit 6)

List of Exhibits

Exhibit 1 – Area Maps of Livestock Facility

- Air Photo – Proposed Facilities
- Site Map – Proposed Facilities
- Two Mile Radius Maps (10 panels) for Clusters A & B
  - A Maps – Existing buildings and roads
  - B Maps – Property lines, navigable waters and 10' topographic lines
- Residences within 2500 foot Radius (See Two Mile Radius Maps Panels 5 & 8)
- Plat Map - Town of Ledgeview – T.23N. – R.21E.

Exhibit 2 – Site Maps of Livestock Facility

- Proposed Structures with 1,000 foot Radius (Multiple reference points combine)
- Two foot contours within 300 feet of structures (Multiple reference points combine)

Exhibit 3 – Employee Training Plan

- Employee Training Log

Exhibit 4 – Environmental Incident and Emergency Response Plan

- Environmental Incident and Emergency Response Plan Summary
- Manure or Hazardous Material Spill Accident Worksheet

Exhibit 5 – Advanced Odor Management Plan

- Record of Odor & Dust Complaints

Exhibit 6 – Waste Storage Facility Summary

Exhibit 7 – Well Location & Well Construction Logs

Exhibit 8 – Construction Timeline

Exhibit 9 – Other Laws and Permits

Exhibit 10 – Cluster A Odor Score Documentation

Exhibit 11 – Cluster B Odor Score Documentation

List of Attachments

Attachment 1 – Heifer Site Waste Storage Facility, Y1 Yard Runoff Controls and Leachate Management System Construction Plans and Specifications

Ledgeview Farm, LLC
Livestock Facility Siting Application Narrative

Background Information & Current Operations

Ledgeview Farm, LLC is an existing farm owned and managed by Roy, Glen and Jason Pansier. Currently the farm is operating under a Wisconsin Pollution Discharge Elimination System (WPDES) Permit; however, the WPDES Permit has not yet been issued.

The farm enterprise conducts livestock activities at two production sites. The Headquarters Site (HQ) located at 3875 Dickinson Road DePere. The Heifer Site (HS) is located at 3499 Lime Kiln Road, in Ledgeview Township, in Brown County Wisconsin. The Livestock Facility Siting Application is for new facilities that will be constructed at the Heifer Site.

Ledgeview Farm, LLC (LF) currently has approximately 1,084 milking and dry cows. In addition, the entity raises the replacement heifers (770) and steers (838) from birth to 24 months housed at the HQ and Heifer Sites. This application is to allow expanding livestock Animal Units to 3,483 (Worksheet 1).

Headquarters Site
Structures include:

- Milking Center
- Four (4) Freestall Barns
- Calf Barn
- Heifer Barn (Bedded Pack).
- Machinery Storage
- Shop
- Residence
- Waste Storage Facility
- Feed Storage Area

Heifer Site
Structures include:

- Heifer - Freestall Barn (L2)
- Heifer – Bedded Pack (L1)
- Concrete Yard (Y1)
- Feed Storage Area
- Machinery Storage
- Shop
- Residence

At present, LF has no Waste Storage Facility at the HS. Ledgeview Farm, LLC operates under a Nutrient Management Plan (NMP) and works with Kevin Beckard, of Ag Source to develop the Nutrient Management Plan.

Heifer Site Expansion Plans

The Wisconsin Department of Natural Resources (WDNR) and the Environmental Protection Agency (EPA) are requiring LF to install a Y1 Yard runoff collection system

and a Leachate Management System (LMS) to collect leachate and contaminated runoff. In addition, the agencies require LF to construct additional waste storage capacity, to allow for storage of manure and processed wastewater for a minimum of 180 days. Currently LF has waste storage capacity of approximately 100 days.

New Facilities

- Expansion of the FSA
- LMS to collect leachate and contaminated runoff from the FSA and transfer to waste storage
- Y1 Yard runoff transfer system to waste storage
- Waste Storage Facility
- Expansion of the L2 Freestall Barn (timeline has not been determined)

Siting Application Supplemental Information

Exhibit 1 contains Area Maps of the Livestock Facility. *Exhibit* 2 contains Site Maps of the Livestock Facility. The maps are required by the Livestock Facility Siting Application.

The proposed Barn expansion, Feed Storage Expansion and Waste Storage Facility meet the applicable setback requirements outlined in Wisconsin Administrative Code ATCP 51 as well as the requirements of Brown County. The Town of Ledgeview operates under Wisconsin Administrative Code ATCP 51. The L2 Barn does not meet the setback requirements from a livestock structure to a road right-of-way however; the structure was constructed prior to the Town of Ledgeview adopting Chapter ATCP 51.

There are two (2) well installations at the HS. The existing wells that serve the production site, meets the requirements contained in Wis. Adm. Code NR 811 and NR 812 Table A, as well as the requirements found in Wis. Adm. Code NR 243.15 (1) (2).

As part of the Livestock Facility Siting Application, LF has developed an employee-training plan used to train new and existing employees. *Exhibit 3* contains LF Employee Training Plan.

Ledgeview Farm, LLC has an Environmental Incident Response Plan (EIRP) in place and a copy of the plan is contained in *Exhibit 4*. A Manure or Hazardous Material Spill Accident Worksheet is included as part of the EIRP.

Ledgeview Farm, LLC has developed an Odor Management Plan to reduce the effect of odors produced by the production sites on local residences. *Exhibit 5* contains the LF Odor Management Plan.

Animal Units:

Ledgeview Farm, LLC plans on expanding facilities at the HS to house addition replacement heifers and steers as milking cow numbers grow slowly at the HQ site. The HQ site housing will allow milking cow numbers to be expanded internally without purchasing cattle or adding additional housing. At this time there is no timetable established for expanding the livestock housing at the HS. Worksheet 1 of the Livestock Facility Siting application contains the animal unit numbers that are supported by the current NMP and allow for the expansion of livestock from the current numbers. If additional animal units are proposed in the future, beyond the animal units requested

in Worksheet 1, LF will file an amendment to the Livestock Siting Application as well as updated the NMP to show the land base will support the proposed additional livestock.

Odor Management:
As part of the Livestock Facility Siting Law, expanded livestock operations with more than 1,000 animal units are required to pass the odor standard.

For the purpose of calculating the Odor Score, Chapter ATCP 51 – Livestock Siting allows an applicant to group livestock structures separated by greater than 750 feet into Clusters. The distance between the livestock structures at the Headquarter Site and the Heifer Site is greater than 1,500 feet. Ledgeview Farm, LLC has elected to designate the livestock structures located at the Headquarters Site as Cluster A and the livestock structures located at the Heifer Site as Cluster B. The Odor scores and maps determined a closest neighbor for each Cluster.

Cluster A – Headquarters Site
For Cluster A there are four (4) residences owned by others for which, Odor Scores were calculated. The residence identified as N1 is the residence closest to the WSF at 334 feet. The residence identified as E1 is the residence closest to the L1 Barn (429'). The residence identified as W1 is the residence closest to the L2 Barn (376'), L3 Barn (594') & L4 Barn (465'). The residence identified as S1 is the residence closest to the L5 Barn (398'), L6 Barn (285') and the Y1 Yard (368'). All of the closest neighbors have odor scores above the Livestock Siting Application minimum score of 500. The Nearest Neighbor Site Plan, Odor Score Worksheets and Distance to Neighbor Table are found in Exhibit 10.

Cluster B – Heifer Site
For Cluster B there are three (3) residences owned by others for which, Odor Scores were calculated. The residence identified as N1 is the residence closest to the WSF at 361 feet. The residence identified as E1 is the residence closest to the Collection Basin (1,156'), L1 Barn (855') and Y1 Yard (930'). The residence identified as S1 is the residence closest to the L2 Barn (464') and Y2 Yard (1,079'). All of the closest neighbors have odor scores above the Livestock Siting Application minimum score of 500. The Nearest Neighbor Site Plan, Odor Score Worksheets and Distance to Neighbor Table are found in Exhibit 11

Waste and Nutrient Management:
At expanded conditions, it is estimated that approximately 24.8 million gallons of manure and wastewater is generated annually at both production sites. According to the Nutrient Management Plan (NMP), there is adequate cropland to land apply manure and wastewater for the expanded livestock numbers.

Waste Storage and Transfer Facilities:
As part of the WDNR, Wisconsin Pollution Discharge Elimination System (WPDES) permit, Roach & Associates, LLC inspected and developed an evaluation of the existing facilities at the HQ and HS. Roach & Associates, LLC designed the proposed facilities including the Waste Storage Facility, Manure Transfer System, Feed Storage Area and LMS to meet the criteria found in the Natural Resources Conservation Service (NRCS), Field Office Technical Guide (FOTG), Section IV, Standard 313 Waste Storage Facility,

Standard 522 Pond Sealing or Lining – Concrete, Standard 634 Waste Transfer and Standard 629 Waste Treatment. In addition; all of the criteria found in Wis. Admin. Code ch. NR 243 are met.

1

Chapter ATCP 51

APPENDIX A

APPLICATION FORM AND WORKSHEETS

Application for Local Approval
New or Expanded Livestock Facility

Wisconsin Department of Agriculture, Trade and Consumer Protection
2811 Agriculture Drive
P.O. Box 8911
Madison, WI 53708–8911
(608) 224–4622
(608) 224–4500

Introduction

Use this application form to obtain local approval for a *new* or *expanded* livestock facility (cattle, swine, poultry, sheep or goats) that will exceed 500 "animal units" (or a lower threshold established by local zoning ordinance prior to July 19, 2003).

Some local governments require local approval, but others do not. Check with your local government (county and town or municipality) to see if local approval is required in your area.

In some cases, you may need local approval from more than one local government (for example, the county and the town, or 2 towns if your livestock facility straddles the town line). But the application and approval process should be the same.

The construction of a new or altered *livestock structure* does not, by itself, constitute an "expansion" (unless there will also be an increase in *animal units*). If you already have a permit or local approval, you may not need another approval unless your planned expansion exceeds the number of animals previously authorized by your local government.

Local approval, if required, is governed by statewide uniform standards in Wisconsin Statutes s. 93.90 and Wisconsin Administrative Code chapter *ATCP 51*. This application documents compliance with those standards.

The Livestock Facility

A livestock facility includes livestock, livestock structures, the land on which they are located (it does not include pastures or winter grazing areas). *Related livestock facilities* (see definition below) are treated as a single livestock facility, for purposes of local approval. However:

- *A separate species facility* (see definition below) may be treated as a separate livestock facility, even if it is owned by the same person and located on the same land parcel as another livestock facility.
- A mere acquisition of a neighboring livestock facility does not constitute an *expansion* unless more *animal units* are added to the combined facilities.

Completing the Application

If local approval is required, complete this entire application form (including the worksheets). Follow the instructions in the application form. Attach all of the supplementary documentation required. Your application must be complete, credible and internally consistent.

The application form and worksheets ask for information to show compliance with Wisconsin livestock facility siting standards. A local government has *very limited* authority to modify the standards by local ordinance (modifications, if any, must be reflected in the local version of this application form).

As part of your application, you must specify the number of *animal units* that you will keep at a new or expanded livestock facility. If the local government approves your requested number, this will be the maximum number that you may keep for 90 days or more in any 12-month period.

A local government may require you to submit up to 4 duplicate copies of the complete application, worksheets, maps and other attachments. But you are not required to submit duplicate copies of engineering design specifications.

Worksheets

This application includes the following worksheets:

- *Animal units* (worksheet 1)
- Odor management (worksheet 2)
- Waste and nutrient management (worksheet 3)
- Waste storage facilities (worksheet 4)
- Runoff management (worksheet 5)

Complete the worksheets following all instructions (including those on each worksheet). You may use a convenient automated spreadsheet in place of Tables A and B of worksheet 2 if you prefer (results are identical). The spreadsheet is available at http://www.datcp.state.wi.us.

If the Wisconsin Department of Natural Resources (*DNR*) has issued a Wisconsin Pollutant Discharge Elimination System (*WPDES*) permit for your proposed livestock facility, you can check a box on worksheets 3, 4 and 5, and submit a copy of that permit with the worksheets. A *WPDES* permit does not affect the requirements for completing worksheets 1 and 2.

Fees

A local government may require a fee to offset its reasonable costs to review and process this application. The fee, if any, must be established by local ordinance and may not exceed $1,000. A local government may NOT charge any other fee, or require you to post any bond or security.

Local Approval Process

If you complete the application properly, the local government MUST APPROVE the proposed livestock facility unless it finds, based on clear and convincing evidence in the local record, that the facility fails to meet the state standards.

Within 45 days after you submit your application, the local government must notify you whether your application is complete. If you failed to complete part of the application, you must submit the missing information. The local government must grant or deny the application within 90 days after it declares the application complete, and issue its decision in writing. The approval must include a duplicate copy of the approved application, marked "approved." The duplicate copy shall include all the worksheets, maps, and other attachments included in the application, with the exception of the engineering design specifications. The local government must make a record of its decision making process, and the evidence supporting its decision. The record must include your application.

Appeal of Local Decision

If you disagree with the local government's decision on your application, you may appeal that decision to the Wisconsin Livestock Facility Siting Review Board ("Board"). Other "aggrieved persons" may also appeal to the Board. An "aggrieved person" includes any person who resides or owns land within 2 miles of your proposed livestock facility.

You must file your appeal within 30 days after the local government issues its decision (or, if you pursue a local administrative appeal process first, within 30 days after that appeal process is complete). The Board will review the local decision based on the evidence in the local record (it will not hold a new hearing or accept new testimony or evidence). You must file your appeal in writing at the following address:

Wisconsin Livestock Facility Siting Review Board
c/o Secretary, Department of Agriculture, Trade and Consumer Protection
P.O. Box 8911
Madison, WI 53708–8911

Terms Used in this Application Form

In this application form, you will see a number of ***italicized*** terms. Those terms are defined below (for more specific definitions, see *ATCP 51*):

"Adjacent" – Located on land parcels that touch each other, or on land parcels that are separated only by a river, stream, or transportation or utility right–of–way.

"Affected Neighbors" – Residences or *high–use buildings* within 2500 feet of any livestock structure at the proposed facility, other than those owned by the applicant or by persons who have agreed to exclude them from the applicant's odor score calculation. The total odor score for a *livestock facility* depends, in part, on the proximity and density of "affected neighbors."

"Animal housing area" – That portion of an animal housing structure to which animals have access, and in which manure may accumulate. "Animal housing area" includes free–stalls and travel lanes. It does NOT include holding areas, feed alleys, storage areas or milking parlors.

"Animal lot" – A feedlot, barnyard or other outdoor facility where livestock are concentrated for feeding or other purposes. Pastures and winter grazing areas are NOT "animal lots." Treat multiple "animal lots" as a single "animal lot" if runoff from the "animal lots" drains to the same treatment area or if runoff from the "animal lot" treatment areas converges or reaches the same surface water within 200 feet of any of those treatment areas.

"Animal units" – Equivalent units of *livestock*. The number of animals constituting an "animal unit" varies by species. For example, one milking dairy cow equals 1.4 "animal units." A beef animal over 600 lbs. equals 1.0 "animal units." A pig over 55 lbs. equals 0.4 "animal units." A laying chicken equals 0.01 "animal unit." The number of "animal units" kept at a *livestock facility* means the largest number of "animal units" that will be at the *livestock facility* on at least 90 days in any 12–month period. Calculate "animal units" according to worksheet 1.

"BARNY runoff model" – The Wisconsin version of a model that is commonly used to predict nutrient runoff from *animal lots*. An Excel computer spreadsheet version is available on the DATCP website (engineering directory).

"Certified agricultural engineering practitioner" – A practitioner who is properly qualified under *ATCP 50.46*.

"Cluster" – Any group of one or more *livestock structures* within a *livestock facility*. If you wish to do so, you may calculate separate odor scores for "clusters" that are separated by more than 750 feet.

"Complete application for local approval" – An application that contains everything required under ss. ATCP 51.30(1) to (4).

"DATCP" – Wisconsin Department of Agriculture, Trade and Consumer Protection. The application form cites DATCP rules including Wis. Adm. Code chs. *ATCP 51* (livestock facility siting), *ATCP 50* (soil and water resource management) and *ATCP 17* (livestock premises registration).

"DNR" – Wisconsin Department of Natural Resources. The application form cites DNR rules including Wis. Adm. Code chs. *NR 243* (*WPDES* permits), *NR 811* (community wells) and *NR 812* (private wells).

"Expanded livestock facility" – The entire *livestock facility* created by an *expansion*, including new, existing and altered *livestock structures* (existing structures are subject to less rigorous standards). Your application must indicate the maximum number of *animal units* that you will keep at the "expanded livestock facility."

"Expansion" – An increase in the largest number of *animal units* kept at a *livestock facility* on at least 90 days in any 12-month period. The acquisition of an existing livestock facility, by the operator of an *adjacent* facility, is not an "expansion" unless the operator increases the largest number of *animal units* kept at the combined livestock facilities on at least 90 days in any 12-month period.

"High-use building" – A residential building that has at least 6 distinct dwelling units; a restaurant, hotel, motel, or tourist rooming house; a school building; a hospital or licensed care facility; or a non-farm business or workplace that is open at least 40 hours a week. The odor score for your *livestock facility* depends, in part, on the proximity and density of neighboring "high-use buildings."

"Karst features" – Sinkholes, fractured bedrock or like features that may result in direct pollution runoff to groundwater.

"Livestock" – Cattle, swine, poultry, sheep or goats.

"Livestock facility" – A feedlot, dairy farm, or other operation where *livestock* are or will be fed, confined, maintained, or stabled for a total of 45 days or more in any 12-month period. A "livestock facility" includes all of the tax parcels on which the facility is located, but it does NOT include a parcel used only for *pasture* or as a *winter grazing area*. *Related livestock facilities* are considered a single "livestock facility," except a livestock operator may elect to treat a *separate species facilities* as a separate livestock facility.

"Livestock structure" – A building or structure such as a barn, milking parlor, feed storage facility, feeding facility, *animal lot* or *waste storage structure*. *Pastures*, *winter grazing areas* and machine sheds are NOT "livestock structures."

"Local approval" – A license, permit, special zoning exception, conditional use permit, or other local authorization for a *new or expanded livestock facility*. This application form applies, regardless of the form of local approval. However, this application form does NOT cover any of the following permits (for which separate requirements may apply):

- Building, electrical or plumbing permits (if local standards are consistent with state code).
- Manure storage system permits (*see ATCP 50.56*), UNLESS construction is part of a *new or expanded livestock facility*.
- Permits required by certain local ordinances related to shoreland zoning, floodplain zoning, construction site erosion control or stormwater management.

"New livestock facility" – A *livestock facility* used for the first time, or for the first time in at least 5 years.

"NRCS" – The Natural Resource Conservation Service of the United States Department of Agriculture. Wisconsin livestock siting standards refer to NRCS Technical Guide standards.

"Pasture" – Land on which livestock graze or otherwise seek feed in a manner that maintains the vegetative cover over all of the grazing or feeding area.

"Premises ID" – The unique ID number assigned to your *livestock facility* under the Wisconsin Livestock Premises Registration Program (*ATCP 17*). Go to http://www.datcp.state.wi.us for more information. To register your *livestock facility*, go to http://www.wiid.org/.

"Qualified nutrient management planner" – A person, other than the applicant, who is qualified under *ATCP 50.48*.

"Related livestock facilities" – Two or more *livestock facilities* that are owned or managed by the same person and meet any of the following criteria:

- They are located on the same tax parcel or *adjacent* tax parcels.
- They use any of the same *livestock structures* to collect or store manure.
- They generate manure that is applied to the same parcel of land.

"Separate Species Facility" – A distinct part of *a livestock facility* that meets all of the following criteria:

- It has only one of the following types of livestock, and that type is not found in any other part of the *livestock facility*:
  - Cattle
  - Swine
  - Poultry
  - Sheep
  - Goats
- It has no more than 500 *animal units*.
- Its animal housing and manure storage structures, if any, are located at least 750 feet from *livestock structures* that are used by other parts of the *livestock facility*.

"Substantially altered" livestock structure – A *livestock structure* that undergoes a material change in construction or use such as:

- An increase in the capacity of a *waste storage facility*.
- The addition of a liner to a *waste storage facility*.
- An increase of more than 20% in the area or capacity of a *livestock structure* used to house, feed, or confine *livestock* or to store livestock feed.
- An increase of more than 20% in the number of *animal units* that will be kept in a *livestock structure* on at least 90 days in any 12– month period.

"Waste storage structure" – An embankment structure, excavated pit, dugout or fabricated structure that is used to store manure, milking center waste or other organic waste generated by a *livestock facility*. For the purposes of waste storage structure setback (application form, A–2) and worksheet 2, a "waste storage structure" does not include a structure used to collect and store waste under an animal housing facility, or a manure digester consisting of a sealed structure in which manure is subjected to managed biological decomposition.

"Waste storage facility" — A *waste storage structure* and any attached piping or equipment used to load or unload the structure.

"Winter grazing area" – Cropland or *pasture* where *livestock* feed on dormant vegetation or crop residue, with or without supplementary feed, during the period October 1 to April 30. "Winter grazing area" does *not* include any of the following:

- An area, other than a *pasture*, where *livestock* are kept during the period from May 1 to September 30.
- An area which at any time has an average of more than 4 *animal units* per acre.
- An area from which *livestock* have unrestricted access to navigable waters of the state.
- An area in which manure deposited by *livestock* causes nutrient levels to exceed standards in *ATCP 51.16*.

"WPDES permit" – Wisconsin Pollutant Discharge Elimination System permit issued by DNR for a concentrated animal feeding operation over 1000 *animal units*, or for operations of any size that discharge pollutants directly to waters of the state.

arm–lwr– 11/04 January, 2006

Wisconsin Department of Agriculture, Trade and Consumer Protection
2811 Agriculture Drive, PO Box 8911, Madison WI 53708–8911
Phone: (608) 224–4622 or (608) 224–4500

Application for Local Approval
New or Expanded Livestock Facility

Wis. Statutes s. 93.90
Wis. Adm. Code ch. ATCP 51

1. Legal Name of Applicant (Business Entity): Ledgeview Farm, LLC

2. Type of Business Entity: check one

☐ Individual	☐ Corporation	☐ Partnership	☐ Cooperative	☒ LLC
☐ Trust	☐ Other	Describe:		

3. Other names, if any, under which applicant does business (list all):

4. Contact Individual: Name: Jason Pansier

Phone: 920-655-3875 E-mail: jasonpansier@gmail.com

5. Business Address: Street Address: 3875 Dickinson Rd

City/Village/Town:	County:	State:	Zip:
DePere	Brown	WI	54115

6. Principal Owners or Officers (list if applicant is an entity other than an individual):

Name:	Title:	Phone:	
Jason Pansier	Member	920-655-3875	
Address: 3875 Dickinson Rd	City: DePere	State: WI	Zip: 54115
Name: Roy Pansier	Title: Member	Phone: 920-655-1344	
Address: 3875 Dickinson Rd	City: DePere	State: WI	Zip: 54115
Name: Glen Pansier	Title: Member	Phone: 920-655-0416	
Address: 3875 Dickinson Rd	City: DePere	State: WI	Zip: 54115

7. Description of Proposed *Livestock Facility* Leachate Management System, Yl Yard Runoff Transfer System, Waste Storage Facility, Feed Storage Area, Barn Expansion

Check one: ☐ New *Livestock Facility* ☒ *Expanded Livestock Facility* Premises ID: OOKKELB

Address of Proposed *Livestock Facility:* 3499 Lime Kiln Rd

City/Village/Town:	County:	State:	Zip:
Green Bay	Brown	WI	54311

Town #	Range # (E or W)	Section #	¼ Section #
23	21E	28	SE

Application (continued)

8. Total *Animal Units*

Enter total *animal units* from **worksheet 1:**

Total *Animal Units*: 3,483 . This is the maximum *livestock facility* size for which the applicant requests approval at this time.

9. Area Map of *Livestock Facility* Exhibit 1

Attach a scale map or aerial photo of the proposed *livestock facility* and surrounding area. The map or photo must be appropriately sized and marked, so that it clearly and legibly shows all of the following:

- All existing and proposed *livestock structures*. Label each *livestock structure* to show structure type, and whether existing or proposed.
- The area lying within 2 miles of any of the *livestock structures*. Show all existing buildings, property lines, roadways, and navigable waters lying within that area.
- All residences and *high use buildings* within 2500 ft. of any *livestock structure*. Show which (if any) of those buildings are owned by the applicant, or by persons who have agreed to exclude the buildings from the applicant's odor worksheet calculations.
- Topographic lines at 10 ft. elevation intervals.
- Map scale and north direction indicator.

10. Site Map of *Livestock Facility* Exhibit 2

Attach a scale map or aerial photo of the proposed *livestock facility* site. The map or photo shall be appropriately sized and marked, so that it clearly and legibly shows all of the following:

- All existing and proposed *livestock structures*. Label each *livestock structure* to show structure type, and whether existing or proposed.
- The area lying within 1,000 ft. of any of the *livestock structures*. Show all existing buildings, property lines, roadways, navigable waters, and known *karst features* within that area.
- Topographic lines, at 2 ft. elevation intervals, for the area within 300 feet of the *livestock structures*.
- Map scale and north direction indicator.

11. Location of *Livestock Structures*

The applicant certifies that:

- All *livestock structures* comply with applicable local property line and road setbacks (see *ATCP 51.12*).
- All *waste storage structures* comply with setbacks in *ATCP 51.12(2)*.
- All *livestock structures* comply with applicable local shoreland, wetland, and floodplain zoning ordinances (copies available from local government).
- Wells comply with the Wisconsin well code (*NR 811* and *812*). *New or substantially altered livestock structures* are separated from existing wells (including neighbors' wells) by setback distances required in *NR 811* and *812*.

Application (continued)

12. Employee Training Plan Exhibit 3

Attach an Employee Training Plan for employees who will work at the *livestock facility.* Applicant determines plan contents, as long as the plan identifies all of the following:

- Training topics including, at a minimum, nutrient management, odor management, runoff management, manure and waste handling, employee safety, and environmental incident response.
- The number and job categories of employees to be trained.
- The form and frequency of training, which at a minimum must include a plan for at least one training per year.
- Training presenters (these may include *livestock facility* managers, consultants or professional educators).
- A system for taking and recording attendance.

13. Environmental Incident Response Plan Exhibit 4

Attach an Environmental Incident Response Plan for the *livestock facility.* Applicant determines plans contents, as long as the plan identifies all of the following:

- Types of environmental incidents covered. These must include, at a minimum, overflows and spills from waste storage facilities, catastrophic system failures, manure spills during transport and application, movement of manure during or after application, catastrophic mortality disposal emergency, and odor complaints.
- The name and business telephone number of at least one individual who will handle public questions and concerns related to environmental incidents.
- The names and telephone numbers of first responders (e.g. DNR, fire departments, excavation contractors).
- Incident response procedures, including emergency response, recordkeeping and reporting procedures.

14. Odor Management Plan (*Optional*) Exhibit 5

An applicant required to complete the odor management worksheet may attach an *optional* odor management plan. The applicant determines plan contents, as long as the plan addresses all of the following: activities to reduce community conflict; practices used to reduce dust; practices used to reduce odor from feed storage leachate; practices used to conserve water; and practices used to reduce odor from dead animals.

Application (continued)

15. Other Laws

The following laws, among others, may apply to the operation of a *livestock facility*. Local approval of a *livestock facility* siting application is NOT based on these laws, except as specifically provided in *ATCP 51*. However, violations may have other legal consequences:

- Soil conservation and nonpoint pollution laws (contact your county land conservation department). Livestock facilities that have 1,000 or more animal units, or that discharge pollutants directly to waters of the state, must also obtain a *WPDES permit* from *DNR*.
- Pesticide and agricultural chemical laws administered by *DATCP*.
- Animal disease control laws administered by *DATCP*.
- Animal mortality laws administered by *DATCP*.
- Vehicle weight limits and state prohibitions against spilling waste on roads.
- Food safety and animal health licenses administered by *DATCP*. All livestock operations must register, and some (such as dairy farms) must hold a state license.
- Air pollution control regulations administered by *DNR*.
- Building, electrical, plumbing and sanitation codes administered by the Wisconsin Department of Safety and Professional Services. A local authority may disapprove a proposed *livestock facility* that violates a conforming local code.
- Construction site erosion control laws administered by *DNR*.
- Local erosion control and stormwater management ordinances.
- Petroleum storage laws administered by the Wisconsin Department of Safety and Professional Services.
- High capacity well regulations administered by *DNR*.

16. Worksheets

Complete worksheets as required (follow instructions on each worksheet) and attach to application.

Worksheet 1 – Animal Units.

Worksheet 2 – Odor Management.

Worksheet 3 – Waste and Nutrient Management. If you hold a *WPDES permit* from *DNR* for the same proposed *livestock facility* (for an equal or greater number of *animal units*), check the appropriate box on this worksheet, and submit a copy of the permit with this application.

Worksheet 4 – Waste Storage Facilities. If you hold a *WPDES permit* from *DNR* for the same proposed *livestock facility* (for an equal or greater number of *animal units*), check the appropriate box on this worksheet, and submit a copy of the permit with this application.

Worksheet 5 – Runoff Management. If you hold a *WPDES permit* from *DNR* for the same proposed *livestock facility* (for an equal or greater number of *animal units*), check the appropriate box on this worksheet, and submit a copy of the permit with this application.

Application (continued)
Authorized Signature: *I certify that the information contained in this application (including worksheets and all attachments) is complete and accurate to the best of my knowledge.* X _____ 11/22/17 Signature of Applicant or Authorized Representative — Date Jason Parsitt — Owner Partner Print Name — Title

For Office Use Only:	
Application #:	
Date Application Received:	
Date Completeness Determined:	**Date Notice Sent to Applicant:**
Date Notice Sent to Adjacent Landowners:	
Decision Date:	
Approved or Disapproved:	
Date Appeal Filed (if any):	

arm–lwr– 11/04 January 2006

Wisconsin Department of Agriculture, Trade and Consumer Protection
2811 Agriculture Drive, PO Box 8911, Madison WI 53708–8911
Phone: (608) 224–4622 or (608) 224–4500

Worksheet 1 – *Animal Units*

Instructions: Use this worksheet to determine the number of *animal units* for which you request approval. You may request approval for a number that is large enough to accommodate current and potential future expansions. If the local government approves the requested number of *animal units*, that is the maximum number that you may keep for 90 days or more in any 12–month period. You may not exceed that number without additional approval.

To complete this worksheet:

1. Identify each type of *livestock* that you might keep at the proposed facility. Enter the maximum number of animals of each type that you might keep for at least 90 days in any 12–month period.
2. Multiply the number of animals of each type by the relevant Animal Unit Factor to obtain *animal units* of each type.
3. Sum the *animal units* for all *livestock* types to obtain the Total *Animal Units* for which you request approval.

	***Livestock* Type**	**Animal Unit Factor**	***Animal Units* For Proposed Facility**
Example – Milking & Dry Cows			*1.4 x 800 = 1120 AU*
Dairy Cattle	Milking and Dry Cows	**1.4**	1.4 x 1355 = 1897
	Heifers (800 lbs. to 1200 lbs.)	**1.1**	1.1 x 450 = 495
	Heifers (400 lbs. to 800 lbs.)	**0.6**	0.6 x 270 = 162
	Calves (up to 400 lbs.)	**0.2**	0.2 x 270 = 54
Beef	Steers or Cows (600 lbs. to market)	**1.0**	1.0 x 675 = 675
	Calves (under 600 lbs.)	**0.5**	0.5 x 400 = 200
	Bulls (each)	**1.4**	1.4 x =
Swine	Pigs (55 lbs. to market)	**0.4**	0.4 x =
	Pigs (up to 55 lbs.)	**0.1**	0.1 x =
	Sows (each)	**0.4**	0.4 x =
	Boars (each)	**0.5**	0.5 x =
Poultry	Layers (each)	**0.01**	0.01 x =
	Broilers (each)	**0.005**	0.005 x =
	Broilers – continuous overflow watering	**0.01**	0.01 x =
	Layers or Broilers – liquid manure system	**0.033**	0.033 x =
	Ducks – wet lot (each)	**0.2**	0.2 x =
	Ducks – dry lot (each)	**0.01**	0.01 x =
	Turkeys (each)	**0.018**	0.018 x =
Sheep (each)		**0.1**	0.1 x =
Goats (each)		**0.1**	0.1 x =
Total *Animal Units* for Which Applicant Requests Approval			= 3,483

Signature of Applicant or Authorized Representative

11/22/17
Date

Arm–lwr– 11/04 January 2006

Wisconsin Department of Agriculture, Trade and Consumer Protection
2811 Agriculture Drive, PO Box 8911, Madison WI 53708–8911
Phone: (608) 224–4622 or (608) 224–4500

Worksheet 2 – Odor Management Cluster A - Exhibit 10

Instructions: This worksheet addresses odor from *livestock structures*. You are NOT required to complete this worksheet if any of the following apply (check box if applicable):

☐ I am requesting approval for a *new livestock facility* with fewer than 500 *animal units*.

☐ I am requesting approval for an *expanded livestock facility* with fewer than 1,000 *animal units*.

☐ All *livestock structures* will be at least 2500 ft. from the nearest affected neighbor.

If you checked any of the above boxes, just sign below and submit this page with your application. If you did NOT check any of the above boxes, you must complete this worksheet to calculate the odor score (Box 4) for your proposed *livestock facility*. To meet the odor management standard, you must have a total odor score of 500 or more.

If *livestock structures* are located in *clusters* that are separated by more than 750 feet, you may elect to complete a separate worksheet for each *cluster*. If you choose that option, each *cluster* must meet the odor management standard.

A complete worksheet must include Tables A and B. You may use a convenient automated spreadsheet in place of Tables A and B if you prefer (submit spreadsheet output instead of tables, results will be identical). However, you must still sign and submit this signature page. The spreadsheet is available at the *DATCP* website, http://www.datcp.state.wi.us.

TO COMPLETE THIS WORKSHEET, FOLLOW THESE STEPS:

Step 1: Complete Table A to determine the Predicted Odor from your *livestock structures*. Enter the Predicted Odor in Box 3 below (NOT Box 1).

Step 2: Complete Table B to determine your Separation Score. Enter your Separation Score in Box 1 below. (NOT Box 2).

Step 3: Enter your management credits in Box 2 (maximum 100 points). All applicants may enter 80 points for completing required incident response and employee training plans (described on page A–3). Applicants completing an optional odor management plan (described on page A–3), may add an additional 20 points. Applicants determine plan contents, as long as the plan addresses the required topics.

Step 4: Add Box 1 and Box 2. Subtract Box 3 and enter the total in Box 4. This is your Odor Score.

Box 1		Box 2		Box 3		Box 4
569	+	100	–	78	=	591
Separation Score (from Step 2)		**Management Score** (from Step 3)		**Predicted Odor** (from Step 1)		**Odor Score**

A local government must approve a *livestock facility* with an odor score of 500 or more (Box 4). You may add odor control practices to increase your odor score to 500 or more. A local government may approve, but is not required to approve, a *livestock facility* with an odor score less than 500 but not less than 470.

Signature of Applicant or Authorized Representative

11/22/17
Date

Arm–lwr– 11/04 January 2006

Wisconsin Department of Agriculture, Trade and Consumer Protection
2811 Agriculture Drive, PO Box 8911, Madison WI 53708–8911
Phone: (608) 224–4622 or (608) 224–4500

Worksheet 2 – Odor Management Cluster B - Exhibit 11

Instructions: This worksheet addresses odor from *livestock structures.* You are NOT required to complete this worksheet if any of the following apply (check box if applicable):

☐ I am requesting approval for a *new livestock facility* with fewer than 500 *animal units.*

☐ I am requesting approval for an *expanded livestock facility* with fewer than 1,000 *animal units.*

☐ All *livestock structures* will be at least 2500 ft. from the nearest affected neighbor.

If you checked any of the above boxes, just sign below and submit this page with your application. If you did NOT check any of the above boxes, you must complete this worksheet to calculate the odor score (Box 4) for your proposed *livestock facility.* To meet the odor management standard, you must have a total odor score of 500 or more.

If *livestock structures* are located in *clusters* that are separated by more than 750 feet, you may elect to complete a separate worksheet for each *cluster.* If you choose that option, each *cluster* must meet the odor management standard.

A complete worksheet must include Tables A and B. You may use a convenient automated spreadsheet in place of Tables A and B if you prefer (submit spreadsheet output instead of tables, results will be identical). However, you must still sign and submit this signature page. The spreadsheet is available at the *DATCP* website, http://www.datcp.state.wi.us.

TO COMPLETE THIS WORKSHEET, FOLLOW THESE STEPS:

Step 1: Complete Table A to determine the Predicted Odor from your *livestock structures.* Enter the Predicted Odor in Box 3 below (NOT Box 1).

Step 2: Complete Table B to determine your Separation Score. Enter your Separation Score in Box 1 below. (NOT Box 2).

Step 3: Enter your management credits in Box 2 (maximum 100 points). All applicants may enter 80 points for completing required incident response and employee training plans (described on page A–3). Applicants completing an optional odor management plan (described on page A–3), may add an additional 20 points. Applicants determine plan contents, as long as the plan addresses the required topics.

Step 4: Add Box 1 and Box 2. Subtract Box 3 and enter the total in Box 4. This is your Odor Score.

Box 1		Box 2		Box 3		Box 4
569	+	100	−	115	=	554
Separation Score (from Step 2)		**Management Score** (from Step 3)		**Predicted Odor** (from Step 1)		**Odor Score**

A local government must approve a *livestock facility* with an odor score of 500 or more (Box 4). You may add odor control practices to increase your odor score to 500 or more. A local government may approve, but is not required to approve, a *livestock facility* with an odor score less than 500 but not less than 470.

Signature of Applicant or Authorized Representative

11/22/17
Date

See Exhibits 10 + 11

TABLE A: Predicted Odor from *Livestock Structures*

Worksheet 2 (continued)

Instructions: Complete Table A. You must measure all structures to the same affected neighbor. If the nearest neighbor is not the same for all livestock structures, you will need to complete the table once for each close neighbor. Compare the "H" Total of the table for each neighbor. The neighbor that has the lowest weighted distance is considered your nearest affected neighbor, and you should use that table to complete the odor worksheet. Enter the Column F total on page A-6 in **Box 3**. Enter the Column G result on page A-8 in **Table B, Step 1**. Add lines or use additional sheet, if needed, to list all structures.

1. *Animal Housing Areas* – List each

	Column A **Manure Management Type** Enter your housing buildings and the related 4-letter code from Chart 2. You may exclude up to 1000 calf hutches and 4 structures less than the sq. footage listed in Chart 2.	Column B **Odor Generation Number** From Chart 2	Column C **Housing Area** (Ft^2) Use occupied animal area only. Exclude feed alleys, holding areas and milking parlors. Express in 10,000s. (Ex. 15,523 ft^2 = 1.55)	Column D **Odor Control Practice Codes** List all that apply to each housing area, from Chart 3	Column E **Multiplier for Odor Control Practice** List all that apply to Each from Chart 3. Enter "1" if none.	Column F **Predicted Odor** Multiply columns B, C, and E	Column G **Distance to Nearest *Affected Neighbor*** (ft) Measure from corner of the bldg to corner of the neighbor's bldg. Measure all to the same neighbor.	Column H **Weighted Distance** (ft.) Multiply columns F & G
1A.								
1B.								
1C.								
1D.								
1E.								

2. *Waste Storage Facilities* – List each

	Column A **Waste Storage Type** Enter 4-letter type code from Chart 2	Column B **Odor Generation Number** From Chart 2	Column C **Exposed Surface Area** Measure surface area (ft^2) when pit is filled to capacity, excluding freeboard. Enter in 10,000's. (Ex: 75,575 = 7.56)	Column D **Odor Control Practice Codes** List all that apply to each facility from Chart 3	Column E **Multiplier for Odor Control Practice** List all that apply to each from Chart 3. Enter "1" if none.	Column F **Predicted Odor** Multiply columns B, C, and E	Column G **Distance to Nearest *Affected Neighbor*** (ft) Measure from top inside edge to neighbor's bldg corner. Measure to the same neighbor.	Column H **Weighted Distance** (ft.) Multiply columns F & G
2A.								
2B.								
2C.								
2D.								

3. *Animal Lots* – List each

	Column A **Animal Lot Type** Enter 4-letter type code from Chart 2	Column B **Odor Generation Number** From Chart 2	Column C **Animal Lot Area** (ft^2) Enter in 10,000's (Ex: 7438 = .74)	Column D **Odor Control Practice Codes** List all that apply to each facility from Chart 3	Column E **Multiplier for Odor Control Practice** List all that apply to each from Chart 3. Enter "1" if none.	Column F **Predicted Odor** Multiply columns B, C, and E	Column G **Distance to Nearest *Affected Neighbor*** (ft) Measure from corner to corner. Measure all structures to the same neighbor.	Column H **Weighted Distance** (ft.) Multiply columns F & G
3A.								
3B.								
3C.								
						F Total	**G = (H Total) ÷ (F Total)**	**H Total**
						Enter on page A-6, Box 3	Enter on page A-8, Table B, Step 1	

Worksheet 2 (continued)

Table B: Separation Score

INSTRUCTIONS	RESULTS
Step 1: Enter, at right, the result from Table A, Column G (page A-7).	**Distance (ft.) to Nearest *Affected Neighbor*:** _____
Step 2: Select multiplier based on the compass direction looking from the *livestock facility* to the nearest *affected neighbor*. Enter at right.	**Multiplier:** _____
Compass Direction / **Multiplier**: North 1.0; Northeast 1.0; East 1.1; Southeast 1.2; South 1.2; Southwest 1.2; West 1.3; Northwest 1.1	
Step 3: Calculate wind-adjusted separation distance (Distance to nearest *affected neighbor* x multiplier). Enter at right.	**Wind-Adjusted Separation Distance (ft.)** _____
Step 4: Determine *affected neighbor* density and enter at right: *Low density* = No more than 5 residences and no *high-use buildings* within 1300 ft of each structure. *High density* = 6 or more residences or at least one *high-use building* within 1300 ft of each structure.	**Low or High Density?** _____
Step 5: Use results above and Chart 1 to find your Separation Score. Enter at right and on Page A-6 in **Box 1**.	**Separation Score**

Chart 1: Separation Score

Wind-Adjusted Separation Distance (ft.)	Low Density	High Density
0-99	505	503
100-149	506	504
150-199	511	507
200-249	516	510
250-299	521	514
300-349	527	518
350-399	534	523
400-449	541	528
450-499	548	533
500-599	560	542
600-699	577	555
700-799	595	569
800-899	615	585
900-999	636	601
1000-1099	658	619
1100-1199	681	637
1200-1299	705	657
1300-1399	730	
1400-1499	756	
1500-1599	783	
1600-1699	810	
1700-1799	839	
1800-1899	868	
1900-1999	899	
2000-2099	930	
2100-2199	962	
2200-2299	994	
2300-2399	1027	
2400-2499	1061	
2500-2749	1123	
2750-2999	1214	
3000-3249	1309	

Worksheet 2 (continued)

Chart 2: Odor Generation Numbers

Animal Housing Area Type	Housing/ Management Type Code	Manure Management Method	Odor Generation Number	Exempt Buildings Maximum Size (ft^2) *(May exclude up to 4)*
Dairy Stanchion	DSDC	Daily to weekly cleaning	2	7500
Dairy Free Stall and Beef & Dairy Heifers (Forage Ration)	DBSS	Slatted floor (includes floor and pit below)	6	2500
	DBSC	Scrape	4	3500
	DBAF	Alley flush to storage	10	1500
	DBBP	Bedded pack	2	7500
Beef Finishing (High Energy Ration)	BFSF	Slatted floor (includes floor and pit below)	12	1000
	BFSC	Scrape	8	2000
	BFBP	Bedded pack	4	3500
Pork Gestation/ Farrow/Nursery	PGSF	Slatted floor (includes floor and pit below)	46	N/A
	PGPP	Pull plug to storage	22	N/A
Pork Finishing	PFSF	Slatted floor (includes floor and pit below)	34	N/A
	PFPP	Pull plug to storage	20	N/A
	PFSS	Scrape systems to storage	11	1500
	PFDB	Deep bedded	4	3500
Poultry	PBLT	Broiler (litter)	1	15000
	PDLQ	Ducks (liquid)	20	N/A
	PLAY	Layers	20	N/A
	PTDL	Turkey and Ducks (litter)	2	7500

Type Codes	*Waste Storage Facility* Types *Note: Storage under slatted floor is addressed under animal housing.*	Odor Generation Number
WSSS	Solid (stack)	2
WSLT	Long term (6 months or longer as determined in Column E of worksheet 3)	13
WSST	Short term (less than 6 months as determined in Column E of worksheet 3)	28

Animal Lot Codes	*Animal Lot* Types		Odor Generation Number
ALPV	**Paved**		4
UPDB	**Unpaved**	Dairy/Beef/Sheep/Goats	6
UPSW		Swine/Poultry	11

Worksheet 2 (continued)

Chart 3: Odor Control Practices

Category	Practice Code	Practice Name (Practices must meet specifications on pages A-11 to A-13)	Multiplier*
		Animal Housing Area	
A	A1	Diet manipulation	0.8
B (Choose only 1)	B1	Bio-filter	0.1
	B2	Vegetable oil sprinkling (for swine only)	0.4
	B3	Fresh water flush	0.4
	B4	Treated water flush	0.7
	B5	Air Dam (for swine only)	0.9
C	C1	Windbreak (includes man-made berms)	0.9
D	D1	Frequent cleaning of animal housing area	0.9
		Waste Storage Facilities	
E (Choose only 1)	E1	Anaerobic digestion	0.2
	E2	Chemical or biological additives	0.8
	E3	Compost	0.2
	E4	Solids Separation and Reduction	0.6
	E5	Water Treatment	0.1
F (Choose only 1)	F1	Aeration	0.3
	F2	Bio-cover	0.4
	F3	Geotextile cover	0.5
	F4	Impermeable cover	0.1
	F5	Natural crust	0.3
	F6	Bottom fill	0.9
G	G1	Windbreak (includes man-made berms)	0.9
		Animal Lots	
H (Choose only 1)	H1	Frequent cleaning of *animal lot*	0.4
	H2	Drag *animal lot*	0.5
I	I1	*Animal lot* moisture control	0.8
J	J1	Windbreak (includes man-made berms)	0.9

*Smaller multiplier = more odor controlled (e.g. a multiplier of 0.4 represents a 60% control).

Innovative Odor Control Practices (all odor sources):
You may take credit for odor control practices not listed in Chart 3 if *DATCP* pre-approves a multiplier for each of those practices. Follow the procedure in *ATCP 51.14(5)(c)* to obtain *DATCP* approval. If you obtain *DATCP* approval, you may include the approved practice and multiplier in odor worksheet calculations in the same manner as for odor control practices listed in Chart 3 (attach *DATCP* approval to your application).

Worksheet 2 (continued)

Odor Control Practice Specifications

Odor control practices identified in Chart 3 must meet the following specifications:

Animal Housing

Diet manipulation (A1) – Limit protein in animal diet by one of the following means:

- Match nutrient supply with animal requirements.
- Formulate low–protein amino acid supplemented diets.
- Add phytase enzyme ingredients.
- Process ingredients in ways that limit protein content of processed feed.
- Use phase feeding.
- Use split sex feeding.
- Minimize feed wastage.

Bio–filter (B1) – Vent air from *animal housing areas* through a bio–filter consisting of compost and wood chips, mixed at a rate of 30:70 to 50:50 (ratio by weight of compost to wood chips). The mixture must be at least 40% moisture by weight. The bio–filter must be 10" to 18" thick, and must have an area of at least 50 to 85 sq. ft. per 1000 cu. ft. per minute (cfm) of airflow.

Vegetable oil sprinkling (B2) – Sprinkle vegetable oil on floors in *animal housing areas* (swine) each day. Apply oil at start–up rate of approximately 40 milliliters per square meter per day (mL/m^2–day) in the first 1–2 days of each production cycle. During the remainder of each production cycle, apply oil at maintenance rate of 5 mL/m^2–day. Avoid oil applications to pens near fans, to areas near heaters, and to areas surrounding feeders.

Fresh water flush (B3) – Use fresh water to flush manure from floors of *animal housing areas* into collection or *waste storage structures*. Flush at least 3 times a day, and more often if necessary, to prevent manure from drying and sticking to floors. Flush must be adequate to remove manure solids effectively.

Treated water flush (B4) – Use treated manure effluent to flush manure from floors of *animal housing areas* into collection or *waste storage structures*. Flush at least 3 times a day, and more often if necessary, to prevent manure from drying and sticking to floors. Flush with waste storage effluent treated by one of the following means:

- *Solids Separation and Reduction (see E4 below).*
- *Aeration (see F1 below).*
- *Anaerobic digestion (see E1 below).*

Air Dam (B5) – Erect and maintain a wall (typically a 10–foot x 10–foot pipe frame and tarpaulin) placed at the end of a swine–finishing building, immediately downwind of the exhaust to deflect air and odor plume. Replace material used for the barriers (tarpaulins on a frame of solid wood, for example) as needed, which may be from a few years to decades, depending on the material.

Windbreak (C1) – Maintain a solid or porous windbreak, 10 to 50 feet from the odor source, which reduces forward momentum of airflow and vertically disperses the odor plume. The length of a windbreak shall be at least half of the perimeter of the animal housing. A windbreak may be constructed of vegetation or other materials. Vegetation windbreaks must contain at least 3 rows of trees and shrubs, of both fast and slow–growing species, that are well suited for the site. Windbreaks must be designed and constructed according to *NRCS* Technical Guide Standard 380 (June, 2002).

Frequent cleaning of animal housing area (D1) – Scrape and remove manure from *animal housing areas* at least 3 times a day.

Worksheet 2 (continued)

Waste Storage Facilities

Anaerobic digestion (E1) – Subject manure to managed biological decomposition within a sealed oxygen–free container ("digester"). Anaerobic digestion must meet design and operational standards necessary to achieve adequate odor control, including requirements for solids concentration, flow rates, retention time, and minimum temperatures. Systems must meet the following:

- *Plug flow digester.* Treats manure with a total solids concentration of 8 to 14%. Must be kept in the digester for at least 20 days at a temperature of 95° to 104° F. (35° to 40° C). The digester's ratio of flow path width to fluid depth must be between 3.5:1 and 5:1.
- *Complete mix digester.* Treats manure with a total solids concentration of 2.5 to 10%. Must be kept in the digester for at least 17 days at a temperature of 95° to 104° F. (35° to 40° C.). The digester must have appropriate mixing devices to ensure complete mixing.
- *Fixed film digester.* Treats manure with a total solids concentration of not more than 5%. Must be kept in the digester for 1 to 6 days at a temperature of 59° to 99° F (15° to 39° C). Microbial support material must have at least 3–inch openings.
- *Other systems.* Use proprietary design and performance specifications that are commonly accepted and provide adequate odor mitigation.

Chemical or biological additives (E2) – Apply, to stored manure, chemical or biological additives that are scientifically proven to be effective in reducing odor from that manure when applied under applicable conditions and in applicable amounts.

Compost (E3) – Aerobically treat solid or semi–solid manure to create compost. Compost must have a carbon: nitrogen ratio of 25:1 to 40:1, and must consist of at least 40 to 60% moisture by weight. Composted material must be held at a temperature of more than 130° F. (54° C.) for more than 5 days.

Solids Separation and Reduction (E4) – Reduce the solid content of stored manure to an average of less than 2% solids through separation, multi–tiered pits or other means.

Water Treatment (E5) – Install and use a physical, chemical or biological process that removes the majority of contaminants from the waste stream, resulting in a liquid effluent meeting surface water discharge standards. The remaining solid fraction or sludge must be accounted for based on its form, and the management it is subject to.

Aeration (F1) – Use aeration equipment to maintain aerobic activity in stored manure. Aeration must maintain an average of 2 milligrams of dissolved oxygen per liter of manure stored in the upper foot of manure stored in the aerated structure between April and October.

Bio–cover (F2) – Cover the surface of waste storage structure with an 8" to 12" thick blanket of dry wheat, barley or good quality straw. The blanket must cover nearly all of the waste surface between the months of April and October. Add to the blanket as necessary (typically every 6 weeks to 4 months) to maintain the required cover.

Geotextile cover (F3) – Cover the surface of waste storage structure with a geotextile membrane that is at least 2.4 mm thick. The membrane must cover nearly all of waste surface between the months of April and October.

Impermeable cover (F4) – Cover the surface of waste storage structure with an impermeable barrier that prevents gas from escaping. Gas must be drawn off, and either treated or burned.

Natural crust (F5) – Maintain a natural crust of dry manure on the surface of stored manure. The natural crust must cover a substantial amount of the surface area of the stored manure, for most of the time between the months of April and October.

Bottom fill (F6) – Add manure to a liquid *manure storage structure* from the bottom so as to limit disturbance to the surface of the stored manure.

Windbreak (G1) – Maintain a solid or porous windbreak, 10 to 50 feet from the odor source, which reduces forward momentum of airflow and vertically disperses the odor plume. The length of a windbreak shall be at least half of the perimeter of the *waste storage facility.* A windbreak may be constructed of vegetation or other materials. Vegetation windbreaks must contain at least 3 rows of trees and shrubs, of both fast and slow–growing species, that are well suited for the site. Windbreaks must be designed and constructed according to *NRCS* Technical Guide Standard 380 (June, 2002).

Worksheet 2 (continued)

Animal Lots

Frequent cleaning of *animal lot* (H1) – Scrape and remove manure from *animal lot* surfaces at least once every 3 days. You may leave an undisturbed, compacted manure layer (1 to 2 inches thick) on the surface of unpaved *animal lots* to provide good surface sealing.

Drag *animal lot* (H2) – Drag manure in *animal lots* with harrow or disk at least once every 7 days during the months of April though October, to aerate and dry the manure.

***Animal lot* moisture control (I1)** – Prevent runoff water from flowing onto *animal lots* from roofs and other surfaces. Use diversions or roof runoff systems identified in *s. ATCP 50.70 or 50.85. Animal lots* must have a grade of at least one percent to promote drainage and drying.

Windbreak (J1) – Maintain a solid or porous windbreak, 10 to 50 feet from the odor source, which reduces forward momentum of airflow and vertically disperses the odor plume. The length of a windbreak shall be at least half of the perimeter of the *animal lot*. A windbreak may be constructed of vegetation or other materials. Vegetation windbreaks must contain at least 3 rows of trees and shrubs, of both fast and slow-growing species, that are well suited for the site. Windbreaks must be designed and constructed according to *NRCS* Technical Guide Standard 380 (June, 2002).

Arm-lwr- 11/04 January 2006

Wisconsin Department of Agriculture, Trade and Consumer Protection

2811 Agriculture Drive, PO Box 8911, Madison WI 53708-8911
Phone: (608) 224-4622 or (608) 224-4500

Worksheet 3 – Waste and Nutrient Management

Part A. Waste Generation and Storage Summary

Instructions: You must complete Parts A and B of this worksheet. If your *livestock facility* will have fewer than 500 *animal units* you may be exempt from Part C, depending on results of Part B. If Part C applies, it must be signed by a *qualified nutrient management planner* (you must also sign).

You are NOT required to complete this worksheet if you already hold a *WPDES permit* for the proposed *livestock facility* (for the same or greater number of *animal units*). Simply check the following box, sign at the bottom of this page, and include a copy of the *WPDES permit* with your application.

☐ I enclose a copy of my *WPDES permit* in place of Worksheet 3.

Specify a single livestock type (dairy, beef, swine, etc.). *Use a separate worksheet for each livestock type.*

Livestock Type: _____

Description of Storage	Column A Waste Storage Capacity (Gallons or Tons)	Column B Source of Waste (Animal Waste, Wastewater, Leachate, etc.)	Column C Average Annual Volume of Waste Produced from Each Source (Gallons or Tons)	Column D Total Average Annual Volume Waste Produced (Gallons or Tons)	Column E Storage Duration in Days (Column A divided by Column D times 365 days)
Example: Unit 1 – lagoon	*5,000,000 gallons*	*Animal waste* *Wastewater* *Leachate*	*4,000,000 gallons* *1,000,000 gallons* *2,000,000 gallons*	*7,000,000 gallons*	*260 days*
Unit 1				Exhibit 6 See Summary of Waste Production and Storage	
Unit 2					
Unit 3					

Applicant affirms that the information provided in Part A is accurate.

X _____ 11/22/17

Signature of Applicant or Authorized Representative — Date

Worksheet 3 (continued)

Arm–lwr– 11/04 January 2006

Part B – Land Base for Applying Nutrients

1. Enter total *animal units* in proposed *livestock facility* **(from worksheet 1)**: 3,483.

2. What percentage of the waste from the *livestock facility* will be:
   a. Applied to land: 100 %. Attach map showing where waste will be applied to land.
   b. Processed and sold as commercial fertilizer, under a fertilizer license: 0 %.
   c. Disposed of in other ways: 0 %. Describe ways: NA

3. Multiply the percent in line 2a by the number of *animal units* in line 1. Result (# of *animal units*): 3,483

4. Total acres of cropland currently available for land application (owned, rented, or landspreading agreement): 2,752

5. Divide # of acres in line 4 by # of *animal units* in line 3 to obtain ratio of acres to *animal units*: 0.79

6. Is the ratio in line 5 equal to or greater than the applicable ratio in Table 1? No

   If YES, and if the # of *animal units* in line 1 is less than 500, you need NOT complete Part C. Otherwise, complete Part C.

Table 1: Acreage per *Animal Unit*

Animal Type	Acres per *Animal Unit**
Dairy	1.5
Beef	1.5
Swine	1.0
Chickens/Ducks	2.5
Turkeys	5.5
Sheep/Goats	2.0

* NOTE: A *livestock facility* is NOT required to attain or exceed this ratio of acres to *animal units*. But IF your *livestock facility* will attain or exceed this ratio and will have fewer than 500 *animal units*, you need NOT complete Part C of this worksheet.

Applicant affirms that the information provided in Part B is accurate.

X Jason Parker
Signature of Applicant or Authorized Representative

11/22/17
Date

Worksheet 3 (continued)

arm-lwr- 11/04 January 2006

Part C – Nutrient Management Checklist

Instructions: All applicants must submit this checklist unless exempted under Part A or B. The checklist is based on the *NRCS* Technical Guide Nutrient Management Standard 590 (September, 2005).

County Name: Brown | Date Submitted: 11/22/17 | Township (T. 23 (N.) S.) – (R. 21 (E.) W.)

Cropland Acres: (owned, rented, or with manure spreading agreement) | Name of livestock operator submitting checklist:

Own 735 Acres, Rents 1484 Acres, Rental Agreements 533 Acres

	Yes	NA
1. Are the following field features identified on maps or aerial photos?		
a) Field location, soil survey map unit(s), field boundary, and field identification number.	✓	
b) Areas prohibited from receiving nutrient applications: Surface water, established concentrated flow channels with perennial cover, permanent non-harvested vegetative buffer, non-farmed wetlands, sinkholes, lands where established vegetation is not removed, nonmetallic mines, and fields eroding at a rate exceeding tolerable soil loss (T).	✓	
c) Areas within 50 ft of a potable drinking water well where mechanically-applied manure is prohibited.	✓	
d) Areas prohibited from receiving winter nutrient applications: Slopes > 9% (12% if contour-cropped); Surface Water Quality Management Area (SWQMA) defined as land within 1,000 ft of lakes and ponds or within 300 ft of perennial streams draining to these waters, unless manure is deposited through winter gleaning/pasturing of plant residue and not exceeding the N and P requirements of this standard.	✓	
e) Areas where winter applications are restricted unless effectively incorporated within 72 hours: Land contributing runoff within 200 ft upslope of direct conduits to groundwater such as a well, sinkhole, fractured bedrock at the surface, tile inlet, or nonmetallic mine.	✓	
f) Sites vulnerable to N leaching: Areas within 1,000 ft of a municipal well, and soils listed in Appendix 1 of the Conservation Planning Technical Note WI-1.	✓	
2. Are erosion controls implemented so the crop rotation will not exceed T on fields that receive nutrients according to the conservation plan or WI P Index model?	✓	
3. Check the methods below used to determine field soil nutrient levels:		
a) Soil samples were collected and analyzed within the last 4 years according to UW Publication A2100 recommendations.	✓	
b) For fields not meeting (a.) above, soil test phosphorus levels are assumed to be greater than 100 ppm soil test P. *	✓	
c) For fields not meeting (a.) above, preliminary estimates of soil nutrients were determined using limited soil sampling (> 5 acre per sample) but analyzed by a DATCP certified laboratory. *		✓
*For fields with soil nutrient levels determined under (b) or (c), the applicant must collect and analyze soil samples meeting the requirements of A2100 within 12 months of siting approval, and revise the nutrient management plan accordingly.		
4. Using the field's predominant soil series and realistic yield goals, are planned nutrient application rates, timing, and methods of all forms of N, P, and K listed in the plan and consistent with UW Publication A2809, *Soil Test Recommendations for Field, Vegetable and Fruit Crops*, and the 590 standard?	✓	
5. Do manure production and collection estimates correspond to the acreage needed in the plan? Are manure application rates realistic for the calibrated equipment used?	✓	
6. Is a single phosphorus (P) assessment of either the P Index or soil test P management strategy uniformly applied to all fields within a tract?	✓	
7. Are areas of concentrated flow, resulting in reoccurring gullies, planned to be protected with perennial vegetative cover?	✓	
8. Will nutrient applications on non-frozen soil within the SWQMA comply with the following?	✓	
a) Unincorporated liquid manure on unsaturated soils will be applied according to Table 1 of the 590 standard to minimize runoff.	✓	
b) One or more of the following practices will be used: 1) Install/maintain permanent vegetative buffers, or 2) Maintain greater than 30% crop residue or vegetative coverage on the surface after nutrient application, or 3) Incorporate nutrients leaving adequate residue to meet tolerable soil loss, or 4) Establish fall cover crops promptly following application.	✓	
9. Is a narrative included which describes proposed manure collection, transportation, and application methods?	✓	

I certify that the documentation supporting this checklist is complete and accurate:

Signature of *Qualified Nutrient Management Planner*, other than applicant: Kevin Becker

(qualified by 1. NAICC-CPCC, 2. ASA-CCA, 3. ASA-Professional Agronomist, 4. SSSA-Soil Scientist)


Signature of Applicant or Authorized Representative: [signature]

11P Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be 100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Win 100' (300' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

22 Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017

Municipal water in this area



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.


- Well: No Apps Win 100' (200' setback if spudper)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Asch 3 Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

Well: No Apps Win 100' (200' setback if upslope)

Wetland: No Apps Win 25'

Fall N Restriction

CAFO SWQMA-300' Incorp Zone.

CAFO SWQMA-1000' Incorp Zone.

W Soils-Verify Depth To Water B4 Apps

Bedrock-No Apps Unless Verify No Bedrock

Tile Inlet: 25' setback Incorp 100' setback Surface

Tile Outlet

Intermittent Stream

Perennial Stream

Incorp = 25' Setback
Surface = 100' Setback

Concentrated Flow-No Apps

Aschenbrenner Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Win 100' (200' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Bowe. Creek Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.


- Well: No Apps Win 100' (200' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Dairy Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

Well: No Apps Win 100' (200' setback if upslope)

Wetland: No Apps Win 25'

Fall N Restriction

CAFO SWQMA-300' Incorp Zone.

CAFO SWQMA-1000' Incorp Zone.

W Soils-Verify Depth To Water B4 Apps

Bedrock-No Apps Unless Verify No Bedrock

Tile Inlet: 25' setback Incorp 100' setback Surface

Tile Outlet

Intermittent Stream

Perennial Stream

Incorp = 25' Setback Surface = 100' Setback


Concentrated Flow-No Apps

11S1, 11S2, 11Q1, 11R1 Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Win 100' (200' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps


DL Fields Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017

Municipal water in this area



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

Well: No Apps Win 100' (200' setback if upslope)

Wetland: No Apps Win 25'

Fall N Restriction

CAFO SWQMA-300' Incorp Zone.

CAFO SWQMA-1000' Incorp Zone.

W Soils-Verify Depth To Water B4 Apps

Bedrock-No Apps Unless Verify No Bedrock

Tile Inlet: 25' setback Incorp 100' setback Surface

Tile Outlet

Intermittent Stream

Perennial Stream

Incorp = 25' Setback Surface = 100' Setback

Concentrated Flow-No Apps

Heifer Site Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

N

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be 100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Win 100' (200' setback if spetiapp)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Herold Rd Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Wells No Apps Win 100' (200' setback if spslope)
- Wetlands No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

J Kaster Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be 100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.


- Well: No Apps Win 100' (200' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

J Kaster N-Collection Pt Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Wiin 100' (200' setback if upslope)
- Wetland: No Apps Wiin 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

KB1-4 Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

N

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.


- Well: No Apps Win 100' (200' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

KB5-21 Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

Well: No Apps Win 100' (200' setback if upslope)

Wetland: No Apps Win 25'

Fall N Restriction

CAFO SWQMA-300' Incorp Zone.

CAFO SWQMA-1000' Incorp Zone.

W Soils-Verify Depth To Water B4 Apps

Bedrock-No Apps Unless Verify No Bedrock

Tile Inlet: 25' setback Incorp 100' setback Surface

Tile Outlet

Intermittent Stream

Perennial Stream

Incorp = 25' Setback Surface = 100' Setback

Concentrated Flow-No Apps

Maternoski North Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Win 100' (300' setback if applied)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Matemoski South Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Win 100' (350' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
  Incorp = 25' Setback
  Surface = 100' Setback
- Concentrated Flow-No Apps

Matzke Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be 100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Win 100' (200' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

MM Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be 100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps W/in 100' (200' setback if upslope)
- Wetland: No Apps W/in 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Silver Lane Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.


- Well: No Apps Win 100' (300' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Slag Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017 **Most of this area on Municipal water**



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Win 100' (200' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Stein Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

N

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be 100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Walk: No Apps Wlin 100' (300' setback if upslope)
- Wetland: No Apps Wlin 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Titulaer Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Win 100' (200' setback if spoilage)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Tower & W Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Win 100' (200' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Van Straten Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

Well: No Apps Win 100' (300' setback if upslope)

Wetland: No Apps Win 25'

Fall N Restriction

CAFO SWQMA-300' Incorp Zone.

CAFO SWQMA-1000' Incorp Zone.

W Soils-Verify Depth To Water B4 Apps

Bedrock-No Apps Unless Verify No Bedrock

Tile Inlet: 25' setback Incorp 100' setback Surface

Tile Outlet

Intermittent Stream

Perennial Stream

Incorp = 25' Setback Surface = 100' Setback

Concentrated Flow-No Apps

VO-10,11 Restrictions

Farm Name: Ledgeview Farms

Is this a CAFO: True

Map generated on: 12/4/2017 SnapMap Version: 16.0, Crop year: 2017



NR 243 SWQMA Option #1 When Incorporating Manure Do not apply manure within 25' of a navigable water, conduit to navigable water or within 25' of wetlands; and inject or immediately incorporate manure and process wastewater in all other areas within the SWQMA.

NR 243 SWQMA Option #5 When Surface Applying Manure Do Not apply within 100' of a navigable water or conduit to navigable water

The information on this map is not guaranteed to be100% accurate. It has been developed with the use of SNAP-Maps information, aerial imagery analysis, field knowledge and producer information. Field verification of restrictive features should be completed before applications. As new restrictive features are identified these maps will be updated.

- Well: No Apps Win 100' (200' setback if upslope)
- Wetland: No Apps Win 25'
- Fall N Restriction
- CAFO SWQMA-300' Incorp Zone.
- CAFO SWQMA-1000' Incorp Zone.
- W Soils-Verify Depth To Water B4 Apps
- Bedrock-No Apps Unless Verify No Bedrock
- Tile Inlet: 25' setback Incorp 100' setback Surface
- Tile Outlet
- Intermittent Stream
- Perennial Stream
- Incorp = 25' Setback Surface = 100' Setback
- Concentrated Flow-No Apps

Arm–lwr– 11/04 January 2006

Wisconsin Department of Agriculture, Trade and Consumer Protection
2811 Agriculture Drive, PO Box 8911, Madison WI 53708–8911
Phone: (608) 224–4622 or (608) 224–4500

Worksheet 4 – *Waste Storage Facilities*

Instructions: This worksheet must be signed by a registered professional engineer or *certified agricultural engineering practitioner.* This worksheet must identify every *waste storage facility* in the proposed *livestock facility* (including storage structures and transfer systems).

You are NOT required to complete this worksheet if you already hold a *WPDES permit* for the proposed *livestock facility* (for the same or greater number of *animal units*). Simply check the following box, sign at the bottom of this page, and include a copy of the *WPDES permit* with your application.

☐ I enclose a copy of my *WPDES permit* in place of Worksheet 4.

***New* or *Substantially Altered* Facilities:** Design specifications for the following *new* or *substantially altered waste storage facilities* comply with *NRCS* Technical Guide Standards 313 (November, 2004) and 634 (November, 2004). [Identify each facility and attach design specifications for each facility.]

Existing Facilities Retained: The following *waste storage facilities* will continue in use without being *substantially altered.* Each facility meets one of the following:

☐ The facility (list each facility _____) was constructed of concrete or steel or both, was constructed within the last 10 years according to then–existing *NRCS* technical standards, and shows no apparent signs of structural failure or significant leakage.

☒ The facility (list each facility WI WSF, T1 Piston Pump Station + Transfer System) was constructed within the last 3 years according to then–existing *NRCS* technical standards, and shows no apparent signs of structural failure or significant leakage.

☐ The facility (list each facility _____) was constructed to *NRCS* technical standards that existed at the time of construction, is in good condition and repair and shows no apparent signs of structural failure or significant leakage.

☒ The facility (list each facility W1 Collection Auger Channel + Y1 Yard Collection Basin) is in good condition and repair, shows no apparent signs of structural failure or significant leakage, and is located on a site at which the soils and separation distances to groundwater comply with *NRCS* Technical Guide Manure Storage Facility Standard 313, Table 1 (November, 2004).

☐ The facility (list each facility _____) is in good condition and repair, shows no apparent signs of structural failure or significant leakage, is located entirely above ground, and is located on a site at which the soils comply with *NRCS* Technical Guide Manure Storage Facility Standard 313, Table 5 (November, 2004).

Facilities To Be Abandoned: The following *waste storage facilities* will be closed according to a closure plan that complies with *NRCS* Technical Guide Standard 360 (June, 2001). [Attach closure plan for each facility.]

Total Storage Capacity: The *waste storage facilities* in the proposed *livestock facility* have a combined useable storage capacity of 14,775,680 gallons or tons (cannot include required "freeboard" in useable capacity). HQ 5,006,618 Proposed HS 14,749,062

Richard Seas E25248
Print Name of Engineer (include WI License No.) or *Certified Agricultural Engineering Practitioner*

Richard Seas 11/22/17
Signature of Engineer or Practitioner Date

Roach + Associates, LLC 856 N. Main St. Seymour WI 54165
Name of Firm and Address

WISCONSIN Professional Engineer's RICHARD G. SEAS E25248 Green Bay, Wis. PROFESSIONAL ENGINEER

Arm–lwr– 11/04 January 2006

Wisconsin Department of Agriculture, Trade and Consumer Protection
2811 Agriculture Drive, PO Box 8911, Madison WI 53708–8911
Phone: (608) 224–4622 or (608) 224–4500

Worksheet 5 – Runoff Management

Instructions: This worksheet must be signed by a registered professional engineer or *certified agricultural engineering practitioner* (you must also sign). Signers attest to statements in this worksheet. You are responsible for compliance.

You are NOT required to complete this worksheet if you already hold a *WPDES permit* for the proposed *livestock facility* (for the same or greater number of *animal units*). Simply check the following box, sign at the bottom of this page, and include a copy of the *WPDES permit* with your application.

☐ I enclose a copy of my *WPDES permit* in place of Worksheet 5.

Animal Lots[1]

1. ***New* or *Substantially Altered Animal Lots*:** All *new* or *substantially altered animal lots* will be constructed according to the attached design specifications that comply with *NRCS* Technical Guide Standard 635 (January, 2002). [Identify *animal lots* and attach design specifications for each *animal lot*.]

2. **Existing *Animal Lots* Near Surface Waters:** The following *animal lots* are located within 300 feet of a stream[2] or 1,000 feet of a lake. According to the *BARNY runoff model*, each of these *animal lots* has (or with minor alterations[3] will have) predicted average annual phosphorus runoff of less than 5 lbs. per year (measured at the end of the treatment area). Runoff does not discharge to any direct conduit to groundwater. [Identify *animal lots* and minor alterations if any.]

3. **Other Existing *Animal Lots*:** The following *animal lots* are NOT located within 300 feet of a stream[2] or 1,000 feet of a lake. According to the *BARNY runoff model*, each *animal lot* has (or with minor alterations[3] will have), a treatment area that reduces phosphorus runoff to an average of less than 15 lbs. per year (measured at the end of the treatment area). Runoff does not discharge to any direct conduit to groundwater. [Identify *animal lots* and minor alterations if any.] Headquarters Y1 Yard Heifer Site Y1 Yard

Feed Storage

All leachate + Runoff will be collected + stored in the W1 or W2 Waste Storage Facility

1. **General.** The operator agrees to manage feed storage to prevent significant discharge of leachate or polluted runoff to waters of the state.

2. **Existing Feed Storage (High Moisture Feed).** Existing paved areas and bunkers that may be used to store or handle high moisture feed (70% or higher moisture content) will meet the following standards:

   a) Surface water runoff will be diverted from entering the paved area or bunker. [4]

   b) Surface discharge of leachate will be collected before it leaves any paved area or bunker, if the paved area covers more than one acre. Collected leachate will be stored and disposed of in a manner that prevents discharge to waters of the state. [5]

[1] Treat multiple lots as one *animal lot* if runoff from the *animals lots* drains to the same treatment area or if runoff from the *animal lot* treatment areas converges or reaches the same surface water within 200 feet of any of those treatment areas.

[2] Indicated by a solid or dashed blue line on a 1:24,000 scale USGS topographic map.

[3] "Minor alterations" are repairs or improvements that do not result in *a substantially altered animal lot*. "Minor alterations" may include conservation practices such as runoff diversions, contouring, and planting vegetation.

[4] Runoff may be diverted by means of earthen diversions, curbs, walls, gutters, waterways or other practices, as appropriate.

[5] Use safe methods to dispose of collected leachate. For example, leachate may be transferred to *waste storage structures* and then applied to land at agronomic rates.

Ledgeview Farm, LLC
Headquarters Site – Cluster A

Y1 Concrete Yard BARNY Summary

The existing Y1 Yard provides partial containment of runoff within the yard. For full containment, additional curbs will be installed at the Y1 Yard entrances on the east and west ends.

DESIGN A BUFFER USING BARNY

Farmer: Ledgeview Farm, LLC Planner/Designer: JMR Date: 12/4/17

YARD
Headquarters Site - Cluster A

	Input	Output	
Closest City of similar climate:	2		1 Madison 2 Appleton 3 Wausau 4 Eau Claire
Paved lot area:	6,000		sq ft
Earth lot area:			sq ft
Animal Lot size:		6,000	sq ft
Is there a designed settling basin?	2		Yes= 1; No= 2
Animals on lot:	200 number		number
Type of animal:	1		(Dairy = 1;Beef=2)
Ave. Animal Weight:	350 lbs		lbs
Lot Use:	1		1= Heavy;2=Med;3= Light)

TRIBUTARY AREAS

Tributary area:		sq ft	sq ft
Runoff Curve Number:	98		← See RCN tab below for typical values
Roof Trib. area:	5,260	sq ft	

75.7 lbs P per year at downstream lot edge

Maximum P output that can be released: 15 lbs — Your choice based on impacted resources. Max is 15

Buffer Sizing by trial and error

Length:	75	ft	
Width:	125	ft	
Buffer area:		9,375 sq ft	GOOD, meets lot minimum size
Slope:		%	
c value		For c values see table below	

P Output: lb — P Output is too high; Your buffer must be larger.

BUFFER SUMMARY

Length	ft
Width	ft
Slope	%

No buffer dimensions are shown because the P output is too high.

Ledgeview Farm, LLC
Heifer Site – Cluster B

Y1 Concrete Yard BARNY Summary

The existing Y1 Yard provides partial containment of runoff within the yard. For full containment, when the proposed waste storage facility is constructed, a pipe will be added from the existing Catch Basin to the proposed waste storage facility. The pipe will provide full containment of runoff from the Y1 Yard.

DESIGN A BUFFER USING BARNY

Farmer: Ledgeview Farm, LLC Planner/Designer: JMR Date: 12/4/17

91 YARD Heifer Site - Cluster B

	Input	Output	
Closest City of similar climate:	2		1 Madison 2 Appleton 3 Wausau 4 Eau Claire
Paved lot area:	43,750	sq ft	
Earth lot area:		sq ft	
Animal Lot size:		43,750 sq ft	
Is there a designed settling basin?	1	Yes= 1; No= 2	
Animals on lot:	700 number	number	
Type of animal:	1		(Dairy = 1;Beef=2)
Ave. Animal Weight:	800 lbs	lbs	
Lot Use:	1		1= Heavy;2=Med;3= Light)

TRIBUTARY AREAS

Tributary area:		sq ft	sq ft
Runoff Curve Number:	98		← See RCN tab below for typical values
Roof Trib. area:		sq ft	

116.6 lbs P per year at downstream lot edge

Maximum P output that can be released: 15 lbs — Your choice based on impacted resources. Max is 15

Buffer Sizing by trial and error

Length:	75 ft	
Width:	125 ft	
Buffer area:	9,375 sq ft	NO GOOD, too small
	Minimum buffer size is:	65,625
Slope:	%	
c value:	For c values see table below	

P Output: lb

BUFFER SUMMARY

Length	ft
Width	ft
Slope	%

No buffer dimensions are shown because the P output is too high.

Worksheet 5 (continued)

3. ***New* or *Substantially Altered* Feed Storage Structures (High Moisture Feed):** *New* or *substantially altered* feed storage structures (buildings, silos, bunkers or paved areas) used to store or handle high moisture feed (70% or higher moisture content) will be designed, constructed and maintained to the following standards [attach design specifications]:
   a) Surface water runoff will be diverted from entering the feed storage structure.[1]
   b) Surface discharge of leachate will be collected before it leaves the feed storage structure.[2]
   c) The top of the feed storage structure floor will be at least 3 vertical feet from groundwater and bedrock.[3]
   d) Any feed storage structure with an area greater than 10,000 sq. ft. will have a subsurface drainage system to collect leachate that may leak through the structure floor. The subsurface drainage system must consist of drainfill material below the surface material, a tile drainage network designed to collect the leachate and deliver it to storage, and a subliner. The tile drainage network must, at a minimum, be installed at the perimeter of the structure only on the downgradient side(s). The sub–liner must, at a minimum, consist of one of the following:
      - Two feet of soil, either in place or installed, having a minimum of 50% fine soil particles (that pass a #200 soil sieve).
      - Two feet of soil, either in place or installed, having a minimum of 30% fine soil particles (that pass a #200 soil sieve) and a minimum PI (plasticity index) of 7.
      - A 40 mil liner of HDPE, EPDM or PVC.
      - A geosynthetic clay liner.
   e) Collected leachate will be stored and disposed of in a manner that prevents discharge to waters of the state.[2]

Nonpoint Pollution Standards

The livestock facility will be designed, constructed and maintained to do all of the following:

1. Divert runoff from contact with *animal lots*, *waste storage facilities*, paved feed storage areas or manure piles within 300 ft. of a stream or 1,000 ft. of a lake.
2. Avoid having any unconfined manure pile within 300 ft. of a stream or 1,000 ft. of a lake.
3. Prevent any overflow of *waste storage facilities*.
4. Restrict livestock access to waters of the state, as necessary to maintain adequate vegetative cover on banks adjoining the water (this does not apply to properly designed, installed and maintained livestock or farm equipment crossings).

WISCONSIN RICHARD G. SEAS E-25248 Professional Engineer Embossed Seal Green Bay, Wis. PROFESSIONAL ENGINEER

X _____ 11/22/17
Signature of Applicant or Authorized Representative — Date

Richard Seas E25248
Print Name of Engineer (include WI License No.) or Certified Practitioner

_____ 11/22/17
Signature of Engineer or Practitioner — Date

Roach + Associates, LLC 886 N. Main St, Seymour WI 54165
Name of Firm and Address

[1] Runoff may be diverted by means of earthen diversions, curbs, walls, gutters, waterways or other practices, as appropriate.

[2] Use safe methods to dispose of collected leachate. For example, leachate may be transferred to waste storage and then applied to land at agronomic rates.

[3] A tile system or curtain drain may be used to intercept lateral groundwater seepage, as necessary, to achieve the required distance to groundwater.

2

Exhibit 1
Index of Area Maps

Headquarters Site – Cluster A

Air Photo of Existing Facilities

Two Mile Radius Maps (10 Panels)
A Maps – Existing Buildings and Roads
B Maps – Property Lines, Navigable Waters and 10' Topographic Lines

2,500 Foot Radius Maps
See panels 5 and 8 of the Two Mile Radius Maps

Plat Map – Town of Ledgeview

Heifer Site – Cluster B

Air Photo of Existing Facilities
Air Photo of Proposed Facilities

Two Mile Radius Maps (10 Panels)
A Maps – Existing Buildings and Roads
B Maps – Property Lines, Navigable Waters and 10' Topographic Lines

2,500 Foot Radius Maps
See panels 5 and 8 of the Two Mile Radius Maps

Plat Map – Town of Ledgeview

Two Mile Radius Map – Clusters A & B

Because of the concentration of development within two miles of the proposed Ledgeview Farm, LLC facilities, the Two Mile Radius map is shown broken down into ten panels. Each panel is further broken down in two maps (A & B). The A maps are air photos that show existing buildings and roadways. The B maps show property lines, navigable waters and 10 foot topographic lines.

2,500 Foot Radius Map– Clusters A & B

The 2,500 Foot Radius Map is shown on the Two Mile Radius Map. The details of the 2,500 Foot Radius Map are shown on Panels 5 & 8 in the A & B maps for both Clusters.

Cluster A

Headquarters Site



DATE:	11/22/2017	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISIONS BY	DATE	DESCRIPTION OF REVISION	LEDGEVIEW FARMS, LLC 2017 WASTE STORAGE FACILITY AND LEACHATE MANAGEMENT SYSTEM BROWN COUNTY, WISCONSIN	SCALE: 1"=150'	EXISTING FACILITIES	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 1.1
DRAWN BY:	MTS	*	*	*	*	*	*					
CHECKED BY:	JMR											



		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	10/30/17	*	*	*	*	*	*
DRAWN BY:	MHP						
CHECKED BY:	JMR						

LEDGEVIEW FARM LLC
CLUSTER A–HEADQUARTERS
BROWN COUNTY, WISCONSIN

SCALE: 1"=2,250'

2 MI. PANEL REFERENCE MAP

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 1




DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC CLUSTER A–HEADQUARTERS BROWN COUNTY, WISCONSIN	SCALE: 1" = 1225'	PANEL 1A 2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS
DRAWN BY:	MHP	*	*	*	*	*	*			
CHECKED BY:	JMR									

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851


SHEET NO. 2


4
1
5
2
2 MILE RADIUS
EAST RIVER
EAST RIVER
CRYSTAL LAKE
VIVA LAKE
CTH "GV"
CTH "XX"
BELLEVUE ST
RIVER CREEK RD
DEVELOPMENT DR
VAN VIEW CT
VAN VIEW ST
MOHR CT
MOHR LN
GITTOE CT
ANGLE PATH
ANGLE TRAIL CT
CHASE AV
ALTMEYER DR
ALTMEYER TR
MEADOW LN
MEADOW DR
MEADOW RUN
MEADOW RUN TR
MEADOW RUN CT
MEADOW RUN DR
MEADOW RUN WAY
MEADOW RUN TRL
MEADOW RUN PL
MEADOW RUN LN
PHEASANT RUN TR
PHEASANT RUN DR
PHEASANT RUN WAY
PHEASANT RUN TRL
PHEASANT RUN PL
PHEASANT RUN LN
BRIDGE CREEK PL
BRIDGE CREEK DR
BRIDGE CREEK WAY
BRIDGE CREEK TRL
BRIDGE CREEK PL
BRIDGE CREEK LN
BRIDGE CREEK CT



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC CLUSTER A–HEADQUARTERS BROWN COUNTY, WISCONSIN	SCALE: 1" = 1025'	PANEL 2A 2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS	SHEET NO. 4
DRAWN BY:	MHP	*	*	*	*	*	*				
CHECKED BY:	JMR										

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DRAWN BY:	MHP	*	*	*	*	*	*
CHECKED BY:	JMR						

LEDGEVIEW FARM LLC
CLUSTER A-HEADQUARTERS
BROWN COUNTY, WISCONSIN

SCALE: 1" = 875'

PANEL 2B
2 MI. AREA MAP OF LIVESTOCK FACILITIES
PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 5



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DRAWN BY:	MHP	*	*	*	*	*	*
CHECKED BY:	JMR						


LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1" = 1250'

PANEL 3A
2 MI. AREA MAP OF LIVESTOCK FACILITIES
EXISTING BUILDINGS/ROADWAYS

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 6



		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	10/30/17	*	*	*	*	*	*
DRAWN BY:	MHP						
CHECKED BY:	JMR						

LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1" = 850'

PANEL 3B
2 MI. AREA MAP OF LIVESTOCK FACILITIES
PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES


Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 7



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC CLUSTER A–HEADQUARTERS BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							


SCALE:	PANEL 4A	Roach & Associates, LLC	SHEET NO.
1" = 875'	2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS	Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	8



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC CLUSTER A–HEADQUARTERS BROWN COUNTY, WISCONSIN	SCALE: 1" = 675'	PANEL 4B 2 MI. AREA MAP OF LIVESTOCK FACILITIES PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 9
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 625'	PANEL 5A 2 MI. AREAL MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS/ MARKED RESIDENCE AND HIGH USE BUILDINGS	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 10
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											



DATE:	10/30/17
DRAWN BY:	MHP
CHECKED BY:	JMR

REVISION DATE	BY	DESCRIPTION OF REVISION
*	*	*

REVISION DATE	BY	DESCRIPTION OF REVISION
*	*	*


LEDGEVIEW FARM LLC
CLUSTER A–HEADQUARTERS
BROWN COUNTY, WISCONSIN

SCALE: 1" = 675'

PANEL 5B
2 MI. AREA MAP OF LIVESTOCK FACILITIES
PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/
10' TOPOGRAPHIC LINES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 11



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC CLUSTER A–HEADQUARTERS BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							

SCALE:	PANEL 6A	Roach & Associates, LLC	SHEET NO.
1" = 675'	2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS	Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	12

N

3

5

6

8

9

2 MILE RADIUS

SILVER LN

DOLLAR RD

BUTCHMAN RD

CTH "NBH"

STRAWBERRY LN

BEAR CREEK

HEBER VALLEY LN

BEAR CREEK LN

GLENMORE RD

DIAMOND VIEW ESTATES

AMETHYST CT

CARNET CT

AUSTIN VALLEY CT

FASCINATION CT

FASCINATION DR

KEEPSAKE PKWY

SHADOW LN

SHADOW CT

DIAMOND RD

CTH "HH"

IH "43"

CANVAS CT

RIDGE LN

PINE GROVE RD

2647.12'

1241.59'

1319.31'

2647.97'

1250.76'

68.55'

1320.41'

2654.95'

1265.99'

54.42'

1327.53'

2652.57'

1270.63'

56.90'

1327.53'

2652.54'

1268.12'

59.41'

1314.30'

2658.31'

1355.29'

NE-NE
41.98 AC

1414.01'

NW-NW
42.28 AC

1389.34'

NE-NW
41.54 AC

1364.73'

NW-NE
40.85 AC

1314.22'

NE-NW
39.99 AC

1310.89'

NW-NE
40.03 AC

1317.54'

NE-NE
40.23 AC

1324.19'

NW-NW
39.96 AC

1321.18'

DATE:	10/30/17
DRAWN BY:	MHP
CHECKED BY:	JMR

REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
*	*	*	*	*	*


LEDGEVIEW FARM LLC
CLUSTER A–HEADQUARTERS
BROWN COUNTY, WISCONSIN

SCALE: 1" = 900'

PANEL 6B
2 MI. AREA MAP OF LIVESTOCK FACILITIES
PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES


Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 13



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC CLUSTER A–HEADQUARTERS BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							

SCALE:	PANEL 7A	Roach & Associates, LLC	SHEET NO.
1" = 1250'	2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS	Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	14



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC CLUSTER A–HEADQUARTERS BROWN COUNTY, WISCONSIN	SCALE: 1" = 675'	PANEL 7B 2 MI. AREA MAP OF LIVESTOCK FACILITIES PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHI LINES	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920–833–6340 Fax: 920–833–9851	SHEET NO. 15
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											



		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	10/30/17	*	*	*	*	*	*
DRAWN BY:	MHP						
CHECKED BY:	JMR						


LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1" = 825'

PANEL 8A
2 MI. AREA MAP OF LIVESTOCK FACILITIES
EXISTING BUILDINGS/ROADWAYS/
MARKED RESIDENCE AND HIGH USE BUILDINGS

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 16



DATE:	10/30/17
DRAWN BY:	MHP
CHECKED BY:	JMR

REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
*	*	*	*	*	*

LEDGEVIEW FARM LLC
CLUSTER A–HEADQUARTERS
BROWN COUNTY, WISCONSIN

SCALE: 1" = 900'

PANEL 8B
2 MI. AREA MAP OF LIVESTOCK FACILITIES
PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 17



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DRAWN BY:	MHP	*	*	*	*	*	*
CHECKED BY:	JMR						


LEDGEVIEW FARM LLC
CLUSTER A–HEADQUARTERS
BROWN COUNTY, WISCONSIN

SCALE: 1" = 1250'

PANEL 9A
2 MI. AREA MAP OF LIVESTOCK FACILITIES
EXISTING BUILDINGS/ROADWAYS

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 18


5
6
9
10
2 MILE RADIUS
N
SILVER LN
DOLLAR RD
HEADOV PARK DR
VALLEY HEIGHTS DR
CONTINENTAL DR
DON GERARD VY
GEMINI RD
VAIL CT
KLONDIKE RD
CAPRICORN RD
ADAMUS RD
VIRGO RD
LUCERNE DR
WILTSHIRE CT
NOTTINGHAM CT
DAWSON LN
PISCES LN
LAUREL LN
SUNSET DR
EMERALD DR
VARN SPRINGS CT
RED LODGE CT
CRYSTAL SPRINGS DR
CRYSTAL SPRINGS CT
ONTARIO RD
ALTAIR ST
SPICA LN
SAVANNA WY
SAGEBRUSH WY
WHEAT VY
AURORA LN
GEMSTONE TR
HIDDEN VALLEY LN
HIDDEN VALLEY CT
GALLIE CT
GLENMORE RD
AUSTIN VALLEY CT
MAPLE RIDGE CT
DAYBROOK CT
DAYBROOK DR
OAK LN
BIG CREEK RD
MAPLE RIDGE RD
MATTHIAS RD
STRAUBERT LN
CLOVERS RD
HERMAN RD
OLIVER RD
GLENDALE RD
MAIN ST
MAIN ST HWY 41
HWY 41
CTH "HH"
CTH "VV"
CTH "GV"
CTH "GV" HWY 41
CTH "GV" MAIN ST
CTH "GV" MATTHIAS RD
CTH "GV" OLIVER RD
CTH "GV" GLENDALE RD
CTH "GV" HERMAN RD
CTH "GV" CLOVERS RD
CTH "GV" BIG CREEK RD
CTH "GV" MAPLE RIDGE RD
CTH "GV" DAYBROOK DR
CTH "GV" OAK LN
CTH "GV" HEADOV PARK DR
CTH "GV" VALLEY HEIGHTS DR
CTH "GV" CONTINENTAL DR
CTH "GV" DON GERARD VY
CTH "GV" GEMINI RD
CTH "GV" KLONDIKE RD
CTH "GV" CAPRICORN RD
CTH "GV" ADAMUS RD
CTH "GV" VIRGO RD
CTH "GV" LUCERNE DR
CTH "GV" NOTTINGHAM CT
CTH "GV" PISCES LN
CTH "GV" LAUREL LN
CTH "GV" DAWSON LN
CTH "GV" SUNSET DR
CTH "GV" EMERALD DR
CTH "GV" VARN SPRINGS CT
CTH "GV" RED LODGE CT
CTH "GV" CRYSTAL SPRINGS DR
CTH "GV" CRYSTAL SPRINGS CT
CTH "GV" ONTARIO RD
CTH "GV" ALTAIR ST
CTH "GV" SPICA LN
CTH "GV" SAVANNA WY
CTH "GV" SAGEBRUSH WY
CTH "GV" WHEAT VY
CTH "GV" AURORA LN
CTH "GV" GLENMORE RD
CTH "GV" HIDDEN VALLEY LN
CTH "GV" AUSTIN VALLEY CT
CTH "GV" GALLIE CT
CTH "GV" GEMSTONE TR
CTH "GV" STRAUBERT LN
CTH "GV" MAPLE RIDGE CT
CTH "GV" HERMAN RD
CTH "GV" OLIVER RD
CTH "GV" GLENDALE RD
CTH "GV" MAIN ST
CTH "GV" HWY 41
CTH "GV" MATTHIAS RD
CTH "GV" CLOVERS RD
CTH "GV" BIG CREEK



DATE:	10/30/17
DRAWN BY:	MHP
CHECKED BY:	JMR

REVISION DATE	BY	DESCRIPTION OF REVISION
*	*	*

REVISION DATE	BY	DESCRIPTION OF REVISION
*	*	*

LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1" = 800'

PANEL 10A
2 MI. AREA MAP OF LIVESTOCK FACILITIES
EXISTING BUILDINGS/ROADWAYS

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 20



DATE:	10/30/17
DRAWN BY:	MHP
CHECKED BY:	JMR

REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
*	*	*	*	*	*


LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1" = 800'

PANEL 10A
2 MI. AREA MAP OF LIVESTOCK FACILITIES
EXISTING BUILDINGS/ROADWAYS

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 20




DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 675'	PANEL 10B 2 MI. AREA MAP OF LIVESTOCK FACILITIES PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 21
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											

©2006
Brown
County
Wisconsin

T23N R21E (SW)

Ledgeview & Bellevue(SW)



0 2,640 5,280
Feet

"The acreages shown on this map are based on the latest and most accurate parcel mapping which may differ slightly from the acreages shown on the tax roll.

For more detailed or up-to-date maps please visit us online at:
www.gis.co.brown.wi.us

Map Legend

- Property Boundaries (with acreages**)
- Municipal Boundaries
- Interstate, U.S or State Highway
- County Highway
- Other Road or Street
- Railroads
- Lakes, Ponds, & Rivers
- Trails
- Woodlands/Natural Areas
- Address Grid numbering
- Section or other PLSS line
- Section numbers

15

Copyright 2006 Brown County
Planning & Land Services
Aug 01, 2006

Cluster B

Heifers Site


Exhibit 1.1A

N

Ledgeview Farms, LLC

Heifer Farm-Current Facilities





DATE:	11/22/2017	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISIONS BY	DATE	DESCRIPTION OF REVISION	
DRAWN BY:	MTS	*	*	*	*	*	*	
CHECKED BY:	JMR							

LEDGEVIEW FARMS, LLC
2017 WASTE STORAGE FACILITY AND LEACHATE MANAGEMENT SYSTEM
BROWN COUNTY, WISCONSIN

SCALE: 1"=250'

PROPOSED FACILITIES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 1.1B



		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	10/30/17	*	*	*	*	*	*
DRAWN BY:	MHP						
CHECKED BY:	JMR						

LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1"=2,250'

2 MI. PANEL REFERENCE MAP


Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 1



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							

SCALE:	PANEL 1A	Roach & Associates, LLC	SHEET NO.
1" = 1225'	2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS	Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	2



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							


SCALE: 1" = 800'

PANEL 1B


2 MI. AREA MAP OF LIVESTOCK FACILITIES
PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 3



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 1025'	PANEL 2A 2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 4
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							

SCALE: 1" = 875'

PANEL 2B
2 MI. AREA MAP OF LIVESTOCK FACILITIES
PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES


Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 5



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							

SCALE:	PANEL 3A	Roach & Associates, LLC	SHEET NO.
1" = 1250'	2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS	Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	6



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							

SCALE: 1" = 850'

PANEL 3B

2 MI. AREA MAP OF LIVESTOCK FACILITIES
PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 7



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 875'	PANEL 4A 2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 8
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											

N

1

2 MILE RADIUS

4

5

7

8

LAWTON & SEYMOR SUBD OF [illegible], ESFR

EAST RIVER

CTH "O"

HOWE RD

BOWER CREEK ESTATES SOUTH

BOWER CREEK ESTATES NORTH

KETTLE CREEK SUBD 1ST ADDN

KETTLE CREEK SUBD 2ND ADDN

KETTLE CREEK CT

RIDGE HAVEN CT

RIDGE HAVEN ESTATES

RIVER'S EDGE

RIVER'S EDGE 1ST ADDN

AVA HOPE CT

OLDE SCHOOL SQUARE CONDOMINIUM

DICKINSON RD

LEDGEVIEW COMMERCIAL PARK

BELLE ISLE MEADOWS

DICKINSON HEIGHTS

ANGELS PATH

DALLAS LN

DOLLAR RD

THE CROSSING AT DOLLAR CREEK

NORTHERN EDGE ESTATES

EDGECREST

A COUNTY PLAT

NDING WATERS

MYSTERY VALLEY

MYSTERY VALLEY 1ST ADDN

BRENTWOOD

CONDOMINIUMS

MYSTERY VALLEY

WHITNEY'S SUBD OF [illegible]

DARSTY CT

DATE:	10/30/17
DRAWN BY:	MHP
CHECKED BY:	JMR

REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
*	*	*	*	*	*

LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1" = 675'

PANEL 4B

2 MI. AREA MAP OF LIVESTOCK FACILITIES PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851


SHEET NO. 9



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 625'	PANEL 5A 2 MI. AREAL MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS/ MARKED RESIDENCE AND HIGH USE BUILDINGS	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 10
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											




DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 675'	PANEL 5B 2 MI. AREA MAP OF LIVESTOCK FACILITIES PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/ 10' TOPOGRAPHIC LINES	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 11
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							

SCALE:	PANEL 6A	Roach & Associates, LLC	SHEET NO.
1" = 675'	2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS	Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	12



DATE:	10/30/17
DRAWN BY:	MHP
CHECKED BY:	JMR

REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
*	*	*	*	*	*


LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1" = 900'

PANEL 6B
2 MI. AREA MAP OF LIVESTOCK FACILITIES
PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 13



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							


SCALE: 1" = 1250'

PANEL 7A


2 MI. AREA MAP OF LIVESTOCK FACILITIES
EXISTING BUILDINGS/ROADWAYS

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851


SHEET NO. 14



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 675'	PANEL 78 2 MI. AREA MAP OF LIVESTOCK FACILITIES PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHI LINES	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 15
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 825'	PANEL 8A 2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS/ MARKED RESIDENCE AND HIGH USE BUILDINGS	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 16
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							


LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1" = 850'

PANEL 8B
2 MI. AREA MAP OF LIVESTOCK FACILITIES PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/ 10' TOPOGRAPHIC LINES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 17




DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							

SCALE: 1" = 675'

PANEL 9A
2 MI. AREA MAP OF LIVESTOCK FACILITIES
EXISTING BUILDINGS/ROADWAYS

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 18



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN
DRAWN BY:	MHP	*	*	*	*	*	*	
CHECKED BY:	JMR							


SCALE: 1" = 675'

PANEL 9B


2 MI. AREA MAP OF LIVESTOCK FACILITIES PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 19



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 800'	PANEL 10A 2 MI. AREA MAP OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 20
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEIFER FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 675'	PANEL 10B 2 MI. AREA MAP OF LIVESTOCK FACILITIES PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/10'TOPOGRAPHIC LINES	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 21
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											



		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	10/30/17	*	*	*	*	*	*
DRAWN BY:	MHP						
CHECKED BY:	JMR						

LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1"=2,250'

2 MI. PANEL REFERENCE MAP


Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 1

©2006
Brown
County
Wisconsin

T23N R21E (SW)

Ledgeview & Bellevue(SW)


See Page 17
See Page 12
See Page 16
See Page 7
David J Van Rite
Village of Bellevue
Hs Realty Partnership LLP
Hs Realty
Harold Peeters Jr Etal
David L Swagel
Louanne Kuzmic
Diana K Ferry
Timothy J & deanne M Mckenna
Titulaer Mary V Revocable Trust
Dickinson Development LLC
Mark A & Julie Ann Giardino
Daniel L & Dennis R Mcallister Etal
Leanna Family Ltd Partnership
Ledgeview Facility LLC
Edmund J Gersek
Michael G & Susan M Tesar
Green Bay Country Club Inc
Garot Land Development LLC
Sandra M Arendt
Marion V Coates
Diane L Layman
Kenneth & Dolores Matzke
SCI Properties
Kolb
Joseph J Charles
Vernon A Den Bus
Roy & Glen Pansier
Steven & Cheryl Corrigan & Donald W Corrigan
Josephine Grohusky
Bernard Van Straten 43
Donald Van Straten
Wm C & Muriel J
Daanen &
Roy
David A
Village of Bellevue
Town of Ledgeview
Town of Glenmore
Town Of Ledgeview
Schlag
Village of Bellevue
Green Bay Country Club Inc
Michael G & Susan M Tesar
Garot Land Development LLC
Edmund J Gersek
Ledgeview Facility LLC
Sandra M Arendt
Marion V Coates
Diane L Layman
Kenneth & Dolores Matzke
Leanna Family Ltd Partnership
Dickinson Development LLC
Timothy J & deanne M Mckenna
Titulaer Mary V Revocable Trust
Mark A & Julie Ann Giardino
Daniel L & Dennis R Mcallister Etal
SCI Properties
Kolb
Joseph J Charles
Vernon A Den Bus
Roy & Glen Pansier
Steven & Cheryl Corrigan & Donald W Corrigan
Josephine Grohusky
Bernard Van Straten 43
Donald Van Straten
Harold Peeters Jr Etal
David L Swagel
Louanne Kuzmic
Diana K Ferry
Hs Realty Partnership LLP
Hs Realty
David J Van Rite
Village of Bellevue
Green Bay Country Club Inc
Michael G & Susan M Tesar
Garot Land Development LLC
Sandra M Arendt
Marion V Coates
Diane L Layman
Kenneth & Dolores Matzke
Edmund J Gersek
Ledgeview Facility LLC
Leanna Family Ltd Partnership
Timothy J & deanne M Mckenna
Titulaer Mary V Revocable Trust
Dickinson Development LLC


3

Cluster A

Headquarters Site



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEADQUARTERS BROWN COUNTY, WISCONSIN	SCALE: 1" = 350'	SITE MAP 1 OF LIVESTOCK FACILITIES EXISTING BUILDINGS/ROADWAYS	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 22
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION	LEDGEVIEW FARM LLC HEADQUARTERS BROWN COUNTY, WISCONSIN	SCALE: 1" = 350'	SITE MAP 2 OF LIVESTOCK FACILITIES PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/ KARST FEATURES/ 2' TOPOGRAPHIC LINES	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 23
DRAWN BY:	MHP	*	*	*	*	*	*					
CHECKED BY:	JMR											

Cluster B

Heifers Site



DATE:	10/30/17
DRAWN BY:	MHP
CHECKED BY:	JMR

REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
*	*	*	*	*	*


LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1" = 350'

SITE MAP 1 OF LIVESTOCK FACILITIES
EXISTING BUILDINGS/ROADWAYS

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 22



DATE:	10/30/17	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DRAWN BY:	MHP	*	*	*	*	*	*
CHECKED BY:	JMR						

LEDGEVIEW FARM LLC
HEIFER FACILITY
BROWN COUNTY, WISCONSIN

SCALE: 1" = 350'

SITE MAP 2 OF LIVESTOCK FACILITIES
PROPERTY LINES/ROADWAYS/NAVIGABLE WATERS/ KARST FEATURES/ 2' TOPOGRAPHIC LINES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 23

4

Employee Training Plan
Ledgeview Farm, LLC

Table of Contents

	Page
Training Goals, Objectives, Activities	1
Requirements, Standards, Procedures and Practices	1
Training Content	
Employee / Work Place Safety	2
Environmental Incident Response	2
Nutrient Management	2
Manure and Waste Handling	2
Runoff Management	3
Odor Management	3
Employees to be Trained	3
Frequency and Form of Training	4
Training Presenters	4
Record Keeping	4
Employee Training Log	5

Goals

This Training Plan will enable employees and others to follow standards, procedures and protocols to ensure that Ledgeview Farm, LLC (LF) meets all Livestock Facility Siting Permit requirements as well as other goals of the business.

An employee-training plan is required as part of the local permit issued in accordance with Wis. Admin. Code ATCP 51, Livestock Facility Siting. The Training Plan for Ledgeview Farm, LLC, includes the following:

- Training on: nutrient management, odor management, runoff management, manure and waste handling, employee safety, and emergency response
- Employees to be trained
- Frequency of training
- Training presenters (these may include *livestock facility managers*, consultants or professional educators)
- A system for taking and recording attendance

Objectives

Those in attendance will learn and understand to follow all standards, procedures and practices related to their assigned duties and tasks.

1. Understand basic permit requirements including more stringent local standards, and follow specific standards, procedures and practices to ensure compliance with these permits.
2. Receive current, science-based information to most effectively address key management issues, with specific focus on nutrient management, odor management, runoff management, manure and waste handling, employee safety, and environmental incident response.
3. Provide feedback concerning future training needs, and participate in the design of annual training activities.

Training Activities

Training activities will be designed to provide the necessary knowledge and skills tailored to specific needs of employees and others. Training approaches will be selected to ensure that information is effectively communicated, and will include classroom sessions, individual reading assignments and field exercises. Annual training activities will be customized to reflect changes in requirements, equipment, standards, procedures or practices; accommodate specific training needs; or provide new information critical to the sound management of LF.

Requirements, Standards, Procedures and Practices

Employees and others will be provided training on the requirements of the local siting permit requirements as they relate to their assigned duties and tasks. They will learn the applicable standards as well as the procedures and practices to ensure compliance with permit requirements. They also will learn other standards, procedures and practices that apply to LF as required by this training plan.

Training will cover the use of checklists and other tools used to inspect and monitor farm operations.

Ledgeview Farm, LLC will explain the Livestock Facility Siting Permit and reporting requirements.

Training Content

Employee Safety
Standards, procedures and practices are in place to ensure the health and safety of employees and visitors to LF.

Training will include:

- Proper animal handling
- Proper equipment operations and certification where needed
- Accident reporting protocols
- Working in confined spaces requirements
- Avoidance of dangerous conditions (including exposure to noxious gases)
- Maintaining fences, grates and other safety equipment

Environmental Incident Response
Standards, procedures and practices are in place to ensure proper responses in the event of manure spill or other incident. A written document with response procedures and emergency contacts is readily available at the farm office.

Training will include:

- Review of emergency response plan
- Spill reporting and clean up procedures

Nutrient Management
Standards, procedures and practices are in place for all forms of manure application and must be followed by all employees, consultants and others contracted for manure application. LF Nutrient Management Plan is reviewed semi-annually by LF and their agronomist (Kevin Beckard). A copy of the plan is readily available at the farm office.

Training will include:

- Conservation plan crop rotation and tillage requirements
- Record keeping requirements – spreading logs and inspection sheets
- Recording and analyzing manure sample data
- Review soil fertility, crop rotations and yields
- Understanding manure spreading restriction maps and setback areas

Manure and Waste Handling
Standards, procedures and practices are in place to ensure proper storage, transfer and land application of manure and wastewater.

Training will include:

- Review operations and maintenance procedures for manure storage facilities, waste transfer systems and manure application equipment.
- Identification and use of proper agitation points
- Routine maintenance of equipment
- Review procedures for pump operation, hose placement and pickup, equipment cleanup
- Proper procedures for hauling and applying manure
- Record keeping requirements – inspection reports
- Safety procedures as they relate to manure and waste handling

Runoff Management

Procedures and practices are in place to control storm water runoff from the farm sites, and must be followed by all employees, contractors and visitors.

Training will include:

- Maintenance requirements of storm water system – clearing of gutters, diversions, drains and sediment basins.
- Proper feed bunker tire and plastic placement and removal
- Leachate collection system operation, including pump operation and maintenance as well as the transfer channel.
- Cleaning of traffic areas and pads
- Maintenance (e.g. regarding, seeding) and mowing of filter strips and other grassed areas.

Odor Management

Some basic procedures and practices are in place to minimize odor, and must be followed by all employees and contractors.

Training will include:

- Overview of issues associated with odors
- Review of LF odor management plan and complaint protocol
- Cleaning and maintenance procedures to control odor from the site
- Land application procedures to reduce odors
- Responding to odor complaints

Employees to Be Trained

- Managers
- Herdsman
- Assistant Herdsman
- Feeders
- Milkers
- Manure Handlers

Form and Frequency of Training

At a minimum, training will be provided annually to all employees of LF. Training may be provided through a variety of employee meetings at the farm as well as conferences

sponsored by professional organizations such as the Professional Dairy Producers of Wisconsin, The Dairy Business Association, Professional Nutrient Applicator Association of Wisconsin and other training opportunities sponsored by UW Extension. All of the procedures and protocols for each position will be located in the farm office.

Training Presenters

Presenters will include:

- Farm Managers
- Consultants
- Agronomy Professionals
- University of Wisconsin Extension
- Government Agency staff
- Professional Associations

Recording Attendance

Ledgeview Farm, LLC employees approximately 12 full and part time employees. For all training sessions, employee attendance will be recorded using a sign-up sheet that will include the date of the training and the employees who attended. Similar methods will be used to verify other training received at local meetings and conferences.

Ledgeview Farm, LLC.: Employee Training Log

Date Trained	Employee	Proper Operation & Maintenance of Equipment	Understanding & Interpretation of Field Maps	Explanation Of Wetlands & Waterways	Regulatory Requirements	Review of Wetlands & Waterways on Field Maps	Explanation & Review of Setbacks	Reasons for Setbacks	Applicable Setbacks	Review of Setbacks on Field Maps	How to Reduce Road Dirt	Explanation of Emergency Response Plan	Record Keeping	Importance & Purpose of Record Keeping	Calibration of Application Equipment	Manure Application	Employee Signature

5

Emergency Response Contacts Summary

Farm Name: Ledgeview Farm, LLC

Owner/Operator: Jason Pansier Phone: (920) 655-3875 Cell: _____

Owner/Operator: _____ Phone: _____ Cell: _____

Farm Address: 3499 Lime Kiln Road Green Bay WI 54311

Farm Location: T23N R21E Section 28 County: Brown

Driving Directions or Emergency Coordinates: From the Town of Ledgeview Municipal Building drive East 0.7 miles along Dickinson Rd and make a left turn on Lime Kiln Rd, head North 0.8 miles to the farm.

In Case of Injury, Fire, or Rescue Emergency, Immediately Implement the Following:

1. Assess the condition of the victim, extent of the emergency (fire, rescue) and call for help.
2. Stabilize the victim, use on-site rescue equipment, evacuate buildings, or begin fire suppression as necessary.
3. Brief emergency responders upon arrival on current status of situation.

In Case of a Spill, Leak, or Failure at the Storage Facility, During Transport, or Land Application, Immediately Implement the Following:

1. Stop the source of the leak or spill.
2. Make appropriate calls for people, equipment, and materials. See contacts below.
   - Notify DNR spill hotline: 1-800-943-0003 (Spill reporting is mandatory by state law.)
   - Call sheriff's office if spilled on public roads or its right-of-ways for traffic control.
   - Clear the road and roadside of spilled material immediately.
3. Contain the spill
4. Prevent spillage from entering surface waters, tile intakes, or waterways.
5. Begin cleanup and land apply on approved cropland at appropriate rates.
6. Document your actions.

Emergency Contacts	Contact Person (or Company)	Phone Number
Fire/Rescue	Ledgeview Fire Department	911 or 920-336-3360
County Sheriff	Brown County Sheriff's Department	911 or 920-448-4200
Farm Emergency Coordinator	Jason Pansier	920-655-3875
DNR Hazardous Spill Line		1-800-943-0003
DNR Permit Contact/Warden	Heidi Schmitt-Marquez	
Veterinarian	Ken Foust	920-336-7233
Equipment/Supplies	**Contact Person (or Company)**	**Phone Number**
On-Farm Equipment Operator	Glenn Pansier	920-655-0416
Excavation Contractor	Olson Excavation	920-621-7882
Manure Hauler	Schneider Manure Hauling	920-374-1327
Septic Tank Pumping Truck	Kiekhaefer Septic Service	920-864-7025
Mortality Disposal Contractor	Circle R Mink Ranch	920-434-0218
Local Government Contacts	**Contact Person**	**Phone Number**
Town Chairman Town of Ledgeview	Phil Danen	920-336-3360
LCD County Conservationist	Dave Wettencamp	920-391-4639
NRCS District Conservationist	John Malvitz	920-884-3910

Be prepared to provide the following information:

- Your name and contact information
- Farm address, location and other pertinent identification information.
- Nature of emergency (employee injury, fire, discharge of manure or hazardous materials).
- Emergency equipment and personnel that are needed.
- Potential for manure or hazardous materials to reach surface waters or major field drains.
- Current status of containment efforts.
- Location of hazardous/flammable materials, and fire suppression equipment
- Location of emergency cutoff switches or valves.

Ledgeview Farm, LLC.
Environmental Incident and Emergency Response Plan

Reporting Emergencies

When there is a fire or other emergency that poses immediate danger to people, livestock, property or the environment call the appropriate telephone number listed for the emergency. Follow emergency evacuation procedures. Remain calm, notify others, and respond to the emergency as appropriate. Procedures for responding to specific types of emergencies are described below.

When you call 911 to report an emergency, provide the emergency dispatcher with the following information:

- Your Location
- Building or area name where the emergency response is required
- The location within building or area
- A brief description of emergency
- Your name

Unless there is a risk to your safety, remain on the line until told by the emergency dispatcher to hang up.

Manure Spills

Manure Storage Leak Overflow or Spill

- Stop flow from the manure storage facility.
- Assess the extent of the emergency and determine the help needed.
- Call for the needed help or equipment.
- Contain the spill immediately through the use of basins and berms.
- Divert manure from critical sites including: wells, channels, ditches, waterways, streams, rivers, lakes, ponds, tile inlets, broken tile lines, sinkholes, and bedrock near the surface.
- Repair storage facility immediately
- If field conditions allow, remove enough manure to stop the leak.
- Contact the County Land Conservation Department to make critical repairs.
- Following repairs, clean up the spill where possible.
- Take before and after (clean-up) pictures.
- Report the spill to the WDNR.
- Complete a spill worksheet

Manure spills during or after transport and application

- Stop manure pumps.
- If the manure is coming from a tanker move away from critical areas. If possible take to cropland.
- Close valves or separate pipes to stop the flow of manure.

- Assess the extent of the emergency and determine the help needed.
- Call for the needed help or equipment.
- If spill is on the road call the County Sheriff's office for traffic control
- Clean up the spill on roads immediately by spreading sawdust to absorb the manure and sweeping into piles. Remove piles and apply to cropland according to the 590 NMP.
- Contain the spill immediately through the use of basins and berms, straw bales or sawdust.
- If the flow is coming from a tile line plug or break the tile line to stop the flow.
- Stop the flow through incorporation where possible.
- Take before and after (clean-up) pictures.
- Report the spill to the WDNR.
- Complete a spill worksheet

Chemical Spills

The guidelines below should be followed in the event of a chemical incident in which there is potential for a significant release of hazardous materials.

Spill classifications: Spill response procedures vary depending on whether a spill is small, medium, or large. The following are descriptions of each type of spill:

- **Small spills.** This category includes spills where the major dimension of the spill is less than 18 inches in diameter.
- **Medium spills.** These are spills where the major dimension exceeds 18 inches, but is less than 6 feet.
- **Large spills.** This category includes:
    - Any spill involving a flammable liquid where the major dimension exceeds 6 feet in diameter; and
    - Any "running" spill, where the source of the spill has not been contained or the flow has not been stopped.

Evacuation: Persons in the immediate vicinity of a spill should immediately evacuate the premises. If the spill is "medium" or "large," or if the spill seems hazardous, immediately notify emergency response personnel.

General spill control techniques: Once a spill has occurred, the employees at the spill site must decide whether the spill is small enough to handle without outside assistance. Only employees with training in spill response should attempt to contain or clean up a spill.

Spill control equipment should be available wherever significant quantities of hazardous materials are received or stored. MSDS sheets, respiratory protection, absorbents, over-pack containers, container patch kits, spill dams, shovels, floor dry, acid/base neutralizers and "caution-keep out" signs are common spill response items

that should be stocked in such areas. Consult the Safety Department for more information on what to stock for your area.

Response and cleanup procedures for small spills: Small spills generally can be handled by internal personnel and usually do not require an emergency response by fire department HAZMAT personnel.

First, quickly contain the spill by stopping or securing the spill source. This could be as simple as uprighting a container and using absorbent pads to soak up spilled material. Wear gloves and protective clothing, if necessary. Put spill material and absorbents in secure containers. Do not wash the spill area until consulting with the MSDS sheet for spill and waste disposal procedures. Sometimes the area of the spill should not be washed with water. The spilled material and the absorbent sometimes might be classified as hazardous waste and must be disposed of in compliance with state and federal environmental regulations.

Response and cleanup procedures for medium spills: Police and fire department HAZMAT teams' response normally is required for medium spills. However, common sense also should be used when determining if outside help is necessary. Medium spills require the following actions:

- First, try to contain the spill at its source. This might involve quickly uprighting a container or putting a lid on a container. Do not use absorbents unless they are immediately available. Once you have made a quick attempt to contain the spill, leave the area. Call management or 911. Close, but do not lock, the doors as you leave.
- Second, evaluate the area outside of the spill. Engines and electrical equipment near the spill area must be turned off. This eliminates various sources of ignition in the area. Advise police or emergency responders on how to turn off engines or electrical sources. Do not go back into the spill area once you have left. Help emergency responders by trying to determine how to shut off heating, air conditioning equipment, or air circulating equipment, if necessary.
- If emergency responders evacuate the spill area, follow their instructions in leaving the area.
- After emergency responders have contained the spill, be prepared to assist them with any other information that may be necessary, such as MSDS sheets and questions about the facility.
- Emergency responders or trained personnel with proper personal protective equipment should clean up the spill residue. Do not re-enter the area until the responder in charge gives the all clear. Be prepared to assist these persons from outside the spill area with MSDS sheets, absorbents, containers, etc.
- Reports must be filed with proper authorities.

Response and cleanup procedures for large spills: The response for large spills is much the same as for medium spills, except that the exposure danger is greater. The response for large spills is as follows:

- First, since spill control or containment by management or on farm staff notify police (911). Again, give the operator the spill location, chemical spilled and approximate amount.
- Second, from a safe area, attempt to get MSDS information for the spilled chemical for the emergency responders to use. Also, be prepared to advise responders as to any ignition sources, engines, electrical power, or air conditioning/ventilation systems that may need to be shut off. Advise responders of any absorbents, containers, or spill control equipment that may be available.
- Only emergency response personnel, in accordance with their own established procedures, should handle spills greater than 6 feet in any dimension or that are continuous. Remember, once the emergency responders or HAZMAT team is on the job cleaning up spills or putting out fires, the area is under their control and no one may re-enter the area until the responder in charge gives the all clear.

Accidental Entry In To Manure Storage Enclosure Emergency

- If the person is still conscious attempt to get them out, but **DO NOT ENTER** the manure storage.
- Get additional help from farm staff to remove the person.
- If unable to remove the person, call for emergency help.
- Pump fresh air into the enclosure with fans or blowers until help arrives.
- Make repairs or install safety equipment to prevent further entry.
- Complete an emergency worksheet with events and corrective action to prevent the event from occurring in the future.

Disposal of Animal Carcasses in Emergency Circumstances

The disposal options for dead animals in emergency circumstances are as follows (in order of preference):

1. Rendering plant
2. Licensed landfill
3. Burial on farmland
4. Composting of carcasses (DNR approval required)

If the dead animals are buried on farmlands, every attempt should be made to bury the animals in an upland area away from surface water bodies and above the groundwater table to minimize the potential for contaminating the water. Disposal pits or trenches should be a minimum of 1,200 feet away from private or public water supply wells and 1,000 feet away from surface waters and other sensitive areas.

The carcasses should be buried in pits or trenches (usually easier for placement) that allow for at least 2 feet of soil cover over top of the carcasses. The carcasses should be placed in a single layer in the bottom of the pit/trench and then covered with barn lime and the 2 foot soil layer. This should help the decomposition of the carcasses and keep other animals from digging them back up. The cover soil should be sloped to divert

surface water away from the burial area and top soiled, seeded, and fertilized as soon as possible to maintain a healthy vegetative cover.

This guidance generally conforms to DATCP rules and policies. If there are any questions regarding the DATCP regulations or policies, please contact DATCP staff directly at (608) 224-4872.

Odor Complaint Response

Public relations, especially with neighbors, are an essential component of managing a large dairy business today. Ledgeview Farm, LLC will implement the following protocols to address odor concerns and reduce community conflicts.

1) The goal of Ledgeview Farm, LLC is to establish a relationship with neighbors and community members and implement management practices that limit complaints due to odors. Ledgeview Dairy, LLC will make every effort to inform neighbors before activities are undertaken that may increase odors from the dairy.

2) Ledgeview Farm, LLC has designated Jason Pansier as the lead contact for all odor complaints. All odor complaints will be recorded on the "Record of Odor Complaints Form" at the end of this plan. This form records the date the complaint was received as well as who made the complaint and what concerns were expressed.

3) Ledgeview Farm, LLC will evaluate all odor complaints to determine if any practices can be implemented immediately to help reduce the odors that have generated the complaint. Potential odor control strategies to be implemented are identified in this plan.

4) Ledgeview Farm, LLC will follow up odor complaints to determine if the practices put in place helped to reduce odors after complaints have been received.

Ledgeview Farm, LLC
Manure or Hazardous Material Spill Accident Worksheet

Jason Pansier Manager/Owner
3499 Lime Kiln Road
Green Bay, WI 541311

Jason Pansier Cell – 920-655-3875

DNR Hazardous Spill Line 1-800-943-0003

Picture Information – Provide pictures of spill site: before cleanup ☐ after cleanup ☐

Spill Information

Date and time of the spill: _____

Spill Location: _____

_____

Where Spill Material was Ultimately Deposited: _____

_____

Property Owners Name: _____

Individuals Involved: _____

Material Spilled: _____

Quantity of Spill: _____

Actions Taken to Stop the Release or Minimize the Impact: _____

_____

_____

_____

_____

Potential Impact to Human Health and the Environment: _____

_____

_____

"I hereby declare the information provided above is true, accurate and complete."

Signature _____ Date _____

6

Ledgeview Farm, LLC
Odor Management Plan

Odor Complaint Protocol

Public relations, especially with neighbors, are an essential component of managing a large dairy business today. Ledgeview Farm, LLC (LF) will implement the following protocols to address odor concerns and reduce community conflicts.

1) The goal of LF is to establish a relationship with neighbors and community members and implement management practices that limit complaints due to odors. LF will make every effort to inform neighbors before activities are undertaken that may increase odors from the dairy.
2) Ledgeview Farm, LLC has designated Jason Pansier as the lead contact for all odor complaints. All odor complaints will be recorded on the "Record of Odor Complaints Form" at the end of this plan. This form records the date the complaint was received as well as who made the complaint and what concerns were expressed.
3) Ledgeview Farm, LLC will evaluate all odor complaints to determine if any practices can be implemented immediately to help reduce the odors that have generated the complaint. Potential odor control strategies to be implemented are identified in this plan.
4) Ledgeview Farm, LLC will follow up odor complaints to determine if the practices put in place helped to reduce odors after complaints have been received.

Identified Sources of Odors and Odor Control Strategies

Waste Storage Facilities – Currently, LF has one (1), liquid, long-term Waste Storage Facilities (WSF) at the Headquarters site. Ledgeview Farm, LLC proposes to construct a new long term WSF on the Heifer site that will provide a combined 291 days of storage. The current Waste Storage Facilities are constructed with a sloped floor and a ramp to provide access for periodic waste removal and applied to adjacent crop fields in the spring and fall. After construction of the proposed WSF on the Heifer Farm, the liquid Waste Storage Facilities will have a combined surface area of approximately 5.75 acres that can produce odors. The odors from the Waste Storage Facilities have the potential to bring about odor complaints. The following odor control strategies will be implemented.

- Feeding strategies will be used to avoid overfeeding of protein to help minimize compounds in excreted manure that contribute to excessive odors.
- During agitation, manure will not be sprayed into the air.

Animal Housing – Currently there is a Bedded Packed Heifer Barn, L1, and a Freestall Barn, L2 that are used to house the cattle at the Heifer Farm. Odors from the Animal Housing Facilities are fairly constant throughout the year and provide a low potential to bring about odor complaints. The following odor control strategies will be implemented:

- Animal Housing Facilities will be cleaned frequently to help reduce the amounts of odors generated from these facilities. All litter alleys and travel lanes will be cleaned at least 3 times per week. Frequent cleaning will also prevent the build up of manure in the corners of the litter alleys.
- Water conservation practices are used on the Heifer Farm. Practices include:
    - Checking waters daily to ensure the floats are properly set and the waters are not running over.

- All barn floor surfaces will be kept as dry as possible
- Feeding strategies will be used to avoid overfeeding of protein to help minimize compounds in excreted manure that contribute to excessive odors.

Feed Storage Area – Corn silage and haylage are stored in concrete bunkers in the Feed Storage Area to the south of the Heifer production site. The odors from the Feed Storage Area will be fairly constant throughout the year and provide a low potential to bring about odor complaints. The following odor control strategies will be implemented:

- Feed will be harvested at optimal moisture to minimize the potential for excessive leachate coming from stored feeds.
- Feed will be covered with plastic and tires to reduce the amount of spoiled feed and dust production.
- Excess and waste feed will be removed frequently and properly land applied according to the Nutrient Management Plan.

Land application of manure – Currently LF has a long-term Waste Storage Facility on the Headquarters site. In addition, a new WSF will be constructed on the northeast part of the Heifer site. Long-term Manure Storage Facilities are generally emptied in the spring and fall of the year. The liquid manure is hosed and injected directly into nearby cropland. Tankers are used to apply manure onto distant cropland and manure is injected into cropland. The land application of manure has the potential to produce nuisance odors that can bring about odor complaints. The following odor and dust control strategies will be implemented:

- Manure applications will be completed as quickly as possible to reduce the amount of time that odors can be generated.
- Manure will be injected directly or incorporated as soon as possible after application, to reduce odors.
- All gravel access roads will be sprayed down with water periodically during manure hauling to reduce the amount of dust produced from truck traffic.
- Mud on roads or highways that results will be removed frequently.

Mortalities – Animals dying due to injury or other causes happens in the day-to-day operation of a dairy farm. The mortality rate is generally highest for newborn animals. Odors from mortalities have a low potential to produce odors complaints because LF contracts with Circle R Mink Ranch to remove all dead animals within 24 hours. Odors from mortality disposal practices have a low potential to bring about odor complaints. The following odor control strategies will be implemented:

- Ledgeview Farm, LLC will continue to contract with Circle R Mink Ranch to remove all dead animals within 24 hours of a death event.
- Dead animals will be stored out of public view to reduce other conflicts.

Ledgview Farm, LLC

Record of Odor & Dust Complaints

Date/Time	Neighbor Expressing Concern	Concerns Expressed	Weather Conditions (circle)				Ledgeview Farm, LLC Follow Up Actions
			Wind Speed	Wind Direction	Temp.	Conditions	
			0 - 5	NW N NE	< 30°	Sunny	
			5 - 10	W E	30° to 40°	Partly Cloudy	
			10 - 15	SW S SE	40° to 50°	Mostly Cloudy	
			15 - 20		50° to 60°	Overcast	
			20 - 25		60° to 70°	Hazy	
			> 25		70° to 80°	Rain	
					80° to 90°	Snow	
					> 90°		

Date/Time	Neighbor Expressing Concern	Concerns Expressed	Weather Conditions (circle)				Ledgeview Farm, LLC Follow Up Actions
			Wind Speed	Wind Direction	Temp.	Conditions	
			0 - 5	NW N NE	< 30°	Sunny	
			5 - 10	W E	30° to 40°	Partly Cloudy	
			10 - 15	SW S SE	40° to 50°	Mostly Cloudy	
			15 - 20		50° to 60°	Overcast	
			20 - 25		60° to 70°	Hazy	
			> 25		70° to 80°	Rain	
					80° to 90°	Snow	
					> 90°		

Date/Time	Neighbor Expressing Concern	Concerns Expressed	Weather Conditions (circle)				Ledgeview Farm, LLC Follow Up Actions
			Wind Speed	Wind Direction	Temp.	Conditions	
			0 - 5	NW N NE	< 30°	Sunny	
			5 - 10	W E	30° to 40°	Partly Cloudy	
			10 - 15	SW S SE	40° to 50°	Mostly Cloudy	
			15 - 20		50° to 60°	Overcast	
			20 - 25		60° to 70°	Hazy	
			> 25		70° to 80°	Rain	
					80° to 90°	Snow	
					> 90°		

7

Exhibit 6-1
Waste Storage Facility Summary-Annual Storage Period Expanded Conditions
Leachate, Runoff Generation and Storage Capacity
Ledgeview Farm, LLC

Source	Volume (ft^3)	Volume (gallons)	Comments
Waste Generation			
Manure and Wastewater-Dairy	2,051,871	15,347,995	Exhibit 6-2
Manure and Wastewater-Steers	382,284	2,859,484	Exhibit 6-3
FSA Leachate-Heifer Farm	16,786	125,556	Exhibit 6-4
FSA Runoff-Heifer Farm	285,046	2,132,140	Exhibit 6-6
FSA Leachate-HQ*	1,683	12,589	Exhibit 6-9
FSA Runoff-HQ*	13,029	97,453	Exhibit 6-11
Y1 Heifer Farm Lot Runoff	84,856	634,723	Exhibit 6-8
Y1 HQ Farm Lot Runoff*	14,822	110,869	Exhibit 6-13
Sub-total	**2,850,376**	**21,320,809**	
Net Precipitation**			
WSF 1	111,303	832,546	
WSF 2	351,609	2,630,038	
Sub-total	**462,912**	**3,462,583**	
Total Waste Generated	**3,313,288**	**24,783,392**	
Waste Stored Above the MOL			
FSA-Heifer Farm 25 yr-24 hr	41,427	309,873	Exhibit 6-5
FSA-HQ 25 yr-24hr*	3,199	23,927	Exhibit 6-10
Y1 Hefier Farm Lot Runoff 25 yr-24 hr	13,263	99,204	Exhibit 6-7
Y1 HQ Farm Lot 25 yr-24 hr*	2,070	15,483	Exhibit 6-12
Total Waste Above MOL	59,958	448,487	
Waste Storage Facilities***			
WSF 1	669,334	5,006,618	
WSF 2	1,971,800	14,749,062	
Total Storage Volume	**2,641,134**	**19,755,680**	
Storage Capacity Evaluation			
Total Storage Volume	2,641,134	19,755,680	
Average Annual Storage Period	291 days		

*Allowance for future runoff collection system
**Net precipitation; 1.7 ft/year x WSF surface area
***MOL volume, determined by CADD

Ex 6-2 **WASTE STORAGE FACILITY DESIGN - 313 STANDARD** Ver. March 2015

CLIENT: Ledgeview Farm, LLC COUNTY: BROWN DATE: 12/4/17

DSN BY: JMR CHK BY: _____ DATE: _____

COMMENTS: Waste Generation - Dairy Expanded Conditions

ANIMAL TYPE> 1 (1=DAIRY, 2=BEEF, 3=VEAL, 4=SWINE(finishing), 5=SWINE(farrowing), 6=POULTRY, 0=OTHER)

For Dairy: Rolling Herd Average 25,000 lbs/cow/yr Is it a stanchion barn? n (Y or N)

MANURE AND WASTEWATER

LIVESTOCK KIND	NUMBER	AVG. WT. PER HEAD	DAILY OUTPUT, CU FT MANURE	BEDDING	TOTAL	DAYS OF STORAGE	VOLUME REQUIRED	ANIMAL UNITS
Cows Milki	1125	1,400	2.53	0.3	3183.8	365	1,162,069	1,575
Cows Dry	230	1,400	2.00	0.3	529.0	365	193,085	322
Heifers	450	1,000	1.60	0.3	855.0	365	312,075	450
Heifers	270	600	0.96	0.3	340.2	365	124,173	162
Calves	270	350	0.56	0.4	245.7	365	89,681	95
WASTEWATER:			3500	GAL/DAY	467.9	CU FT/DAY		2,604 TOT. A.U.
			TOTAL DAILY VOLUME:		5621.6	CU FT / DAY		

	15,347,995	GALLONS
Total Manure and Wastewater	**2,051,871**	**CU FT**
Expected % solids in waste (Includes runoff and precip.)	9.9	%

Ex 6-3 **WASTE STORAGE FACILITY DESIGN - 313 STANDARD** Ver. March 2015

CLIENT: Ledgeview Farm, LLC COUNTY: BROWN DATE: 12/4/17

DSN BY: JMR CHK BY: _____ DATE: _____

MMENTS Waste Generation Steers - Expanded Conditions

ANIMAL TYPE > 2 (1 = DAIRY, 2 = BEEF, 3 = VEAL, 4 = SWINE(finishing), 5 = SWINE(farrowing), 6 = POULTRY, 0 = OTHER)

n

MANURE AND WASTEWATER

LIVESTOCK		AVG. WT.	DAILY OUTPUT, CU FT			DAYS OF	VOLUME	ANIMAL	
KIND	NUMBER	PER HEAD	MANURE	BEDDING	TOTAL	STORAGE	REQUIRED	UNITS	
Beef	550	350	0.35	0.3	357.5	365	130,488	193	
Beef	525	850	1.00	0.3	682.5	365	249,113	446	
Beef									
	WASTEWATER:		55	GAL/DAY	7.4	CU FT/DAY		639	TOT. A.U.
			TOTAL DAILY VOLUME:		1047.4	CU FT / DAY			
								2,859,483	GALLONS
							Total Manure and Wastewater	382,284	**CU FT**
							Expected % solids in waste (Includes runoff and precip.)	10.1	%

Exhibit 6-4

Leachate and First Flush Volume Calculation Worksheet
Ledgeview Farm, LLC - Heifer Farm

Prepared By: Roach
Date: 2017

Input Data	Dimensions* Length	Width	Area ft^2
Existing FSA	varies	varies	93,253
			-
			-
			-

Total Area With Apron	93,253	ft^2
Total Area With Apron	2.1	Acres
Total Feed Storage Area Less Apron	93,253	ft^2

Volume of Feed Stored In the Facility

Silage Height	12	ft
Silage Density (defalt)	60	lbs/ft^3
Silage Volume	33,571	tons

Calculated Annual Leachate Volume

Silage Stored	33,571	tons
Leachate Volume Generated per Ton	0.5	ft^3/ton
Annual Leachate Generated	16,786	ft^3
Annual Leachate Generated	125,556	gal
Leachate Generated Per Day (30 day period)	4,185	gal/day
Leachate Generated Per Day (30 day period)	560	ft^3/day

Calculated First Flush Runoff Generation

Total Feed Storage Area Less Apron	93,253	ft^2
First Flush Runoff Depth Collected per Rain Event	0	in
First Flush Volume Collected per Rain Event	-	ft^3/event
First Flush Volume Collected per Rain Event	-	gal
Number of Rain Events (annual)		
Total Annual First Flush Volume Generated	-	ft^3
Total Annual First Flush Volume Generated	-	gal

Total Annual Leachate & First Flush Volume	125,556	gal
Total Daily Leachate & First Flush Volume	4,185	gal
Volume to Use For Calculation	7,500	gal

Leachate Collection Tank Volume		
Leachate Volume	560	ft^3/day
1st Flush Volume	-	ft^3/event
Total Design Volume	**560**	ft^3

20.72

Summary		
Annual Leachate Generated	16,786	ft^3
Annual First Flush Runoff Generated	-	ft^3
Total Annual Volume to Store	16,786	ft^3
Total Annual Volume to Store	125,556	gal

Cell to Enter Data Into
Cell has Formula and is Calculated

Exhibit 6-5

TR 55 PEAK RUNOFF CALCULATION (GRAPHICAL METHOD)

ver 5-2008

CLIENT: **Ledgeview Farm, LLC** COUNTY: **BROWN** DATE: 11/27/2017
DSN BY: **Roach** CHK BY: DATE:
COMMENTS: Feed Storage Area-Heifer Farm

Drainage Area	2.78	Acres
Runoff Curve Number	98.00	

Time of Concentration 0.07 Hours

Frequency	yr		2	5	10	25	50	100
Rainfall, P (24 hour)	in	1.00	2.5	3.2	3.7	4.3	4.8	5.1
Initial Abstraction, Ia	in	0.00	0	0	0	0	0	0
Ia/P ratio		0.00	0.000	0.000	0.000	0.000	0.000	0.000
Unit Peak Discharge, qu	cfs/ac/in	1.72	1.720	1.720	1.720	1.720	1.720	1.720
Runoff	in	0.83	2.31	3.01	3.51	4.11	4.60	4.90
	ac-ft	0.19	0.54	0.70	0.81	0.95	1.07	1.14
Peak Discharge, qp	cfs	**3.97**	**11.1**	**14.4**	**16.8**	**19.6**	**22.0**	**23.4**

Total Runoff One Inch Rain = 0.19 ac-ft 8,381 cubic feet 62,690 gallons

Total Runoff 25 year Event = 0.95 ac-ft 41,427 cubic feet 309,873 gallons

Peak Flow = 19.63 cfs 8,810 gpm

Exhibit 6-6
Monthly Feed Storage Area Runoff-Heifer Farm
Ledgeview Farm, LLC

	FSA Runoff Volume*		Runoff Volume to WSF	
Month	**(ft^3)**	**(gallons)**	**(ft^3)**	**(gallons)**
Jan**	7,129	53,325	0	0
Feb**	6,463	48,343	0	0
March***	14,992	112,140	7,496	56,070
April	26,343	197,046	26,343	197,046
May	33,722	252,241	33,722	252,241
June	43,560	325,829	43,560	325,829
July	41,109	307,495	41,109	307,495
Aug	42,379	316,995	42,379	316,995
Sept	38,740	289,775	38,740	289,775
Oct	27,062	202,424	27,062	202,424
Nov	19,428	145,321	19,428	145,321
Dec***	10,413	77,889	5,207	38,945
	311,340	2,328,823	285,046	2,132,140
Winter Months (Nov-April)			58,474	437,382

*121,097 sq ft FSA, RCN 98

***Fifty percent snow removal

25 year, 24 hour rainfall runoff	41,427	cu ft	309,873	gallons

Exhibit 6-7

TR 55 PEAK RUNOFF CALCULATION (GRAPHICAL METHOD)

ver 5-2008

CLIENT: **Ledgeview Farm, LLC** COUNTY: **BROWN** DATE: 5/24/2011
DSN BY: **Roach** CHK BY: DATE:
COMMENTS: Y1 Animal Lot - Heifer Farm

Drainage Area	0.89	Acres
Runoff Curve Number	98.00	

Time of Concentration 0.07 Hours

Frequency	yr		2	5	10	25	50	100
Rainfall, P (24 hour)	in	1.00	2.5	3.2	3.7	4.3	4.8	5.1
Initial Abstraction, Ia	in	0.00	0	0	0	0	0	0
Ia/P ratio		0.00	0.000	0.000	0.000	0.000	0.000	0.000
Unit Peak Discharge, qu	cfs/ac/in	1.72	1.720	1.720	1.720	1.720	1.720	1.720
Runoff	in	0.83	2.31	3.01	3.51	4.11	4.60	4.90
	ac-ft	0.06	0.17	0.22	0.26	0.30	0.34	0.36
Peak Discharge, qp	cfs	1.27	3.5	4.6	5.4	6.3	7.0	7.5

Total Runoff One Inch Rain = 0.06 ac-ft 2,683 cubic feet 20,070 gallons

Total Runoff 25 year Event = 0.30 ac-ft 13,263 cubic feet 99,204 gallons

Peak Flow = 6.28 cfs 2,821 gpm

Exhibit 6-8
Monthly Animal Lot Runoff-Heifer Farm
Ledgeview Farm, LLC

	Y1 Runoff Volume*		Runoff Volume to WSF	
Month	**(ft^3)**	**(gallons)**	**(ft^3)**	**(gallons)**
Jan**	2,291	17,137	0	0
Feb**	2,077	15,536	0	0
March***	4,819	36,046	2,410	18,023
April	8,468	63,341	8,468	63,341
May	10,840	81,083	10,840	81,083
June	14,002	104,735	14,002	104,735
July	13,214	98,841	13,214	98,841
Aug	13,622	101,893	13,622	101,893
Sept	8,699	65,069	8,699	65,069
Oct	6,245	46,713	6,245	46,713
Nov	3,347	25,036	3,347	25,036
Dec***	8,019	59,982	4,010	29,991
	95,643	715,410	84,856	634,723
Winter Months (Nov-April)			18,234	136,390

*38,925 sq ft FSA, RCN 98
**Snow removal
***Fifty percent snow removal

25 year, 24 hour rainfall runoff	13,263	cu ft	99,204	gallons

Exhibit 6-9

Leachate and First Flush Volume Calculation Worksheet
Ledgeview Farm, LLC - Headquarters Farm

Prepared By: Roach
Date: 2017

Input Data	Dimensions* Length	Width	Area ft^2
FSA Home Farm	170	55	9,350
			-
			-
			-
			-

Total Area With Apron	9,350	ft^2
Total Area With Apron	0.2	Acres
Total Feed Storage Area Less Apron	9,350	ft^2

Volume of Feed Stored In the Facility

Silage Height	12	ft
Silage Density (defalt)	60	lbs/ft^3
Silage Volume	3,366	tons

Calculated Annual Leachate Volume

Silage Stored	3,366	tons
Leachate Volume Generated per Ton	0.5	ft^3/ton
Annual Leachate Generated	1,683	ft^3
Annual Leachate Generated	12,589	gal
Leachate Generated Per Day (30 day period)	420	gal/day
Leachate Generated Per Day (30 day period)	56	ft^3/day

Calculated First Flush Runoff Generation

Total Feed Storage Area Less Apron	9,350	ft^2
First Flush Runoff Depth Collected per Rain Event	0	in
First Flush Volume Collected per Rain Event	-	ft^3/event
First Flush Volume Collected per Rain Event	-	gal
Number of Rain Events (annual)		
Total Annual First Flush Volume Generated	-	ft^3
Total Annual First Flush Volume Generated	-	gal

Total Annual Leachate & First Flush Volume	12,589	gal
Total Daily Leachate & First Flush Volume	420	gal
Volume to Use For Calculation		gal

Leachate Collection Tank Volume		
Leachate Volume	56	ft^3/day
1st Flush Volume	-	ft^3/event
Total Design Volume	**56**	**ft^3**

2.08

Summary		
Annual Leachate Generated	1,683	ft^3
Annual First Flush Runoff Generated	-	ft^3
Total Annual Volume to Store	1,683	ft^3
Total Annual Volume to Store	12,589	gal

Cell to Enter Data Into	
Cell has Formula and is Calculated	

Exhibit 6-10

TR 55 PEAK RUNOFF CALCULATION (GRAPHICAL METHOD)

ver 5-2008

CLIENT: **Ledgeview Farm, LLC** COUNTY: **BROWN** DATE: 5/24/2011
DSN BY: **Roach** CHK BY: DATE:
COMMENTS: Feed Storage Area Headquartrs Farm

Drainage Area	0.21	Acres
Runoff Curve Number	98.00	

Time of Concentration 0.07 Hours

Frequency	yr		2	5	10	25	50	100
Rainfall, P (24 hour)	in	1.00	2.5	3.2	3.7	4.3	4.8	5.1
Initial Abstraction, Ia	in	0.00	0	0	0	0	0	0
Ia/P ratio		0.00	0.000	0.000	0.000	0.000	0.000	0.000
Unit Peak Discharge, qu	cfs/ac/in	1.72	1.720	1.720	1.720	1.720	1.720	1.720
Runoff	in	0.83	2.31	3.01	3.51	4.11	4.60	4.90
	ac-ft	0.01	0.04	0.05	0.06	0.07	0.08	0.09
Peak Discharge, qp	cfs	0.31	0.9	1.1	1.3	1.5	1.7	1.8

Total Runoff One Inch Rain = 0.01 ac-ft 647 cubic feet 4,841 gallons

Total Runoff 25 year Event = 0.07 ac-ft 3,199 cubic feet 23,927 gallons

Exhibit 6-11
Monthly Feed Storage Area Runoff-Headquarters Farm
Ledgeview Farm, LLC

	FSA Runoff Volume*		Runoff Volume to WSF	
Month	**(ft^3)**	**(gallons)**	**(ft^3)**	**(gallons)**
Jan**	834	6,238	0	0
Feb**	779	5,827	0	0
March***	1,340	10,023	670	5,012
April	1,792	13,404	1,792	13,404
May	1,434	10,726	1,434	10,726
June	1,348	10,083	1,348	10,083
July	982	7,345	982	7,345
Aug	1,286	9,619	1,286	9,619
Sept	1,683	12,589	1,683	12,589
Oct	1,675	12,529	1,675	12,529
Nov	1,621	12,125	1,621	12,125
Dec***	1,075	8,041	538	4,021
	15,849	118,551	13,029	97,453
Winter Months (Nov-April)			4,621	34,561

*9,350 sq ft FSA, RCN 98
**Snow removal
***Fifty percent snow removal

25 year, 24 hour rainfall runoff	2,070	cu ft	15,481	gallons

Exhibit 6-12

TR 55 PEAK RUNOFF CALCULATION (GRAPHICAL METHOD)

ver 5-2008

CLIENT: **Ledgeview Farm, LLC** COUNTY: **BROWN** DATE: 5/24/2011
DSN BY: **Roach** CHK BY: DATE:
COMMENTS: Animal Lot Headquarters Farm

Drainage Area	0.14	Acres
Runoff Curve Number	98.00	

Time of Concentration 0.07 Hours

Frequency	yr	2	5	10	25	50	100
Rainfall, P (24 hour)	in	2.5	3.2	3.7	4.3	4.8	5.1
Initial Abstraction, Ia	in	0	0	0	0	0	0
Ia/P ratio		0.000	0.000	0.000	0.000	0.000	0.000
Unit Peak Discharge, qu	cfs/ac/in	1.720	1.720	1.720	1.720	1.720	1.720
Runoff	in	2.31	3.01	3.51	4.11	4.60	4.90
	ac-ft	0.03	0.03	0.04	0.05	0.05	0.06
Peak Discharge, qp	cfs	0.6	0.7	0.8	1.0	1.1	1.2

Total Runoff One Inch Rain = 0.01 ac-ft 419 cubic feet 3,132 gallons

Total Runoff 25 year Event = 0.05 ac-ft 2,070 cubic feet 15,483 gallons

Exhibit 6-13
Monthly Animal Lot Runoff-Headquarters Farm
Ledgeview Farm, LLC

	FSA Runoff Volume*		Runoff Volume to WSF	
Month	**(ft^3)**	**(gallons)**	**(ft^3)**	**(gallons)**
Jan**	356	2,663	0	0
Feb**	323	2,416	0	0
March***	749	5,603	375	2,801
April	1,316	9,844	1,316	9,844
May	1,685	12,604	1,685	12,604
June	2,176	16,276	2,176	16,276
July	2,054	15,364	2,054	15,364
Aug	2,117	15,835	2,117	15,835
Sept	1,935	14,474	1,935	14,474
Oct	971	7,263	971	7,263
Nov	520	3,890	520	3,890
Dec***	3,347	25,036	1,674	12,518
	17,549	131,267	14,822	110,869
Winter Months (Nov-April)			3,884	29,052

*6,050 sq ft FSA, RCN 98
**Snow removal
***Fifty percent snow removal

25 year, 24 hour rainfall runoff	2,070	cu ft	15,481	gallons

8

Wel. 6-30M(6-50)

WELL CONSTRUCTOR'S REPORT TO WISCONSIN STATE BOARD OF HEALTH

See Instructions on Reverse Side

1. County Brown — Town ☒ / Village ☐ / City ☐ De Pere (Check one and give name)

2. Location N.W.¼ of S.W.¼ of sec. 28, T.23N, R.21E
Name of street and number of premise or Section, Town and Range numbers

3. Owner ☒ or Agent ☐ Anton Dollar
Name of individual, partnership or firm

4. Mail Address Route 2, DePere, Wisconsin
Complete address required

RECEIVED JAN 19 1951 WISCONSIN STATE BOARD OF HEALTH SAN. ENG.

5. From well to nearest: Building 20 ft; ~~sewer~~ privy 80 ft; drain ____ ft; septic tank ____ ft; dry well or filter bed ____ ft; abandoned well ____ ft.

6. Well is intended to supply water for: Farm

7. DRILLHOLE:

Dia. (in.)	From (ft.)	To (ft.)	Dia. (in.)	From (ft.)	To (ft.)
8	0	20			
6	20	170			

8. CASING AND LINER PIPE OR CURBING:

Dia. (in.)	Kind and Weight	From (ft.)	To (ft.)
6	Standard Weight Steel Pipe	0	54

9. GROUT:

Kind	From (ft.)	To (ft.)
Puddled Clay (fill)	0	20

10. FORMATIONS:

Kind	From (ft.)	To (ft.)
Red Clay	0	50
Gravel	50	54
Limestone	54	114
Shale & Limestone	114	170

Construction of the well was completed on:
January 17, 1951

The well is terminated 6 inches ☒ above, below ☐ the permanent ground surface.

Was the well disinfected upon completion? Yes X No ____

Was the well sealed watertight upon completion? Yes X No ____

11. MISCELLANEOUS DATA:

Yield test: 4 Hrs. at 10 GPM.

Depth from surface to water-level: 33 ft.

Water-level when pumping: 36 ft.

Water sample was sent to the state laboratory at: Green Bay (City) on January 17, 1951

Signature Ray Gleason (Registered Well Driller)

1169 Pine Street, Green Bay, Wis. (Complete Mail Address)

Please do not write in space below

Rec'd ____ No. ____

Ans'd ____

Interpretation ____

	10 ml	10 ml	10 ml	10 ml	10 ml
Gas—24 hrs.					
48 hrs.					
Confirm					
B. Coli					

Examiner ____

BN 3878

9

Ledgeview Farm, LLC

Date	Activity
Waste Storage Facility, Feed Storage and Leachate Management System	
May 2018	Install erosion control measures
May 2018	Strip and stockpile topsoil from Waste Storage Facility
May 2018	Seed topsoil piles
June 2018	Inspect erosion control measures and take corrective action
June 2018	Excavation for Waste Storage Facility and fill Leachate channel
July 2018	Install concrete liner in Waste Storage Facility and construct Leachate Channel
July 2018	Install concrete liner in Waste Storage Facility and construct Leachate Channel
July 2018	Inspect erosion control measures and take corrective action
July 2018	Install topsoil, final grade and seed as needed
Heifer Barn Expansion and Y2 Yard	
June 2019	Install erosion control measures
June 2019	Strip and stockpile topsoil from barn area
June 2019	Seed topsoil piles
June 2019	Inspect erosion control measures and take corrective action
June 2019	Install footings and walls
June 2019	Install underground utilities
June 2019	Install litter and feed alleys
July 2019	Install columns and rafters
July 2019	Install utilities
July 2019	Complete barn construction
August 2019	Install topsoil, final grade and seed as needed

10

Exhibit 9

Other Laws & Permits

The following laws may apply to the operations of Ledgeview Farm, LLC:

- Town of Ledgeview Chapter ATCP 51 – Livestock Facility Siting
- Town of Ledgeview Conditional Use Permit
- Town of Ledgeview Building Permit
- Town of Ledgeview Construction Site Erosion Control Permit
- Brown County Animal Waste Management Ordinance
  - Animal Waste Storage Facility Permit
  - Animal Feedlot Permit
- Brown County – Nutrient Management Plan approval
- DNR Chapter NR 243 - Animal Feeding Operations - WPDES permit
- DNR - Plan & Specifications approval for all reviewable facilities
- DNR – Construction Site Erosion Control Permit

11

N

N1

E1

W1

S1

S2

W1: WASTE STORAGE FACILITY

L1: FREESTALL BARN

L2: HEIFERS BEDDED PACK BARN

L3: FREESTALL BARN

L4: FREESTALL BARN

L5: HEIFER BEDDED PACK

L6: CALF BARN

Y1: CONCRETE YARD

W1 TO N1 = 334'

L1 TO N1 = 649'

W1 TO E1 = 600'

L5 TO N1 = 1179'

Y1 TO N1 = 1218'

L6 TO N1 = 1239'

W1 TO S1 = 1061'

L4 TO N1 = 1138'

L3 TO N1 = 1051'

L4 TO E1 = 1273'

L3 TO E1 = 1159'

L2 TO N1 = 1170'

L2 TO E1 = 1163'

L5 TO E1 = 1134'

L1 TO E1 = 429'

Y1 TO N1 = 1218'

Y1 TO E1 = 1161'

L6 TO E1 = 1161'

W1 TO W1 = 1116'

L3 TO WI = 594'

L4 TO WI = 465'

L1 TO WI = 736'

L4 TO S2 = 826'

L3 TO S2 = 718'

L2 TO WI = 376'

L5 TO WI = 567'

Y1 TO W1 = 664'

W1 TO L6 = 594'

L4 TO S1 = 794'

L2 TO S2 = 586'

L3 TO S1 = 618'

L2 TO S1 = 492'

Y1 TO S2 = 454'

Y1 TO S1 = 368'

L6 TO S1 = 285'

L1 TO S1 = 573'

W1 TO S2 = 1000'

L1 TO S2 = 519'

L5 TO S2 = 478'

L6 TO S2 = 379'

250' TO WELL

APPLICANT-OWNED RESIDENCE

250' TO WELL

EXEMPT RESIDENCE

Dickinson Rd

CTH "G"

CTH "V" Lime Kiln Rd

Lime Kiln Rd

DATE:	11/22/2017	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISIONS BY	DATE	DESCRIPTION OF REVISION
DRAWN BY:	MTS	*	*	*	*	*	*
CHECKED BY:	JMR						

LEDGEVIEW FARM LLC
2017 WASTE STORAGE FACILITY AND LEACHATE MANAGEMENT SYSTEM
BROWN COUNTY, WISCONSIN

SCALE: 1"=150'

NEAREST NEIGHBOR SITE PLAN

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 1

Ledgeview Farm, LLC
Cluster A
Livestock Siting Distance to Neighbors

Livestock Structures	Nearest Neighbors			
	N1	E1	W1	S1
	(feet)			
L1 Barn	649	429	736	573
L2 Barn	1,170	1,163	376	492
L3 Barn	1,051	1,159	594	618
L4 Barn	1,138	1,273	465	704
L5 Barn	1,179	1,134	567	398
L6 Barn	1,239	1,161	594	285
Waste Storage Facility - W1	334	600	1,116	1,061
Concrete Yard - Y1	1,218	1,161	664	368

Livestock Facility: Ledgeview Farm, LLC - Cluster A
Location: N1 North Neighbor

Odor Score Spreadsheet - Ver. 2.0

4/30/17

1. Animal Housing

ID	Manure Management	Generation number	Occupied Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
L1	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	90,743	649	Diet manipulation	0.8	None	1	None	1	29
L2	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	31,758	1,170	Diet manipulation	0.8	None	1	None	1	10
L3	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	16,523	1,051	Diet manipulation	0.8	None	1	None	1	5
L4	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	18,578	1,138	Diet manipulation	0.8	None	1	None	1	6
L5	Bedded Pack - Dairy and Beef	2	15,103	1,179	Diet manipulation	0.8	None	1	None	1	2
L6	Bedded Pack - Dairy and Beef	2	17,378	1,239	Diet manipulation	0.8	None	1	None	1	3
1G											
1H											
1I											
1J											
1K											
1L											

2. Waste Storage

ID	Storage type	Generation number	Surface Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
W1	Liquid storage - Long term (pit and tank) Open anaerobic	13	56,189	334	Natural Crust	0.3	None	1	None	1	22
					None		None		None		
2C											
2D											
2E											
2F											

3. Animal Lots

ID	Lot type	Generation number	Surface Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
Y1	Paved	4	5,953	1,218	Clean frequently (within 3 days)	0.4	None	1	None	1	1
					None		None		None		

4. Separation Distance

Weighted Distance to Neighbor	734
Direction of Nearest Neighbor	North
Adjusted Weighted Distance	734
Density (neighbors within 1,300 ft.)	High

5. Management

Basic Management Plans	Required
Advanced Odor Management Plan?	Yes

Total Predicted Odor	78
Separation Score	569
Basic Management Score	80
Advanced Management Score	20
Odor Score	591

587

Livestock Facility: Ledgeview Farm, LLC - Cluster A — Odor Score Spreadsheet - Ver. 2.0 — 11/30/17

Loca E1 East Neighbor

1. Animal Housing

ID	Manure Management	Generation number	Occupied Area (Ft.²)	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
L1	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	90,743	429	Diet manipulation	0.8	None	1	None	1	29
L2	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	31,758	1,163	Diet manipulation	0.8	None	1	None	1	10
L3	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	16,523	1,159	Diet manipulation	0.8	None	1	None	1	5
L4	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	18,578	1,273	Diet manipulation	0.8	None	1	None	1	6
L5	Bedded Pack - Dairy and Beef	2	15,103	1,134	Diet manipulation	0.8	None	1	None	1	2
L6	Bedded Pack - Dairy and Beef	2	17,378	1,161	Diet manipulation	0.8	None	1	None	1	3
1G											
1H											
1I											
1J											
1K											
1L											

2. Waste Storage

ID	Storage type	Generation number	Surface Area (Ft.²)	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
W1	Liquid storage - Long term (pit and tank) Open anaerobic	13	56,189	600	Natural Crust	0.3	None	1	None	1	22
					None		None		None		
2C											
2D											
2E											
2F											

3. Animal Lots

ID	Lot type	Generation number	Surface Area (Ft.²)	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
Y1	Paved	4	5,953	1,161	Clean frequently (within 3 days)	0.4	None	1	None	1	1
					None		None		None		

4. Separation Distance

Weighted Distance to Neighbor	739
Direction of Nearest Neighbor	East
Adjusted Weighted Distance	813
Density (neighbors within 1,300 ft.)	High

5. Management

Basic Management Plans	Required
Advanced Odor Management Plan?	Yes

Total Predicted Odor	78
Separation Score	585
Basic Management Score	80
Advanced Management Score	20
Odor Score	607

588

Livest[illegible]k Facility: Ledgeview Farm, LLC - Cluster A
Loca[illegible]: W1 West Neighbor

Odor Score Spreadsheet - Ver. 2.0

[illegible]/30/17

1. Animal Housing

ID	Manure Management	Generation number	Occupied Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
L1	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	90,743	736	Diet manipulation	0.8	None	1	None	1	29
L2	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	31,758	376	Diet manipulation	0.8	None	1	None	1	10
L3	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	16,523	594	Diet manipulation	0.8	None	1	None	1	5
L4	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	18,578	465	Diet manipulation	0.8	None	1	None	1	6
L5	Bedded Pack - Dairy and Beef	2	15,103	567	Diet manipulation	0.8	None	1	None	1	2
L6	Bedded Pack - Dairy and Beef	2	17,378	594	Diet manipulation	0.8	None	1	None	1	3
1G											
1H											
1I											
1J											
1K											
1L											

2. Waste Storage

ID	Storage type	Generation number	Surface Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
W1	Liquid storage - Long term (pit and tank) Open anaerobic	13	56,189	1,116	Natural Crust	0.3	None	1	None	1	22
					None		None		None		
2C											
2D											
2E											
2F											

3. Animal Lots

ID	Lot type	Generation number	Surface Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
Y1	Paved	4	5,953	664	Clean frequently (within 3 days)	0.4	None	1	None	1	1
					None		None		None		

4. Separation Distance

Weighted Distance to Neighbor	756
Direction of Nearest Neighbor	West
Adjusted Weighted Distance	983
Density (neighbors within 1,300 ft.)	High

5. Management

Basic Management Plans	Required
Advanced Odor Management Plan?	Yes

Total Predicted Odor	78
Separation Score	601
Basic Management Score	80
Advanced Management Score	20
Odor Score	623

589

Livestock Facility: Ledgeview Farm, LLC - Cluster A
Location: S1 South Neighbor

Odor Score Spreadsheet - Ver. 2.0

11/30/17

1. Animal Housing

ID	Manure Management	Generation number	Occupied Area (Ft.²)	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
L1	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	90,743	573	Diet manipulation	0.8	None	1	None	1	29
L2	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	31,758	492	Diet manipulation	0.8	None	1	None	1	10
L3	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	16,523	618	Diet manipulation	0.8	None	1	None	1	5
L4	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	18,578	704	Diet manipulation	0.8	None	1	None	1	6
L5	Bedded Pack - Dairy and Beef	2	15,103	398	Diet manipulation	0.8	None	1	None	1	2
L6	Bedded Pack - Dairy and Beef	2	17,378	285	Diet manipulation	0.8	None	1	None	1	3
1G											
1H											
1I											
1J											
1K											
1L											

2. Waste Storage

ID	Storage type	Generation number	Surface Area (Ft.²)	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
W1	Liquid storage - Long term (pit and tank) Open anaerobic	13	56,189	1,061	Natural Crust	0.3	None	1	None	1	22
					None		None		None		
2C											
2D											
2E											
2F											

3. Animal Lots

ID	Lot type	Generation number	Surface Area (Ft.²)	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
Y1	Paved	4	5,953	368	Clean frequently (within 3 days)	0.4	None	1	None	1	1
					None		None		None		

590


4. Separation Distance

Weighted Distance to Neighbor	695
Direction of Nearest Neighbor	South
Adjusted Weighted Distance	834
Density (neighbors within 1,300 ft.)	High

5. Management

Basic Management Plans	Required
Advanced Odor Management Plan?	Yes

Total Predicted Odor	78
Separation Score	585
Basic Management Score	80
Advanced Management Score	20
Odor Score	607



DATE:	11/22/2017	REVISION DATE	BY	DESCRIPTION OF REVISION	REVISIONS BY	DATE	DESCRIPTION OF REVISION	LEDGEVIEW FARMS, LLC 2017 WASTE STORAGE FACILITY AND LEACHATE MANAGEMENT SYSTEM BROWN COUNTY, WISCONSIN	SCALE: 1"=300'	NEAREST NEIGHBOR SITE PLAN	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 1
DRAWN BY:	MTS											
CHECKED BY:	JMR											

12

Ledgeview Farm, LLC
Cluster B
Livestock Siting Distance to Neighbors

Facility	N1	E1	S1
	(feet)		
Collection Basin - CB	1,309	1,156	1,773
Waste Storage Facility - W2	361	509	1,935
Bedded Pack Barn - L1	1,226	855	1,631
Freestall Barn - L2	1,748	1,213	464
Concrete Yard - Y1	1,309	930	1,519
Concrete Yard - Y2	1,735	1,233	1,079
Feed Storage Area	1,472	1,029	1,098

Livest[illegible] Facility: Ledgeview Farm, LLC - Cluster B

Locat. N1 North Neighbor

Odor Score Spreadsheet - Ver. 2.0

[illegible]21/17

1. Animal Housing

ID	Manure Management	Generation number	Occupied Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
L1	Bedded Pack - Dairy and Beef	2	34,279	1,226	Diet manipulation	0.8	None	1	None	1	5
L2	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	81,532	1,748	Diet manipulation	0.8	None	1	None	1	26
1C											
1D											
1E											
1F											
1G											
1H											
1I											
1J											
1K											
1L											

2. Waste Storage

ID	Storage type	Generation number	Surface Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
W2	Liquid storage - Long term (pit and tank) Open anaerobic	13	194,475	361	Natural Crust	0.3	None	1	None	1	76
CB	Liquid storage - Short term (pit and tank) Open anaerobic	28	638	1,309	None	1	None	1	None	1	2
2C											
2D											
2E											
2F											

3. Animal Lots

ID	Lot type	Generation number	Surface Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
Y1	Paved	4	42,660	1,309	Clean frequently (within 3 days)	0.4	Water Control (gutters & diversions)	0.8	None	1	5
Y2	Paved	4	4,494	1,735	Clean frequently (within 3 days)	0.4	None	1	None	1	1

4. Separation Distance

Weighted Distance to Neighbor	782
Direction of Nearest Neighbor	North
Adjusted Weighted Distance	782
Density (neighbors within 1,300 ft.)	High

5. Management

Basic Management Plans	Required
Advanced Odor Management Plan?	Yes

Total Predicted Odor	115
Separation Score	569
Basic Management Score	80
Advanced Management Score	20
Odor Score	554

Livestock Facility: Ledgeview Farm, LLC - Cluster B
Location: E1 East Neighbor

Odor Score Spreadsheet - Ver. 2.0

11/21/17

1. Animal Housing

ID	Manure Management	Generation number	Occupied Area (Ft.²)	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
L1	Bedded Pack - Dairy and Beef	2	34,279	855	Diet manipulation	0.8	None	1	None	1	5
L2	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	81,532	1,213	Diet manipulation	0.8	None	1	None	1	26
1C											
1D											
1E											
1F											
1G											
1H											
1I											
1J											
1K											
1L											

2. Waste Storage

ID	Storage type	Generation number	Surface Area (Ft.²)	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
W2	Liquid storage - Long term (pit and tank) Open anaerobic	13	194,475	509	Natural Crust	0.3	None	1	None	1	76
CB	Liquid storage - Short term (pit and tank) Open anaerobic	28	638	1,156	None	1	None	1	None	1	2
2C											
2D											
2E											
2F											

3. Animal Lots

ID	Lot type	Generation number	Surface Area (Ft.²)	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
Y1	Paved	4	42,660	930	Clean frequently (within 3 days)	0.4	Water Control (gutters & diversions)	0.8	None	1	5
Y2	Paved	4	4,494	1,233	Clean frequently (within 3 days)	0.4	None	1	None	1	1

595

4. Separation Distance

Weighted Distance to Neighbor	719
Direction of Nearest Neighbor	East
Adjusted Weighted Distance	791
Density (neighbors within 1,300 ft.)	High

5. Management

Basic Management Plans	Required
Advanced Odor Management Plan?	Yes

Total Predicted Odor	115
Separation Score	569
Basic Management Score	80
Advanced Management Score	20
Odor Score	554

Livest[illegible] Facility: Ledgeview Farm, LLC - Cluster B

Locat[illegible] S1 South Neighbor

Odor Score Spreadsheet - Ver. 2.0

[illegible]21/17

1. Animal Housing

ID	Manure Management	Generation number	Occupied Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
L1	Bedded Pack - Dairy and Beef	2	34,279	1,631	Diet manipulation	0.8	None	1	None	1	5
L2	Freestall - Dairy - Scrape (incl. Beef and Heifers on forage ration)	4	81,532	464	Diet manipulation	0.8	None	1	None	1	26
1C											
1D											
1E											
1F											
1G											
1H											
1I											
1J											
1K											
1L											

2. Waste Storage

ID	Storage type	Generation number	Surface Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
W2	Liquid storage - Long term (pit and tank) Open anaerobic	13	194,475	1,935	Natural Crust	0.3	None	1	None	1	76
CB	Liquid storage - Short term (pit and tank) Open anaerobic	28	638	1,773	None	1	None	1	None	1	2
2C											
2D											
2E											
2F											

3. Animal Lots

ID	Lot type	Generation number	Surface Area (Ft.^{2})	Dist. to Nearest Neighbor (Ft.)	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Control Practice	Reduction Factor	Predicted Odor
Y1	Paved	4	42,660	1,519	Clean frequently (within 3 days)	0.4	Water Control (gutters & diversions)	0.8	None	1	5
Y2	Paved	4	4,494	1,079	Clean frequently (within 3 days)	0.4	None	1	None	1	1

4. Separation Distance

Weighted Distance to Neighbor	1,561
Direction of Nearest Neighbor	South
Adjusted Weighted Distance	1,873
Density (neighbors within 1,300 ft.)	High

5. Management

Basic Management Plans	Required
Advanced Odor Management Plan?	Yes

Total Predicted Odor	115
Separation Score	793
Basic Management Score	80
Advanced Management Score	20
Odor Score	778

596

LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS

3688 LIME KILN ROAD
DE PERE, WI
BROWN COUNTY

OFFICE USE ONLY

LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS



NTS



SITE VICINITY MAP

LEGEND

- EXISTING CONTOURS (500 / 499)
- PROPOSED CONTOURS (500 / 499)
- PROPOSED CONCRETE
- EXISTING CONCRETE
- PROPOSED ASPHALT
- COMPACTED FILL
- PROPOSED GRAVEL DRIVE
- IN-PLACE EARTH LINER
- COMPACTED CLAY LINER
- EXISTING BUILDING
- PROPOSED BUILDING
- PRESSURE TRANSFER PIPE
- GRAVITY TRANSFER PIPE
- TILE LINE
- SILT FENCE
- BALE DIVERSION
- ELECTRIC LINE
- WL — WETLAND (DELINEATED)
- DITCH CHECK
- TEST PIT
- WELL
- BENCH MARK

PLAN TABLE OF CONTENTS

SHEET #	DESCRIPTION
1	TITLE SHEET
2	SITE PLAN
3	WASTE STORAGE FACILITY PLAN
4	WASTE STORAGE FACILITY PROFILES
	1: PLAN – WATERSTOP PLACEMENT
	2: PROFILE – WASTE STORAGE FACILITY
	3: PROFILE – WASTE STORAGE FACILITY
	4: 5" CONCRETE DETAIL
	5: 7" CONCRETE DETAIL
5	DETENTION BASIN PLAN AND PROFILES
	1: PLAN – DETENTION BASIN
	2: PROFILE – DETENTION BASIN
	3: PROFILE – DETENTION BASIN
	4: PROFILE – DETENTION BASIN
	5: 5" CONCRETE DETAIL
	6: 7" CONCRETE DETAIL
	7: CONCRETE CONNECTION DETAIL
6	WASTE TRANSFER PIPE #1 PLAN AND PROFILE
	1: PLAN – WASTE TRANSFER PIPE #1
	2: PROFILE – WASTE TRANSFER PIPE #1
	3: ALTERNATE PIPE MATERIALS
	4: MANHOLE @ STA: 11+00 DETAIL
	5: PIPE TRENCH DETAIL
7	WASTE TRANSFER PIPE #2 PLAN AND PROFILE
	1: PLAN – WASTE TRANSFER PIPE #2
	2: PROFILE – WASTE TRANSFER PIPE #2
	3: LINER PENETRATION DETAIL
	4: TANK PENETRATION DETAIL
	5: DOUBLE CLEANOUT DETAIL
	6: 4-FT MANHOLE DETAIL
8	CONSTRUCTION DETAILS
	1: WATERSTOP JOINT DETAIL
	2: WATERSTOP INSTALLATION DETAIL
	3: DEPTH GAUGE DETAIL
	4: FENCE DETAIL
	5: PIPE PENETRATION DETAIL
E1.0	CONSTRUCTION SITE EROSION CONTROL PLAN
E1.1	EROSION CONTROL DETAILS
	1: SEEDING PLAN
	2: TRACKING PAD
	3: FILTER SOCK DETAIL
	4: CONSTRUCTION SCHEDULE
	5: CUT & FILL QUANTITIES
	6: EROSION CONTROL NOTES
	7: SOIL LOSS & SEDIMENT DISCHARGE CALCULATIONS

NO REPRESENTATION IS MADE BY ROACH & ASSOCIATES AS TO THE EXISTENCE OR NONEXISTENCE OF UNDERGROUND HAZARDS. PRIOR TO THE START OF CONSTRUCTION THE OWNERS OF UTILITIES MUST BE NOTIFIED OF THE PENDING CONSTRUCTION. CONTRACTOR WILL BE LIABLE FOR DAMAGES RESULTING FROM CONSTRUCTION ACTIVITIES. (CALL DIGGERS HOTLINE)

To the best of my professional knowledge, judgment and belief, this design and these construction plans 2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS, meet the criteria, standards and specifications outlined in USDA Natural Resources Conservation Service Field Office Technical Guide, Section IV, Standards 313(10/17), 522(10/12), and 634(1/14), Spec.'s 4(10/12), 004(10/17), 204(10/12) and 634(8/16)

Richard Seas Date 12/6/17

WISCONSIN
RICHARD C. SEAS
E25248
Green Bay, Wis.
PROFESSIONAL ENGINEER

ENGINEER:

ROACH & ASSOCIATES, LLC
856 N. MAIN ST., SEYMOUR, WI 54165
PHONE: 920-833-6340

Richard Seas 12/6/17

		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	12/06/2017	*	*	*	*	*	*
DRAWN BY:	TJS	*	*	*	*	*	*
CHECKED BY:	JMR	*	*	*	*	*	*

LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS
BROWN COUNTY, WISCONSIN

SCALE: VARIES

TITLE SHEET

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851


SHEET NO. 1

LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS


3688 LIME KILN ROAD
DE PERE, WI
BROWN COUNTY

OFFICE USE ONLY

LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS



NTS



SITE VICINITY MAP

LEGEND

- EXISTING CONTOURS (500 / 499)
- PROPOSED CONTOURS (500 / 499)
- PROPOSED CONCRETE
- EXISTING CONCRETE
- PROPOSED ASPHALT
- COMPACTED FILL
- PROPOSED GRAVEL DRIVE
- IN–PLACE EARTH LINER
- COMPACTED CLAY LINER
- EXISTING BUILDING
- PROPOSED BUILDING
- PRESSURE TRANSFER PIPE
- GRAVITY TRANSFER PIPE
- TILE LINE
- SILT FENCE
- BALE DIVERSION
- ELECTRIC LINE
- WL — WETLAND (DELINEATED)
- DITCH CHECK
- TP — TEST PIT
- W — WELL
- BENCH MARK

NO REPRESENTATION IS MADE BY ROACH & ASSOCIATES AS TO THE EXISTENCE OR NONEXISTENCE OF UNDERGROUND HAZARDS. PRIOR TO THE START OF CONSTRUCTION THE OWNERS OF UTILITIES MUST BE NOTIFIED OF THE PENDING CONSTRUCTION. CONTRACTOR WILL BE LIABLE FOR DAMAGES RESULTING FROM CONSTRUCTION ACTIVITIES. (CALL DIGGERS HOTLINE)

PLAN TABLE OF CONTENTS

SHEET #	DESCRIPTION
1	TITLE SHEET
2	SITE PLAN
3	WASTE STORAGE FACILITY PLAN
4	WASTE STORAGE FACILITY PROFILES
	1: PLAN – WATERSTOP PLACEMENT
	2: PROFILE – WASTE STORAGE FACILITY
	3: PROFILE – WASTE STORAGE FACILITY
	4: 5" CONCRETE DETAIL
	5: 7" CONCRETE DETAIL
5	DETENTION BASIN PLAN AND PROFILES
	1: PLAN – DETENTION BASIN
	2: PROFILE – DETENTION BASIN
	3: PROFILE – DETENTION BASIN
	4: PROFILE – DETENTION BASIN
	5: 5" CONCRETE DETAIL
	6: 7" CONCRETE DETAIL
	7: CONCRETE CONNECTION DETAIL
6	WASTE TRANSFER PIPE #1 PLAN AND PROFILE
	1: PLAN – WASTE TRANSFER PIPE #1
	2: PROFILE – WASTE TRANSFER PIPE #1
	3: ALTERNATE PIPE MATERIALS
	4: MANHOLE @ STA: 11+00 DETAIL
	5: PIPE TRENCH DETAIL
7	WASTE TRANSFER PIPE #2 PLAN AND PROFILE
	1: PLAN – WASTE TRANSFER PIPE #2
	2: PROFILE – WASTE TRANSFER PIPE #2
	3: LINER PENETRATION DETAIL
	4: TANK PENETRATION DETAIL
	5: DOUBLE CLEANOUT DETAIL
	6: 4–FT MANHOLE DETAIL
8	CONSTRUCTION DETAILS
	1: WATERSTOP JOINT DETAIL
	2: WATERSTOP INSTALLATION DETAIL
	3: DEPTH GAUGE DETAIL
	4: FENCE DETAIL
	5: PIPE PENETRATION DETAIL
E1.0	CONSTRUCTION SITE EROSION CONTROL PLAN
E1.1	EROSION CONTROL DETAILS
	1: SEEDING PLAN
	2: TRACKING PAD
	3: FILTER SOCK DETAIL
	4: CONSTRUCTION SCHEDULE
	5: CUT & FILL QUANTITIES
	6: EROSION CONTROL NOTES
	7: SOIL LOSS & SEDIMENT DISCHARGE CALCULATIONS

To the best of my professional knowledge, judgment and belief, this design and these construction plans 2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS, meet the criteria, standards and specifications outlined in USDA Natural Resources Conservation Service Field Office Technical Guide, Section IV, Standards 313(10/17), 522(10/12), and 634(1/14), Spec.'s 4(10/12), 004(10/17), 204(10/12) and 634(8/16)

_____ Date _____

ENGINEER:

ROACH & ASSOCIATES, LLC
856 N. MAIN ST., SEYMOUR, WI 54165
PHONE: 920–833–6340

		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	12/06/2017	*	*	*	*	*	*
DRAWN BY:	TJS	*	*	*	*	*	*
CHECKED BY:	JMR	*	*	*	*	*	*


LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS
BROWN COUNTY, WISCONSIN

SCALE: VARIES

TITLE SHEET

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920–833–6340 Fax: 920–833–9851

SHEET NO. 1



WSF: CUT & FILL BALANCE (CU.YD.)		
FILL		-28,056.4
TOPSOIL		-11,446.4
CUT	37,748.5	
7" CONCRETE	3,111.3	
5" CONCRETE	969.2	
SUBTOTALS	41,829.0	-39,502.8
TOTAL-SURPLUS	2,326.4	

DB: CUT & FILL BALANCE (CU.YD.)		
FILL		-112.5
TOPSOIL		-376.4
CUT	173.7	
7" CONCRETE	79.0	
5" CONCRETE	31.0	
SUBTOTALS	283.7	-488.9
TOTAL-SHORT FALL		-205.2

		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	12/06/2017	*	*	*	*	*	*
DRAWN BY:	TJS	*	*	*	*	*	*
CHECKED BY:	JMR	*	*	*	*	*	*

LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS
BROWN COUNTY, WISCONSIN

SCALE
1"=60'

SITE PLAN

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO.
2

N

2/4

18" PVC PIPE
DETAIL 1/6

R250'

BERM ELEVATION
720.0-FT

FENCE
DETAIL 4/8

4.0:1

20'

337'-10"

2.5:1

56,844 SQ.FT
5" CONCRETE DETAIL 4/4

LINER PENETRATION
DETAIL 3/7

58'-6"

275'-10"

266'-8"

36'-6"

30'

20'

28'

SUMP
EL: 705.6

5:1

3,776 SQ.FT.
5" CONCRETE
DETAIL 4/4

2,185 SQ.FT.
5" CONCRETE
DETAIL 4/4

9.2:1

5.6:1

108'-2"

CURB STAFF GAUGE
DETAIL 3/8

MOL EL: 718.36
194,475 SQ.FT.
14,749,062 GALLONS

247'-11"

2,484 SQ.FT.
7" CONCRETE (RAMP)
DETAIL 5/4

20'

50-FT SETBACK

DELINEATED WETLAND

FLOOR ELEVATION
706.6-FT

141,524 SQ.FT.
7" CONCRETE (FLOOR)
DETAIL 5/4

5" CONCRETE DETAIL 4/4

BERM ELEVATION
720.0-FT

4.0:1

2.5:1

20'

3/4

196'-6"

146'-3"

545'

205'

LINER PENETRATION
DETAIL 3/7

314'-11½"

15" PVC PIPE
DETAIL 1/7

CORE TRENCH DETAIL 2/4

5" CONCRETE DETAIL 4/4

BERM ELEVATION
720.0-FT

612'

20'

2.5:1

4.0:1

2/4

		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	12/06/2017	*	*	*	*	*	*
DRAWN BY:	TJS	*	*	*	*	*	*
CHECKED BY:	JMR	*	*	*	*	*	*


LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS
BROWN COUNTY, WISCONSIN

SCALE
1"=30'


WASTE STORAGE FACILITY PLAN

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO.
3



1 / 4 PLAN - WATERSTOP PLACEMENT
SCALE 1" = 60'




GENERAL CONSTRUCTION NOTES:

1. CONCRETE IS TO BE MIXED AND PLACED ACCORDING TO SPEC. 4 AND SHALL BE CONSOLIDATED AS NECESSARY TO INSURE DENSE CONCRETE
2. JOINTS, IF USED, ARE TO BE SPACED AS SPECIFIED ELSEWHERE
3. WHITE CURING COMPOUND SHALL BE APPLIED TO CONCRETE AS SOON AS THE CONCRETE CAN BE WALKED ON.
4. SITE PREPARATION: REMOVE ALL ORGANIC AND UNCOMPACTED MATERIAL BEFORE PLACING SUBGRADE.
5. SUB-LINER IS TO BE CLEAN, COMPACTED, MINERAL SOILS WITH GREATER THAN OR EQUAL TO 40% FINES PASSING A #200 SIEVE, AND A PI GREATER THAN OR EQUAL TO 12. DAMPEN THE SUB-LINER BEFORE THE CONCRETE IS POURED.
6. METAL CHAIRS, METAL HANGERS, METAL SPACERS, CONCRETE SPACERS OR PLASTIC CHAIRS SHALL BE USED TO SUPPORT THE REINFORCEMENT. ANY METAL SUPPORTING DEVICES SHALL HAVE A PROTECTIVE COATING, BARRIER, OR FINISH BETWEEN THE REINFORCING STEEL AND THE SUPPORT AND/OR BETWEEN THE GROUND AND THE SUPPORT, IF THE SUPPORT IS NOT FULLY ENCASED IN CONCRETE. THE COATING, BARRIER, OR FINISH CAN BE HOT DIP GALVANIZING, EPOXY, PLASTIC, OR STAINLESS STEEL. CONCRETE CHAIRS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH EQUAL TO, OR GREATER THAN, THAT OF THE CONCRETE BEING PLACED.
7. #4 LAP = 16"

QUANTITIES:

	LOCATION OF SLAB – WSF SIDE SLOPES
SLAB AREA –	62,805 SQ. FT.
REBARS: (#4 @ 15" O.C., EACH WAY, 1.71FT/FT2)	107,397 LIN.FT.
CONCRETE SLAB (5" SLAB – 1.55 CU. YD. PER 100 SQ. FT.)	970 CU.YD.
WHITE CURING COMPOUND SQ.FT. (ASTM C-309, TYPE 2)	62,805 SQ. FT.

4 / 4 5" CONCRETE DETAIL
NTS




GENERAL CONSTRUCTION NOTES:

1. CONCRETE IS TO BE MIXED AND PLACED ACCORDING TO SPEC. 4 AND SHALL BE CONSOLIDATED AS NECESSARY TO INSURE DENSE CONCRETE
2. JOINTS, IF USED, ARE TO BE SPACED AS SPECIFIED ELSEWHERE
3. WHITE CURING COMPOUND SHALL BE APPLIED TO CONCRETE AS SOON AS THE CONCRETE CAN BE WALKED ON.
4. SITE PREPARATION: REMOVE ALL ORGANIC AND UNCOMPACTED MATERIAL BEFORE PLACING SUBGRADE.
5. SUB-LINER IS TO BE CLEAN, COMPACTED, MINERAL SOILS WITH GREATER THAN OR EQUAL TO 40% FINES PASSING A #200 SIEVE AND A PI GREATER THAN OR EQUAL TO 12. DAMPEN THE SUB-LINER BEFORE THE CONCRETE IS POURED.
6. METAL CHAIRS, METAL HANGERS, METAL SPACERS, CONCRETE SPACERS OR PLASTIC CHAIRS SHALL BE USED TO SUPPORT THE REINFORCEMENT. ANY METAL SUPPORTING DEVICES SHALL HAVE A PROTECTIVE COATING, BARRIER, OR FINISH BETWEEN THE REINFORCING STEEL AND THE SUPPORT AND/OR BETWEEN THE GROUND AND THE SUPPORT, IF THE SUPPORT IS NOT FULLY ENCASED IN CONCRETE. THE COATING, BARRIER, OR FINISH CAN BE HOT DIP GALVANIZING, EPOXY, PLASTIC, OR STAINLESS STEEL. CONCRETE CHAIRS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH EQUAL TO, OR GREATER THAN, THAT OF THE CONCRETE BEING PLACED.
7. #5 LAP = 20"


QUANTITIES:

	LOCATION OF SLAB – WSF RAMP, WSF FLOOR AND TRANSFER APRONS
SLAB AREA –	144,008 SQ. FT.
REBARS: (#5 @ 15" O.C., EACH WAY, 1.74 FT/FT2	250,574 LIN.FT.
CONCRETE SLAB (7" SLAB– 2.16 CU. YD. PER 100 SQ. FT.)	3,112 CU.YD.
WHITE CURING COMPOUND SQ.FT. (ASTM C-309, TYPE 2)	144,008 SQ. FT.

5 / 4 7" CONCRETE DETAIL
NTS



2 / 4 PROFILE - WASTE STORAGE FACILITY
HORIZONTAL SCALE 1" = 30'
VERTICAL SCALE 1" = 4'



3 / 4 PROFILE - WASTE STORAGE FACILITY
HORIZONTAL SCALE 1" = 30'
VERTICAL SCALE 1" = 4'

		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	12/06/2017	*	*	*	*	*	*
DRAWN BY:	TJS	*	*	*	*	*	*
CHECKED BY:	JMR	*	*	*	*	*	*


LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS
BROWN COUNTY, WISCONSIN

SCALE: VARIES


WASTE STORAGE FACILITY PROFILES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851


SHEET NO. 4



1 5 PLAN - DETENTION BASIN
SCALE 1" = 10'




2 5 PROFILE - DETENTION BASIN
HORIZONTAL SCALE 1" = 20'
VERTICAL SCALE 1" = 2'




NOTES:
1. ACCEPTABLE HYDROPHILIC SEALANT; SIKASWELL TYPE A, SIKASWELL TYPE E, LEAKMASTER LV-1

7 5 CONCRETE CONNECTION DETAIL
NTS




NOTES:
1) SLOPE VARIES BETWEEN HORIZONTAL AND 10%
2) SLOPE VARIES BETWEEN 3.4% AND 10%

3 5 PROFILE - DETENTION BASIN
HORIZONTAL SCALE 1" = 20'
VERTICAL SCALE 1" = 2'



NOTES:
1) SLOPE VARIES BETWEEN 20% AND 28%
2) SLOPE VARIES BETWEEN 16% AND 28%

4 5 PROFILE - DETENTION BASIN
HORIZONTAL SCALE 1" = 20'
VERTICAL SCALE 1" = 2'



TYPICAL SECTION

GENERAL CONSTRUCTION NOTES:


1. CONCRETE IS TO BE MIXED AND PLACED ACCORDING TO SPEC. 4 AND SHALL BE CONSOLIDATED AS NECESSARY TO INSURE DENSE CONCRETE
2. JOINTS, IF USED, ARE TO BE SPACED AS SPECIFIED ELSEWHERE
3. WHITE CURING COMPOUND SHALL BE APPLIED TO CONCRETE AS SOON AS THE CONCRETE CAN BE WALKED ON.
4. SITE PREPARATION: REMOVE ALL ORGANIC AND UNCOMPACTED MATERIAL BEFORE PLACING SUB-LINER.
5. SUB-LINER IS TO BE CLEAN, COMPACTED, MINERAL SOILS WITH GREATER THAN OR EQUAL TO 40% FINES PASSING A #200 SIEVE AND A PI GREATER THAN OR EQUAL TO 12. DAMPEN THE SUB-LINER BEFORE THE CONCRETE IS POURED.
6. METAL CHAIRS, METAL HANGERS, METAL SPACERS, CONCRETE SPACERS OR PLASTIC CHAIRS SHALL BE USED TO SUPPORT THE REINFORCEMENT. ANY METAL SUPPORTING DEVICES SHALL HAVE A PROTECTIVE COATING, BARRIER, OR FINISH BETWEEN THE REINFORCING STEEL AND THE SUPPORT AND/OR BETWEEN THE GROUND AND THE SUPPORT, IF THE SUPPORT IS NOT FULLY ENCASED IN CONCRETE. THE COATING, BARRIER, OR FINISH CAN BE HOT DIP GALVANIZING, EPOXY, PLASTIC, OR STAINLESS STEEL. CONCRETE CHAIRS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH EQUAL TO, OR GREATER THAN, THAT OF THE CONCRETE BEING PLACED.

7 #4 LAP = 16"

QUANTITIES: LOCATION OF SLAB – DETENTION BASIN

SLAB AREA –	2,000 SQ. FT.
REBARS: (#4 @ 18" O.C., EACH WAY 1.42 LF/SQ.FT.)	2,840 LIN.FT.
CONCRETE SLAB:	31 CU.YD.
WHITE CURING COMPOUND SQ.FT. (ASTM C-309, TYPE 2)	2,000 SQ. FT.

5 5 5" CONCRETE DETAIL
NTS



TYPICAL SECTION

GENERAL CONSTRUCTION NOTES:

1. CONCRETE IS TO BE MIXED AND PLACED ACCORDING TO SPEC. 4 AND SHALL BE CONSOLIDATED AS NECESSARY TO INSURE DENSE CONCRETE
2. JOINTS, IF USED, ARE TO BE SPACED AS SPECIFIED ELSEWHERE
3. WHITE CURING COMPOUND SHALL BE APPLIED TO CONCRETE AS SOON AS THE CONCRETE CAN BE WALKED ON.
4. SITE PREPARATION: REMOVE ALL ORGANIC AND UNCOMPACTED MATERIAL BEFORE PLACING SUB-LINER.
5. SUB-LINER IS TO BE CLEAN, COMPACTED, MINERAL SOILS WITH GREATER THAN OR EQUAL TO 20% FINES PASSING A #200 SIEVE AND A PI GREATER THAN OR EQUAL TO 12. DAMPEN THE SUB-LINER BEFORE THE CONCRETE IS POURED.
6. METAL CHAIRS, METAL HANGERS, METAL SPACERS, CONCRETE SPACERS OR PLASTIC CHAIRS SHALL BE USED TO SUPPORT THE REINFORCEMENT. ANY METAL SUPPORTING DEVICES SHALL HAVE A PROTECTIVE COATING, BARRIER, OR FINISH BETWEEN THE REINFORCING STEEL AND THE SUPPORT AND/OR BETWEEN THE GROUND AND THE SUPPORT, IF THE SUPPORT IS NOT FULLY ENCASED IN CONCRETE. THE COATING, BARRIER, OR FINISH CAN BE HOT DIP GALVANIZING, EPOXY, PLASTIC, OR STAINLESS STEEL. CONCRETE CHAIRS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH EQUAL TO, OR GREATER THAN, THAT OF THE CONCRETE BEING PLACED.
7. #4 LAP = 16"

QUANTITIES: LOCATION OF SLAB – DETENTION BASIN

SLAB AREA –	3,650 SQ. FT.
REBARS: (#4 @ 15" O.C., EACH WAY, 1.71LF/SQ.FT.)	6,242 LIN.FT.
CONCRETE SLAB	79 CU.YD.
WHITE CURING COMPOUND SQ.FT. (ASTM C-309, TYPE 2)	3,650 SQ. FT.

6 5 7" CONCRETE DETAIL
NTS

		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	12/06/2017	*	*	*	*	*	*
DRAWN BY:	TJS	*	*	*	*	*	*
CHECKED BY:	JMR	*	*	*	*	*	*


LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS
BROWN COUNTY, WISCONSIN

SCALE: VARIES

DETENTION BASIN PLAN AND PROFILES

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851


SHEET NO. 5




1 6 PLAN - WASTE TRANSFER PIPE #1
SCALE 1" = 40'

TABLE 1: GRAVITY PIPELINES (INCLUDING ABRASIVE MATERIALS)				
SIZE	MATERIAL	SPECIFICATION	JOINT PERFORMANCE SPECS	JOINT FITTING SPEC
4"–10"	HDPE	AASHTO M252, TYPE S	ASTM D3212 (10.8 PSI)	F2306/F477)
12"–60"	HDPE	AASHTO M294, TYPE S OR ASTM F2306	ASTM D3212 (10.8 PSI)	F2306/F477)
18"–48"	PVC	ASTM F679	ASTM D3212, D3139, D2672	ASTM F679
3"–15"	PVC	ASTM D3034 (SDR35)	ASTM D3212, D3139, D2672	ASTM D3034
1/8"–36"	PVC	ASTM D2241 (SDR32.5)	ASTM D3212, D3139, D2672	ASTM D2241
PIPE JOINTS AND FITTINGS MUST MEET THE DESIGNATED MAXIMUM OPERATING PRESSURE.				
OTHER JOINTS AND METAL/CAST FITTINGS MAY BE USED IF PRESSURE RATING OF FITTING IS GREATER THAN PRESSURE RATING OF THE PIPE TO BE INSTALLED.				

3 6 ALTERNATE PIPE MATERIALS




2 6 PROFILE - WASTE TRANSFER PIPE #1
HORIZONTAL SCALE 1" = 40'
VERTICAL SCALE 1" = 5'



NOTES:

1. FOR ALL PIPE PENETRATIONS USE CAST IN PLACE ASTM C-923 PIPE CONNECTOR
2. MANHOLE IS TO BE ASTM C-478 MONOLITHICALLY POURED WITH THE BASE
3. NEENAH FOUNDRY MANHOLE FRAME R-1792 OR EQUIVALENT
4. GRATE CONSTRUCTED OF #4 REBAR, WELDED 6-INCHES ON CENTER OR EQUIVALENT
5. ACCEPTABLE HYDROPHILIC SEALANT; SIKASWELL TYPE A, SIKASWELL TYPE E, LEAKMASTER LV-1

4 6 MANHOLE @ STA: 11+00 DETAIL
SCALE 1" = 2'



PIPE BEDDING AND BACKFILL NOTES:

1. MINIMUM PIPE COVER TO BE 4 FT.
2. BED THE TRANSFER PIPE WITH CLEAN, PIT-RUN, SAND/GRAVEL COMPACTED IN 4-INCH LIFTS TO 6" ABOVE TOP OF PIPE.

5 6 PIPE TRENCH DETAIL
NTS

		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	12/06/2017	*	*	*	*	*	*
DRAWN BY:	TJS	*	*	*	*	*	*
CHECKED BY:	JMR	*	*	*	*	*	*


LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS
BROWN COUNTY, WISCONSIN

SCALE: VARIES


WASTE TRANSFER PIPE #1
PLAN AND PROFILE

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851


SHEET NO. 6




1/7 PLAN - WASTE TRANSFER PIPE #2
SCALE 1" = 20'



5/7 DOUBLE CLEANOUT DETAIL
NTS





2/7 PROFILE - WASTE TRANSFER PIPE #2
HORIZONTAL SCALE 1" = 20'
VERTICAL SCALE 1" = 4'




NOTES:
1. BED THE TRANSFER PIPE WITH CLEAN, PIT-RUN SAND-GRAVEL COMPACTED IN 4 IN. LIFTS TO 6" ABOVE TOP OF PIPE FROM THE DETENTION BASIN TO THE EMBANKMENT CENTERLINE.
2. FROM THE EMBANKMENT CENTERLINE TO THE PIPE OUTLET, THE PIPE BEDDING AND TRENCH BACKFILL MATERIAL SHALL MATCH THE STORAGE FACILITY DESIGN. THE PERFORMANCE AND INTEGRITY OF ALL LINERS SHALL BE MAINTAINED.
3. THE SECTION OF PIPE THAT PENETRATES THE WSF LINER SHALL BE A MINIMUM OF 10 FT. IN LENGTH
4. JOINTS WITHIN 25 FT. OF THE PENETRATION SHALL HAVE A MECHANICAL A/O CONCRETE RESTRAINT
5. ACCEPTABLE HYDROPHILIC SEALANT: SIKASWELL TYPE A, SIKASWELL TYPE E, LEAKMASTER LV-1

3/7 LINER PENETRATION DETAIL
NTS






4/7 TANK PENETRATION DETAIL
NTS



NOTE: PLAN VIEW SHOWN WITH OPTIONAL FLOWLINES



SPECIFICATIONS:

* MANUFACTURED TO ASTM C-478 SPECIFICATIONS
* CONCRETE STRENGTH - 4000 P.S.I.
* STEEL DESIGN IN ACCORDANCE WITH ASTM C-478
* ALL REINFORCING DESIGNED FOR 1" MIN. COVER
* STEP - STEEL, PLASTIC COATED, 16" C-C
* EXTENDED MONOLITHIC BASE SECTION BUILT PER PLAN DIMENSIONS AND SPECIFICATIONS BY SPECIAL ORDER
* PIPE TO MANHOLE BOOT SEAL ACCOMODATES 2" THROUGH 18" PIPE, CALL FOR SPECIAL LARGER PIPE SIZING
* FLOWLINES AVAILABLE UPON REQUEST
* 48" DIAMETER - 890 LBS./VERTICAL FT.

6/7 4-FT MANHOLE DETAIL
NTS

COUNTY MATERIALS CORPORATION
County Materials Corporation
240 Hwy 29 West • PO Box 130 • Marathon, WI 54448-0130
(715) 443-6162 • fax (715) 443-2318 • toll free (888) 443-6162
www.countymaterials.com

Drawing #: B2
Date: 0109

Sanitary Sewer Systems
Standard Sanitary Manhole

		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	12/06/2017	*	*	*	*	*	*
DRAWN BY:	TJS	*	*	*	*	*	*
CHECKED BY:	JMR	*	*	*	*	*	*

LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS
BROWN COUNTY, WISCONSIN

SCALE: VARIES

WASTE TRANSFER PIPE #2
PLAN AND PROFILE


Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 7

CONSTRUCTION NOTES

1. FACTORY PREFABRICATED CORNERS AND TRANSITIONS SHALL BE USED, LEAVING ONLY STRAIGHT BUTT JOINT SPLICES FOR FIELD WELDING.
2. SEE DETAIL FOR PREFABRICATED TRANSITIONS NEEDED.
3. SEE JOINT PLAN, SHEET 8, FOR LOCATIONS AND DETAILS OF JOINTS
4. PROVIDE FACTORY WELDED WATERSTOP INTERSECTIONS AS SHOWN.
5. WATERSTOP IS TO BE MANUFACTURED PVC, TPE, OR PE, WITH A MINIMUM WEB THICKNESS OF 3/8".
6. ACCEPTABLE MODELS: GREENSTREAK 706, 717, 779, BOMETALS RCB-638LB, RCB-612, RCB-638NT, DURAJOINT TYPE 9.
7. EMBEDDED WATERSTOPS MAY NOT BE WELDED OR JOINED TO OTHER WATERSTOPS OF DIFFERENT SIZE, CONFIGURATION, OR MATERIAL.


QUANTITIES
6" WATERSTOP – 3,740 LIN.FT.




A. TYPICAL WATERSTOP CROSS SECTION (BOMETALS RCB-638NT SHOWN)

B. FLAT CROSS
QUANTITY: 9


C. FLAT TEE
QUANTITY: 3




D. CUSTOM CORNER
QUANTITY: 1




E. CUSTOM CORNER
QUANTITY: 1




F. CUSTOM CORNER
QUANTITY: 1




G. CUSTOM CORNER
QUANTITY: 1




H. CUSTOM CORNER
QUANTITY: 1



I. CUSTOM CORNER
QUANTITY: 1




J. CUSTOM CORNER
QUANTITY: 1




K. CUSTOM CORNER
QUANTITY: 1

1/8 WATERSTOP JOINT DETAIL
NTS



CROSS-SECTION OF WATERSTOP CONTROL JOINT
LOAD BEARING

NOTE:
SLAB THICKNESS AT ALL CONTROL JOINTS TO BE 8"



CROSS-SECTION OF WATERSTOP CONTROL JOINT
NON-LOAD BEARING

INSTALLATION:
A. CENTER THE WATERSTOP ON THE JOINT.

B. SECURE THE WATERSTOP ALONG ITS LENGTH AT THE CENTER BULB AND SUFFICIENTLY AT THE WEB TO HOLD IT IN PLACE.


C. PLACE CONCRETE WITHOUT DISPLACING THE WATERSTOP.

D. THOROUGHLY VIBRATE CONCRETE AROUND THE WATERSTOP TO PREVENT VOIDS.


E. AFTER THE FIRST POUR, CLEAN THE UNEMBEDDED WATERSTOP WEB TO INSURE FULL CONTACT WITH THE SECOND POUR OF CONCRETE.

F. KEEP THE CENTER BULB UNEMBEDDED AT THE JOINT CENTERLINE.

2/8 WATERSTOP INSTALLATION DETAIL
NTS




GATE SECTION



SEE NOTE 5

CORNER POST ASSEMBLY



SEE NOTE 6


PULL POST ASSEMBLY

QUANTITIES


TOTAL LENGTH OF FENCE	1,852 LIN. FT.
NUMBER OF CORNERS	5 EA.
NUMBER OF PULL POST ASSEMBLIES	0 EA.
CORNER POSTS (5 1/2" X 8')	7 EA.
BRACE POSTS (5" X 7')	12 EA.
HORIZONTAL BRACES (3" X 6 1/2')	12 EA.
LINE POSTS	112 EA.
WIRE FENCE (12-1/2 GAGE)	14,812 LIN. FT

NOTES
1. USE PRESSURE TREATED POSTS WITH BRACING AT THE CORNERS AND GATES. STEEL POSTS 6.5 FEET LONG MAY BE USED FOR LINE POSTS
2. MAXIMUM POST SPACING IS 16.5 FEET
3. WOVEN OR WELDED WIRE TO BE A MINIMUM 12-1/2 GAGE NON-CLIMB TYPE WITH 2"X4" OPENINGS OR CYCLONE DIAMOND SHAPE
4. FENCE HEIGHT TO BE A MINIMUM OF 48"
5. CORNER POST ASSEMBLIES NEEDED AT CORNERS OF DEFINITE ANGLES (NOT JUST 90°)
6. PULL POST ASSEMBLY NEEDED EVERY 660 FEET.

4/8 FENCE DETAIL
NTS




PLAN VIEW



SECTION A-A


QUANTITIES

CONCRETE (.0164 CU.YDS. PER LIN.FT.)	2 CU.YD.
#4 REBAR	124 FT.



SECTION B-B

NOTE: ALL STEEL SHALL BE TIED PRIOR TO POURING



EPOXY COATED #4 BAR, 24" LONG, CENTER OF BEND 8" FROM END

NOTE
INSTALL MARKERS AT THE FOLLOWING ELEVATIONS:
707.6, 708.6, 709.6, 710.6, 711.6, 712.6, 713.6, 714.6, 715.6, 716.6, 717.6
MOL - EL: 718.36
MOS - EL: 719.00

3/8 DEPTH GAUGE DETAIL
NTS

		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	12/06/2017	*	*	*	*	*	*
DRAWN BY:	TJS	*	*	*	*	*	*
CHECKED BY:	JMR	*	*	*	*	*	*

LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS
BROWN COUNTY, WISCONSIN

SCALE: VARIES

CONSTRUCTION DETAILS

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. 8

		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	12/06/2017	*	*	*	*	*	*
DRAWN BY:	TJS	*	*	*	*	*	*
CHECKED BY:	JMR	*	*	*	*	*	*

LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS
BROWN COUNTY, WISCONSIN

SCALE: VARIES

CONSTRUCTION SITE EROSION CONTROL PLAN

Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851

SHEET NO. E1.0

SEEDING DATES: NORTH PLANTING ZONE

TIME PERIOD	DATES			TYPE OF SEEDING
Spring	4/15	through	6/1	Permanent
Summer	6/1	through	8/1	Temporary *
Late Summer	8/1	through	8/21	Permanent
Fall	8/21	through	10/31	Temporary *
Late Fall	11/1	through	snow cover	Dormant
Winter	snow cover	through	Spring Seeding	Frost Seed Not Allowed

MATERIALS

If no soil test is available, apply a minimum of 150 pounds of 20–10–10 fertilizer per acre. This is equivalent to 30 pounds nitrogen (N), 15 pounds phosphate (P_2O_5), and 15 pounds potash (K_2O) per acre. Apply two tons/ac of 80–89 lime or equivalent.

Two (2) tons/ac of 80–89 lime or equivalent from UW–EXT A3671

Lime Quality	Tons/AC.
40–49	3.9
50–59	3.2
60–69	2.7
70–79	2.3
90–99	1.9
100+	1.6

PERMANENT AND DORMANT SEEDING MIX

MINIMUM PURE LIVE SEED (PLS)[1] RATE PER ACRE AND TOTAL POUNDS OF SEED NEEDED

SEEDING MIX 342–2		LOCATION ACRES 2.5		SEEDING MIX _____		LOCATION ACRES _____	
	SPECIES	RATE	POUNDS	SPECIES		RATE	POUNDS
	SMOOTH BROMEGRASS	15.0	37.5				
	ALFALFA	7	17.5				
	TIMOTHY	3	7.5				
**	OATS	65.5	164				

1. PLS = (% Germination X % Purity)
** Companion Crop

Additional native seeds may be required by permitting agencies. These additions are allowed.
Seed mixture shall meet all requirements of the WI weed laws.
Species identified as restricted or prohibited by law shall not be planted.
Certified seed shall be used, and the seeding rates will be based on pure live seed.
For dormant seedings, increase the seeds per square foot by 15%.

SEEDBED PREPARATION

Seedbed preparation shall immediately follow construction activities.
Prepare a fine, firm seedbed to a minimum depth of three inches. A seedbed is considered firm when a footprint penetrates 1/4 to 1/2 inch deep.

SEEDING

Inoculate legumes with the specific inoculum for the species in accordance with the manufacturer's recommendations. When using a hydroseeder, five times the recommended rate of inoculant shall be added to the hydroseeder. Inoculant shall not be mixed with liquid fertilizer.

Seed may be broadcast or drilled as appropriate to the site.
Seed, fertilize, and lime as soon as possible after construction.
Seeding perpendicular to direction of flow is required to limit erosion.
Seed grasses and legumes no more than 1/4 inch deep.
Consider seeding at a lower rate and making 2 passes to ensure more uniform distribution.

TEMPORARY SEEDING OPTIONS

Select one of the following species for temporary cover if:

1) The required seeds or plant stock are not available or
the normal permanent seeding period for the species has passed
Forage Sorghum – 1/2 bushel per acre (May 15–July 15)
Sorghum – Sudangrass Hybrid – 1 bushel per acre (May 15–July 15)
Sudangrass – 1 bushel per acre (May 15–July 15)
Winter Wheat – 2 bushels per acre (Aug 1–Oct 1)
Winter Cereal Rye – 2 bushels per acre (Aug 1–Oct 15)
Oats – 2 bushels per acre (Apr 1–Sept 1)
Annual Ryegrass – 20 Pounds per acre (Apr 1–Sept 1)

2) Triazine herbicide carryover will not allow establishment of permanent cover immediately.
Forage Sorghum – 1/2 Bushel per acre (May 15–July 15)
Sorghum – Sudangrass Hybrid – 1 Bushel per acre (May 15–July 15)
Sudangrass – 1 Bushel per acre (May 15–July 15)

DORMANT SEEDING

Seed is broadcast and incorporated, no–tilled, or drilled into the seedbed.
Seedbed preparations and conditions are similar to conventional seeding.

MULCHING

Below is a summary of WDNR Conservation Practice Standard 1058 – Mulching for Construction Sites. Please see CPS 1058 for complete details.
Site Preparation

- Soil surface shall be prepared prior to the application of mulch in order to achieve the desired purpose and to ensure optimum contact between soil and mulch. All areas to be mulched shall be reasonably free of rills and gullies.

Materials

- Mulch shall consist of natural biodegradable material such as plant residue (including but not limited to straw and hay), or other equivalent materials of sufficient dimension (depth or thickness) and durability to achieve the intended effect for the required time period.
- Straw and hay mulch that will be crimped shall have a minimum fiber length of 6 inches.
- Wood chips or wood bark shall only be used for sites that are not seeded.

Application Rate (for seeded areas)

- Mulch shall be placed loose and open enough to allow some sunlight to penetrate and air to circulate but still cover a minimum of 70% of the soil surface. Mulch shall be applied at a uniform rate of 1.5 to 2 tons per acre. This application results in a layer of 0.5 to 1.5 inches thick.


Mulch Anchoring Methods


- Crimping – Immediately after spreading, the mulch shall be anchored by a mulch crimper or equivalent device consisting of a series of dull flat discs with notched edges spaced approximately 8–inches apart. The mulch shall be impressed in the soil to a depth of 1 to 3 inches.
- Polypropylene Plastic, or Biodegradable Netting – Apply plastic netting over mulch application and staple according to manufacturer's recommendations.
- Tackifier – Tackifier shall be sprayed in conjunction with mulch or immediately after the mulch has been placed. Tackifiers must be selected from those that meet the WisDOT Erosion Control Product Acceptability List (PAL). Asphalt based products shall not be applied. Tackifiers shall be applied at the following minimum application rates per acre:
  - ** Latex–Base: mix 15 gallons of adhesive (or the manufacturer's recommended rate which ever is greater) and a minimum of 250 pounds of recycled newsprint (pulp) as a tracer with 375 gallons of water.
  - ** Guar Gum: mix 50 pounds of dry adhesive (or the manufacturer's recommended rate which ever is greater) and a minimum of 250 pounds of recycled newsprint (pulp) as a tracer with 1,300 gallons of water.
  - ** Other Tackifiers: (Hydrophilic Polymers) mix 100 pounds of dry adhesive (or the manufacturer's recommended rate which ever is greater) and a minimum of 250 pounds of recycled newsprint (pulp) as a tracer with 1,300 gallons of water.

1 E1.1 SEEDING PLAN

1. TRACKING PAD SHALL BE INSTALLED PRIOR TO CONSTRUCTION TRAFFIC.
2. TRACKING PAD SHALL BE INSTALLED TO THE FULL WIDTH OF THE EGRESS POINT.
3. TRACKING PAD SHALL BE 3" – 6" STONE WITH LESS THAN 10% FINES. 10:1 APPROACHES TO PADS MAY BE BREAKER–RUN STONE.
4. WHERE SATURATED CONDITIONS ARE EXPECTED, PAD SHALL BE UNDERLAIN BY TYPE I, WOVEN GEOTEXTILE. (WI–DOT TYPE 'R')
5. SURFACE WATER SHALL BE DIVERTED AWAY FROM TRACKING PAD OR CONVEYED THROUGH WITH A CULVERT.

VOLUME OF STONE (EA.) 45.5 TONS.
35 CU.YD.





2 E1.1 TRACKING PAD
NTS

JUNE 1 THROUGH AUG 1, 2018

1. INSTALL THREE TRACKING PADS[1]
2. INSTALL FILTER SOCK[2]
3. WSF2, WTP#1, WTP#2, DETENTION BASIN
   3.1. STRIP TOPSOIL & STOCKPILE[3]
   3.2. INITIAL GRADING
   3.3. ROUGH & FINAL GRADING. STABILIZE WITH CONCRETE.
   3.4. INSTALL TOPSOIL ON SLOPES AND PERMANENT SEEDING[4]

4 E1.1 CONSTRUCTION SCHEDULE

WSF: CUT & FILL BALANCE (CU.YD.)		
FILL		–28,056.4
TOPSOIL		–11,446.4
CUT	37,748.5	
7" CONCRETE	3,111.3	
5" CONCRETE	969.2	
SUBTOTALS	41,829.0	–39,502.8
TOTAL–SURPLUS	2,326.4	

DB: CUT & FILL BALANCE (CU.YD.)		
FILL		–112.5
TOPSOIL		–376.4
CUT	173.7	
7" CONCRETE	79.0	
5" CONCRETE	31.0	
SUBTOTALS	283.7	–488.9
TOTAL–SHORT FALL		–205.2

5 E1.1 CUT & FILL QUANTITIES

CONSTRUCTION SITE EROSION CONTROL NOTES

1. TRACKING PAD DETAIL 2/E1.1
2. FILTER SOCK DETAIL 3/E1.1
3. IF STOCKPILES WILL REMAIN INACTIVE FOR 7 DAYS OR LONGER, STABILIZE STOCKPILES WITH TEMPORARY SEEDING OF OATS AT A RATE OF 1 BUSHEL PER ACRE AND SURROUND STOCKPILES AS NEEDED WITH FILTER SOCK (DETAIL 3/E1.1)
4. PERMANENT SEED ACCORDING TO DETAIL 1/E1.1. INSTALL FILTER SOCK AT TOE OF SLOPE AT LOCATIONS SHOWN IN THE EROSION CONTROL PLAN, ACCORDING TO DETAIL 3/E1.1.
5. FILTER SOCK AS DITCH CHECK ACCORDING TO DETAIL 3/E1.1
6. STABILIZE AREAS OF FINAL GRADING WITHIN 7 DAYS OF REACHING FINAL GRADE
7. MAKE PROVISIONS FOR WATERING WITHIN THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.
8. PROVIDE ANTI–SCOUR PROTECTION AND MAINTAIN NON–EROSIVE FLOW DURING DEWATERING. PERFORM DEWATERING OF ACCUMULATED SURFACE RUNOFF IN ACCORDANCE WITH WDNR TECHNICAL STANDARD #1061. GROUNDWATER DEWATERING IS SUBJECT TO A WASTEWATER DISCHARGE PERMIT AND DNR HIGH CAPACITY WELL APPROVAL IF CUMULATIVE PUMP CAPACITY IS GREATER THAN 70 GPM.
9. INSPECTIONS SHALL BE MADE EVERY SEVEN (7) DAYS, OR WITHIN 24 HOURS OF A RAINFALL EVENT OF 0.50 INCHES OR GREATER. ANY PRACTICES THAT ARE DAMAGED OR NOT WORKING PROPERLY SHALL E REPAIRED BY THE END OF THE DAY AND RECORDED IN THE RECORDS BINDER. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED A HEIGHT OF ONE–HALF THE HEIGHT OF THE STRUCTURE. IN ADDITION, THE FOLLOWING MEASURE SHALL BE TAKEN:
   9.1. ALL SEEDED AREAS WILL BE RE–SEEDED AND MULCHED AS NECESSARY ACCORDING TO THE SPECIFICATIONS IN THE PLANNED PRACTICES TO MAINTAIN A VIGOROUS, DENSE VEGETATED COVER
   9.2. REMOVE SILT FENCE AND TEMPORARY STRUCTURES ONLY AFTER FINAL STABILIZATION AND VEGETATIVE COVER IS ESTABLISHED.
   9.3. AVOID THE USE OF FERTILIZERS AND PESTICIDES IN OR ADJACENT TO CHANNELS OR DITCHES
   9.4. CONSTRUCTION AND WASTE MATERIALS SHALL BE PROPERLY DISPOSED

6 E1.1 EROSION CONTROL NOTES

Soil Loss & Sediment Discharge Calculation Tool

for use on Construction Sites in the State of Wisconsin

WDNR Official Version 1.0 (05-15-2015)

WISCONSIN DEPT. OF NATURAL RESOURCES

YEAR 1

Developer: Ledgeview
Project: WSF2
Date: 12/5/2017
County: Brown
Version 1.0

Activity	Begin Date	End Date	Period % R	Annual R Factor	Sub Soil Texture	Soil Erodibility K Factor	Slope (%)	Slope Length (feet)	LS Factor	Land Cover C Factor	Soil loss A (tons/acre)	Sediment Control Practice	Sediment Discharge (tons/acre)
Bare Ground	6/1/2017	8/1/2017	43.1%	100	Silty Clay	0.28	3.0%	251	0.43	1.00	5.2	Manufactured Pex	2.4
End	8/1/2017	-----	-----	-----	-----	-----	3.0%	251	0.43	-----	-----		0.0
		-----	-----	-----	-----	-----	3.0%	251	0.43	-----	-----		0.0
		-----	-----	-----	-----	-----	3.0%	251	0.43	-----	-----		0.0
		-----	-----	-----	-----	-----	3.0%	0	-----	-----	-----		0.0
		-----	-----	-----	-----	-----	0.0%	0	-----	-----	-----		0.0
										TOTAL	5.2	TOTAL	2.4
												% Reduction Required	NONE

Notes:
See Help Page for further descriptions of variables and items in drop-down boxes.
The last land disturbing activity on each sheet must be 'End'. This is either 12 months from the start of construction or final stabilization.
For periods of construction that exceed 12 months, please demonstrate that 5 tons/acre/year is not exceeded in any given 12 month period.


NOTE: THIS TOOL ONLY ADDRESSED SOIL EROSION DUE TO SHEET FLOW. MEASURES TO CONTROL CHANNEL EROSION MAY ALSO BE REQUIRED TO MEET SEDIMENT DISCHARGE REQUIREMENTS.

Recommended Permanent Seeding Dates:
4/15-6/1 and 8/1-8/21 Turf, introduced grasses and legumes
Thaw-6/30 Native Grasses, forbs, and legumes

Designed By:	TJS
Date	12/5/2017

F:\Clients\Ledgeview Dairy\2017 WSF\CSECP\WSF2 soil,LossSediment,DischargeCalculationTool.xls

7 E1.1 SOIL LOSS & SEDIMENT DISCHARGE CALCULATIONS



PLAN VIEW FOR DITCH APPLICATION

FILTER SOCK CHECK DAM ESTIMATED QUANTITIES						
	V-DITCH[1]			TRAPEZOIDAL DITCH[2]		
	24" FILTER SOCK (INSTALLED HEIGHT 19")	12" FILTER SOCK STACKED (INSTALLED HEIGHT 19")	18" FILTER SOCK STACKED (INSTALLED HEIGHT 28")	24" FILTER SOCK (INSTALLED HEIGHT 19")	12" FILTER SOCK STACKED (INSTALLED HEIGHT 19")	18" FILTER SOCK STACKED (INSTALLED HEIGHT 29")
LENGTH(FT)	20	60	48	24	72	60


1. ESTIMATED QUANTITIES BASED ON 4:1 SIDE SLOPES. QUANTITIES WILL VARY BASED ON ACTUAL DITCH CONFIGURATION.
2. ESTIMATED QUANTITIES BASED ON 4FT BOTTOM WIDTH, 4 FT DEPTH, AND 4:1 SIDE SLOPES. QUANTITIES WILL VARY BASED ON ACTUAL DITCH CONFIGURATION.

FILTER SOCK SPACING FOR SLOPE APPLICATION				
SLOPE	8"	12"	18"	24"
2%	70'	80'	N/A	N/A
5%	30'	60'	80'	N/A
10%	20'	30'	70'	80'
6:1	N/A	20'	40'	55'
4:1	N/A	20'	30'	30'
3:1	N/A	N/A	20'	25'
2:1	N/A	N/A	20'	20'

N/A = NOT RECOMMENDED
SPACING NOT TO EXCEED 80'


FILTER SOCK SPACING FOR DITCH APPLICATION	
DITCH SLOPE	MAXIMUM FILTER SOCK SPACING
LESS THAN 2%	80'
2%	80'
3%	50'
4%	40'
5%	30'
6%	20'
GREATER THAN 6%	20'

BASED ON AN INSTALLED HEIGHT OF 19 INCHES. SEE TABLE ON EC-STR-6 FOR OTHER HEIGHTS.



SECTION A–A

SOCK HEIGHTS INSTALLED		
NOMINAL DIAMETER, D	INSTALLED HEIGHT OF SINGLE SOCK	INSTALLED HEIGHT OF STACKED SOCKS
8"	6.5"	N/A
12"	9.5"	19"
18"	14.5"	29"
24"	19"	38"



SECTION B–B

MINIMUM SPECIFICATION FOR FILTER MEDIA		
PROPERTY	UNITS	RANGE
pH	pH	5.0 - 8.5
MOISTURE CONTENT	% WET WEIGHT BASIS	< 60
ORGANIC MATTER CONTENT	% DRY WEIGHT BASIS	25 - 100
PHYSICAL CONTAMINANTS	% DRY WEIGHT BASIS	< 1
PARTICLE SIZE	% PASSING SELECTED MESH SIZE, DRY WEIGHT BASIS	2 INCH - 99% ½INCH - 50% - 50% MAX. PARTICLE SIZE 2 INCHES

NOTE: MANUFACTURER SPECIFICATION MAY BE SUBSTITUTED WITH THE APPROVAL OF ENGINEER.



FILTER SOCK JOINT DETAIL (FOR SLOPE APPLICATION ONLY)

FILTER SOCK STACKING DETAIL

3 E1.1 FILTER SOCK DETAIL
NTS

		REVISION DATE	BY	DESCRIPTION OF REVISION	REVISION DATE	BY	DESCRIPTION OF REVISION
DATE:	12/06/2017	*	*	*	*	*	*
DRAWN BY:	TJS	*	*	*	*	*	*
CHECKED BY:	JMR	*	*	*	*	*	*

LEDGEVIEW FARM, LLC
2017 WASTE STORAGE FACILITY AND RUNOFF MANAGEMENT SYSTEMS
BROWN COUNTY, WISCONSIN

SCALE: VARIES

EROSION CONTROL DETAILS


Roach & Associates, LLC
Dairy Business and Management Consulting
Environmental Engineering
856 North Main Street, Seymour, WI, 54165 PH: 920–833–6340 Fax: 920–833–9851

SHEET NO. E1.1

2017 Waste Storage Facility & Runoff Management Systems

for

Ledgeview Farm, LLC
3875 Dickinson Road
DePere, WI 54115



December 6, 2017

Prepared by

Roach & Associates, LLC
856 N. Main Street
Seymour, WI 54165

Roach & Associates, LLC

Dairy Business and Management Consulting
Environmental Engineering
856 N Main Street • Seymour, WI 54165 • Phone 920-833-6340 • Fax 920-833-9851

December 6, 2017

Jeff Kreider
Bureau of Watershed Management
Wisconsin Department of Natural Resources
PO Box 7921
Madison, WI 53707-7921

Re: Plans and Specifications
Waste Storage Facility and Leachate Management System
Ledgeview Farm, LLC

Mr. Kreider,

On behalf of Ledgeview Farm, LLC, we are submitting Plans and Specifications for a Waste Storage Facility and Leachate Management System. The proposed facilities have been designed based on Natural Resources Conservation Service, Field Office Technical Guide, Standards 313 Waste Storage Facility (10/17), 522 Pond Sealing or Lining-Concrete (10/17) and 634 Waste Transfer (1/14).

Please contact our office if there are any questions regarding this project or a need for further information.

Sincerely,

Richard Seas

Richard G. Seas, PE
Project Manager

CC: Ledgeview Farm, w/enclosure
Brown County LWCD, w/enclosure
Town of Ledgeview, w/enclosure

Ledgeview Farm, LLC
Table of Contents

	Page
Introduction and Design Rationale	1-2
Management Assessment	3-8
Site Assessment	9-14
Operation and Maintenance Plan	15-18
Construction Plan	19-20
Construction Verification and Documentation Plan	21-22

Attachments	**Exhibit**
Plat Map	1
Aerial Photo	2
Soil Map	3
Test Pit Logs	4
Laboratory Analysis of Soils	5
Wetland Determination and Concurrence	6
Well Construction Logs	7
Waste Generation and Storage Summary	8
Waste Transfer Pipe Design	9
Detention Basin Design and HEC-HMS Modeling Summary	10
Emergency Action Plan Summary	11
Referenced NRCS Standards and Wisconsin Construction Specifications	12
Authority of Inspector	13

Introduction and Design Rationale

Introduction and Design Rationale

Introduction

Ledgeview Farm, LLC (LF) is an existing dairy that conducts operations at two sites in the Town of Ledgeview, Brown County. The Headquarters Farm is located at 3875 Dickinson Road, De Pere, WI 54115 and the Heifer Farm is located at 3688 Lime Kiln Road, Green Bay, WI 54311. The proposed modifications, located at the Heifer Farm, include a new Waste Storage Facility (WSF 2) and Runoff Management Systems that will transfer leachate and runoff from the Feed Storage Area and an existing Animal Lot.

Design Criteria

The proposed improvements are based on Natural Resources Conservation Service (NRCS), Field Office Technical Guide (FOTG), Section IV Standards, Wisconsin Construction Specifications (WCS) and Wisconsin Administrative Codes. A list of Design Standards that may apply is found in Exhibit 12.

Operating Objectives

Waste Storage Facility 2 (WSF 2) will provide additional waste storage capacity that will eliminate the need for unconfined manure stacks at the production site and spreading manure on frozen ground during the winter months. The Runoff Management Systems will provide runoff controls for the Feed Storage Area (FSA) and the Y1 Yard at the Heifer Farm.

Project Description

The primary components of the proposed modifications are identified below. More detailed descriptions and operational procedures are presented in the appropriate sections of this submittal.

- LMS - Detention Basin, and Gravity Flow Waste Transfer Pipe
  - The Detention Basin liner will be reduced seepage concrete with waterstop.
  - Transfer pipe will be PVC
- Y1 Yard – Waste Transfer System
  - Transfer pipe will be PVC
- WSF 2 will have a reduced seepage concrete with waterstop liner.

The Waste Storage System (WSF 1 & WSF 2) will provide storage of manure and wastewater from dairy operations as well as collected runoff from the Heifer Farm FSA and Y1 Yard. Including an allowance for waste from future runoff controls, the average annual design storage period will be 291 days.

Site Investigations
Site investigations that were conducted by Brown County Land and Water Conservation Division (LWCD) and Roach & Associates, LLC (R&A) in 2017 were used for the design of the proposed improvements, including topographical survey, test pits and analysis of soil samples.

Waste Storage System
The storage volume of the proposed Waste Storage Facility W2 (WSF 2), when combined with the storage volume of the existing WSF 1, will provide an annual average storage period to 291 days at design conditions (expanded). The actual storage period will vary depending on the level of precipitation that occurs.

Project Schedule
Construction of the proposed improvements, including WSF 2, the Leachate Management System and the Y1 Yard Waste Transfer System, are planned for 2018.

Management Assessment

Management Assessment

Introduction

Ledgeview Farm, LLC (LF) is an existing dairy operation that has two production sites in the Town of Ledgeview, Brown County. The Headquarters Farm is located at 3875 Dickinson Road, De Pere, WI 54115 and the Heifer Farm is located at 3688 Lime Kiln Road, Green Bay, WI 54311(Exhibit 1).

Site Descriptions

An aerial photo of the Headquarters Farm production area is shown in Exhibit 2-1. The existing facilities are labeled and described as follows:

- L1 – Freestall Barn with Collection Channel
- L2 – Bedded Pack Heifer Barn
- L3 – Freestall Barn
- L4 – Freestall Barn
- L5 – Bedded Pack Heifer Barn
- L6 – Calf Barn
- Parlor – Milking Parlor and Holding Area
- T1 – Piston Pump Station
- Y1 – Heifer Feedlot – Concrete Yard
- WSF 1 – Existing Waste Storage Facility 1, Concrete and Earthen Liners
- Pit 1– Existing Waste Storage Facility, inactive
- Pit 2– Existing Waste Stacking Facility, inactive

An aerial photo of the Heifer Farm production area is shown in Exhibit 2-2. The existing facilities are labeled and described as follows:

- L1 – Heifer Barn 1
- L2 – Freestall Barn
- Y1 – Concrete Yard
- T1 – Concrete Yard Collection Basin
- Feed Storage Area

Intent and Purpose of the Proposed Project

Heifer Farm:

Ledgeview Farm, LLC proposes to construct a new Waste Storage Facility (WSF 2) and Runoff Management Systems for leachate and runoff. The Runoff Management Systems will include the Leachate Management System (LMS) for the Feed Storage Area (FSA) and the Waste Transfer System (WTS) for the Y1 Yard. The LMS is designed to collect and transfer leachate and runoff; the Y1 WTS will collect and transfer runoff and manure from the Y1 Yard. Waste from both systems will be transferred to the proposed WSF 2. The Management Assessment presents the design criteria and operating parameters for the 2018 Waste Storage Facility and Runoff Management Systems.

Components of the proposed improvements include:

- LMS - Detention Basin and gravity waste transfer pipe
  - The Detention Basin liner will be reduced seepage concrete with waterstop.
  - Transfer pipe will be PVC

- Y1 Waste Transfer System
  - Transfer pipe will be PVC
- Waste Storage Facility 2
  - The WSF 2 liner will be reduced seepage concrete with waterstop.

Waste Storage Facility 2 will be designed to receive waste from both sites, including waste from future Runoff Control Systems. Future Runoff Control Systems may be installed to collect waste and runoff from the FSA and Y1 Concrete Yard at the Headquarters Farm. While future Runoff Control Systems have not been designed, the design of the Waste Storage System includes an allowance for the projected design flows.

The design of the proposed 2018 WSF 2, Y1 Yard Manure Transfer System and LMS is based on Natural Resources Conservation Service (NRCS), Field Office Technical Guide (FOTG), Section IV Standards, Wisconsin Construction Specifications (WCS) and Wisconsin Administrative Code (Exhibit 12). The standards include:

- NRCS Standard 313 Waste Storage Facility (10/17)
- NRCS Standard 522 Pond Sealing or Lining – Concrete (10/17)
- NRCS Standard 634 Waste Transfer (1/14)
- WCS 4 Concrete (10/17)
- WCS 004 Embedded Expansive Waterstop (10/17)
- WCS 204 Earthfill for Waste Storage Facility (10/12)
- WCS 300 Clay Liner (3/16)
- WCS 634 Waste Transfer Pipe (8/16)
- NR 213 Lining of Industrial Lagoons and Design of Storage Structures
- NR 243 Animal Feeding Operations

Waste Storage Facility 2 will provide storage of wastes generated at the farm. Including an allowance for waste from future Runoff Control Systems, the Waste Storage System (WSF 1-2) will provide an average annual storage period of 291 days at design conditions (Exhibit 8-1).

Runoff Management Systems

Leachate Management System

The LMS will provide for the collection of leachate and runoff from the Heifer Farm Feed Storage Area (FSA) and transfer of the collected waste to WSF 2. The LMS will include a Detention Basin (DB) that will receive the leachate and runoff. The wastewater will flow by gravity to WSF 2 via PVC Waste Transfer Pipe (WTP).

Detention Basin

Leachate and runoff from the FSA will flow by gravity to the Detention Basin (DB), located in the southern part of the Heifer Farm production area (Construction Drawings Sheet 2). The Detention Basin (DB) is designed according to NRCS, FOTG, Section IV, Standards 313 Waste Storage Facility (10/17) and 522 Pond Sealing or Lining – Concrete (10/17), Table 2, column 1 criteria. The on-site soils to be used for the sub liner meet the requirements of NRCS, FOTG, Section IV, Standard 522 Pond Sealing or Lining – Concrete (10/17), Table 2A, column 3 (Site Assessment). The DB will also meet the requirements of NR 213 Lining of Industrial Lagoons and Design of Storage Structures.

The FSA and the adjacent tributary drainage area will generate 41,427 ft^3 (309,873 gallons) of runoff from a 25 year, 24 hour rainfall event (Exhibit 8-5). The peak flow rate will be 19.63 cfs (8,810 gpm). The maximum daily leachate volume will be 560 ft^3 (4,189 gallons) with an average flow rate of approximately 3 gpm (Exhibit 8-4). Therefore, the design daily flow will be 41,987 ft^3 (314,062 gallons) with a peak design flow of 19.64 cfs (8,813 gpm). The peak flow rate can be moderated by using the DB for flow equalization.

The DB has a design storage capacity of 6,598 ft^3 (49,353 gallons) (Exhibit 10-1). Based on a hydraulic analysis performed using HEC-HMS software, the staged storage provided by the DB will reduce the peak discharge to the 18 inch ASTM F 679 PVC gravity WTP to approximately 9.9 cfs (4,443 gpm) (Exhibit 10-2).

Detention Basin-WSF 2 Waste Transfer Pipe

The DB-WSF 2 WTP will be designed and constructed in accordance with NRCS, FOTG, Section IV, Standard 634 (1/14), Table 1 and WCS 634 Waste Transfer Pipe (8/16), Table 1 criteria for a gravity pipe. The WTP will be an ASTM F679 PVC pipe and will include water tight precast concrete (ASTM C-478) manholes that will function as clean-outs. While the spacing of the manholes exceeds the criteria, the waste to be transferred will have low solids so clean-outs are not required. Therefore, the spacing of the manholes is considered acceptable.

The hydraulic capacity of the DB-WSF 2 WTP will depend on the minimum difference in the design water surface elevations of the DB and WSF 2. The maximum allowable DB water elevation is 728 and the WSF 2 MOL is 718.36, a difference of approximately 9.6 feet. At the peak design discharge from the DB of 9.9 cfs (4,443 gpm), the head loss through the WTP will be 9.6 feet, equal to the difference in surface elevations verifying that the discharge will flow by gravity (Exhibit 9-1).

Y1 Waste Transfer System

Runoff from the Y1 Concrete Yard will flow across the surface of the yard to the Collection Basin (CB) and then flow by gravity to WSF 2 through the 15 inch Waste Transfer Pipe (WTP). The WTP will be designed and constructed in accordance with NRCS, FOTG, Section IV, Standard 634 (1/14), Table 1 and WCS 634 Waste Transfer Pipe (8/16), Table 1 criteria for a gravity pipe. The WTP will be an ASTM D3034 (SDR 35).

The hydraulic capacity of the WTP will depend on the minimum difference in the design water surface elevations of the CB and WSF 2. The CB Maximum Operating Level (MOL) is 725.9 and the WSF 2 MOL is 718.36, a difference of approximately 7.5 feet. At the peak design discharge from the CB of 6.28 cfs or 2,821 gpm (Exhibit 8-7), the head loss through the WTP will be 2.6 feet, less than the maximum difference in surface elevations verifying that the discharge will flow by gravity (Exhibit 9-2).

The peak flow of runoff from the Heifer Farm Y1 from a 25 year, 24 hour rainfall will be 6.28 cfs (2,821 gpm) (Exhibit 8-7). The hydraulic capacity of the WTP will be greater than 7.8 cfs (3,500 gpm) (Exhibit 9-2). Therefore, the WTP has the capacity to transfer the design peak flow from Y1 to WSF 2.

Waste Storage System

Waste Storage Facility 1 (WSF 1), located at the Headquarters Farm, is an existing facility with a concrete liner in the lower part of the facility and an earthen liner on the remainder.

The facility was evaluated in the WPDES Permit application and found to meet the intent of NRCS, FOTG, Section IV, Standard 313 Waste Storage Facility (1/14), Table 1, column 2 and Table 5, column 4 criteria. WSF 1 has a MOL marker and a ramp to provide access for removal of settled solids.

WSF 1 has a design waste storage volume at the Maximum Operating Level (MOL) of 669,334 ft^3 (5,006,618 gallons) (Exhibit 8-1). The MOL volume includes 111,303 ft^3 (832,546 gallons) for net precipitation. The runoff from a 25 year, 24 hour rainfall event will be stored above the MOL. WSF 1 will be used to store waste from the Headquarters Farm. The facility is not designed to accept leachate or runoff from a FSA. Any collected Headquarters Farm FSA leachate or runoff will be transferred to WSF 2.

Waste Storage Facility 2

Waste Storage Facility 2 (WSF 2), designed according to NRCS, FOTG, Section IV, Standards 313 Waste Storage Facility (10/17) and 522 Pond Sealing or Lining – Concrete (10/17), Table 2, column 1 criteria, will be located in the northern part of the Heifer Farm production area (Construction Drawings Sheet 2). The on-site soils to be used for the sub liner meet the requirements of NRCS, FOTG, Section IV, Standard 522 Pond Sealing or Lining – Concrete (10/17), Table 2A, column 3 (Site Assessment).

A ramp will be installed to provide equipment access for removal of settled sand and heavy solids.

WSF 2 has a design waste storage capacity at the Maximum Operating Level (MOL), of 1,971,800 ft^3 (14,749,062 gallons) (Exhibit 8-1). The MOL volume includes 351,609 ft^3 (2,630,038 gallons) of storage for net precipitation. The runoff from a 25 year, 24 hour rainfall event from the FSA and Y1 Yard will be stored above the MOL. WSF 2 will be used to store waste from the Heifer Farm and wastes transferred from the Headquarters Farm.

WSF 2 will have a staff gauge to allow measurement of the volume of waste within the facility at different depths.

Waste Characterization and Planned Storage Period

Ledgeview Farm, LLC will generate 2,850,376 ft^3 (21,320,809 gallons) of manure, wastewater, leachate and runoff annually (Exhibit 8-1). The Waste Storage System will provide an average annual storage period of 291 days, including an allowance for future Runoff Control Systems.

Contingency Operation

WSF 2 is designed to have a minimum of one foot of freeboard. WSF 1 will normally be operated with an additional one foot of freeboard. The additional storage capacity can be utilized if unexpected circumstances prevent removal of waste from the facility.

Secondary Containment Evaluation

WSF 2 has been reviewed to evaluate the need for secondary containment. A Secondary Containment System would prevent a discharge in the event that WSF 2 fails. WSF 2 has been designed to meet NRCS, FOTG, Section IV, Standard 313, Waste Storage Facility (10/17) criteria. The NRCS standards include provisions providing for the structural stability of a structure that have proven to be acceptable. Therefore, it was determined that

additional secondary containment measures are not warranted. In addition, there are no environmentally sensitive areas in close proximity to WSF 2.

Stabilization of Organic By-Products
Manure and wastewater from the dairy will be collected and stored within WSF 1 and WSF 2. The wastes will be stored until removed for application onto cropland in accordance with the approved Nutrient Management Plan (NMP).

Nutrient Concentration
The proposed 2017 Waste Storage Facility and Runoff Management Systems will not concentrate nutrients.

Energy Production
The proposed 2017 Waste Storage Facility and Runoff Management Systems will not produce energy.

Volume Reduction
The proposed 2017 Waste Storage Facility and Runoff Management Systems will not reduce the volume of wastes. All reasonable efforts have been made to minimize the volume of runoff from tributary areas.

Waste Characterization
The waste produced at the dairy will be generated from dairy livestock, steers and from the runoff control systems (Exhibit 8-1). For storage purposes, net precipitation is included as waste. The overall waste characteristics will be typical of wastes generated from a dairy. The other waste streams will generate less than ten percent of the annual design waste load. The annual leachate volume represents less than 0.5 percent of the annual waste volume and the average annual collected runoff from the FSA and Y1 Yard will be approximately 8 percent of the total design waste volume.

Land-Base Available for Utilization of Waste
The current NMP identifies sufficient acres for utilization of wastes from LF. The cropland is either owned, rented or under manure agreements by Ledgeview Farm, LLC.

Planned Storage Period
WSF 1 has a design storage volume, including net precipitation, of 669,334 ft^3 (5,006,618 gallons). WSF 2 has a design storage volume, including net precipitation, of 1,971,800 ft^3 (14,749,062 gallons). The average design storage period, including an allowance for future Runoff Control Systems, will be 291 days (Exhibit 8-1).

Waste Handling and Transfer
Waste will be handled and transferred according to standard operating procedures that are employed by the farm.

Facility Waste Removal Methods
When it is time to remove manure from each Waste Storage Facility, liquids will be agitated and then waste will be pumped from the Waste Storage Facility. The liquids and solids will be surface applied via drag hose or tankers and the waste shall be incorporated into the soil within 24 hours.

Storage Liner Possibilities and Preferences
The Detention Basin and WSF 2 will both be constructed with reduced seepage concrete with waterstop liners, including sub-liner soils, constructed according to NRCS, FOTG, Section IV, Standard 522, Pond Sealing or Lining – Concrete (10/17), Tables 2, column 1 and 2A, column 1 criteria.

Access Needs and Limitations
The WSF 2 floor is designed to allow access for equipment to enter and remove settled solids. The FSA Detention Basin is designed to allow skidsteer access to remove settled solids.

Safety Needs
Each WSF will be fenced and have warning signs to discourage entry by livestock and people.

Labor and Equipment Needs
Ledgeview Farm, LLC owns the equipment necessary to empty each WSF. In the event their equipment is not operational, other equipment is available through custom manure applicators.

Odor Production Concerns and Control Strategies
No significant on-going odors are expected to be generated from the proposed WSF 2 and LMS. Odor will increase at times when agitation of the waste storage facilities occurs.

Aesthetics and Animal Health
Waste Storage Facility 2 will be located north of the nearby Bedded Pack Barn (L1) and, because of the berm elevation, not readily visible from the road. There will be no impact on animal health.

Provisions for Facility Expansion
No further expansion is planned at this time.

Site Assessment

Site Assessment

A Site Assessment of the proposed project area was conducted to evaluate the site conditions and characteristics and verify compliance with applicable design criteria.

Physical Site Characteristics
Ledgeview Farm, LLC is an existing dairy operation that has two production sites in the Town of Ledgeview, Brown County. The Headquarters Farm is located at 3875 Dickinson Road, De Pere, WI 54115 and the Heifer Farm is located at 3688 Lime Kiln Road, Green Bay, WI 54311(Exhibit 1 – Plat Map). All of the proposed improvements are located at the Heifer Farm.

Building Locations and Elevations
The locations of existing and proposed buildings are shown on an aerial photo of the Heifer Farm production area (Exhibit 2-2). The elevations at the site, along with the proposed modifications are shown on the Construction Drawings – Sheet 2.

Roads and Lanes
See plat map (Exhibit 1) for locations and details.

Property Lines, Setbacks and Elevations
See aerial photos (Exhibits 2-1, 2-2) and Construction Drawings – Sheet 2 for locations and details.

Soil Test Pits
See Construction Drawings – Sheet 2 for location of test pits. The test pit logs and analytical data of the soils are found in Exhibits 4 and 5.

Wells
The Heifer Farm has two on-site wells (Exhibit 7 – Well Construction Logs). Both of the wells are more than 250 feet from the proposed Detention Basin and WSF 2. A portion of the Waste Transfer Pipe from the Detention Basin to WSF 2 is greater than the 25' from the well as required in s. NR 812.08 Table A, but less than the 250' as is required in s. NR 243 from one of the wells.

Well Separation Variance Request for 1949 Well
Ledgeview Farm, LLC is requesting a variance from the requirements of s. NR 243.15(1)(a)(2) to allow construction of the proposed Detention Basin-WSF 2 Waste Transfer Pipe within 250 feet of an existing well. The well, constructed in 1949, does not have a Wisconsin Unique Well Number (Exhibit 7). The site details, including the location of the well and Waste Transfer Pipe are shown on the site plan (Construction Drawings – Sheet 2).

The minimum separation distance between the WTP and the 1949 well is approximately 60 feet. The WTP is a gravity ASTM D 3035 (SDR 35) PVC pipe that will transfer leachate and runoff from the Feed Storage Area. Therefore, the WTP will only have significant flow following a rainfall. The WTP will be dry most of the time. The separation distance exceeds the s. NR 812, Table A separation distance of 25 feet for a Manure/Gravity sewer pipe. The 1949 well is cased to a depth of 78 feet and the top of the well is 6 inches above grade (Exhibit 7, Well Construction Logs). Therefore, the well is protected from any runoff from the Waste Transfer Pipe.

Floodplain Locations
There are no floodplains in the proposed project area.

Surface Channels and Drain Tile
The Drainage System relies primarily on surface drainage. The overall drainage from the Heifer Farm site is to the north and west.

Utilities and Overhead Lines
There are no overhead power lines in the project area. There are no known underground utilities that will be impacted by the proposed modifications.

Easements and Permits
LANDOWNER IS RESPONSIBLE FOR PERMITS AND VARIANCES FROM SETBACK REQUIREMENTS.

Cultural Resources
There are no known cultural resources at this site.

Streams and Wetlands
There are no streams within 100 feet of the project area (Exhibit 6-1 – Wetlands Map). Given the presence of wetland indicator soils within the project area, a Wetland Determination was conducted and the WDNR concurred with the findings (Exhibit 6-2). The Wetland Determination found wetlands within the production area but not within the project area. No wetlands will be impacted by the project.

Description of Soils
Soil types – See soil survey map (Exhibit 3). The soil types found in the proposed project area include:

a. KhB – Kewaunee silt loam, 2 to 6 percent slopes
b. MaA – Manawa sandy loam, 1 to 3 percent slopes

Site Investigations – Test Pits
Test pits excavated by Brown County Land and Water Conservation Department (LWCD) and Roach & Associates (R&A) in 2017 were used to provide information for the proposed Waste Storage Facility and Leachate Management System. These investigations will be used to identify and evaluate groundwater and bedrock elevations and soil characteristics for the proposed improvements. Except for the Waste Transfer Pipe from the Detention Basin to WSF 2, the number of test pits meets or exceeds the criteria set forth in NRCS, FOTG, Section IV, Standards 313 Waste Storage Facility (10/17), 634 Waste Transfer (1/14) and NR 213 Lining of Industrial Lagoons and Design of Storage Structures (Exhibit 12). Test pits were excavated at each end of the Detention Basin-WSF 2 Waste Transfer Pipe. The remainder of the route has a concrete surface that prevented excavation of additional test pits. The test pits excavated, along with other site information, was sufficient to characterize site conditions.

Detention Basin
The Detention Basin (DB), will have a reduced seepage concrete with waterstop liner, designed according to NRCS, FOTG, Section IV, Standard 313 Waste Storage Facility (10/17) and NRCS, FOTG, Standard 522 Pond Sealing or Lining – Concrete (10/17), Table 2, column 1 criteria. The required criteria include a minimum separation from groundwater and bedrock of ≥2.5 feet. The characteristics for the Sub Liner Soils include a minimum 8 inches of soil with

≥40% P200 fines and a Plasticity Index (PI) of ≥12. The floor has a minimum elevation of 724.5.

While the DB is designed according to the criteria cited above, it must also comply with the requirements of s. NR 213 Lining of Industrial Lagoons and Design of Storage Structures. The applicable s. NR 213 criteria include a minimum separation distance from bedrock and groundwater of five (5) feet, measured from the base of the liner system. The site investigation criteria require evaluation of site conditions to a depth of ten (10) feet below the base of the liner system

NRCS Standards 313 and 522

Three (3) test pits (TP 59-61) were used to evaluate site conditions for the DB. Given the small footprint of the DB, only two of the test pits (TP 59 & 60) were within 100 feet of the DB with the third test pit (TP 61) located approximately 180 feet from the DB.

The DB has a base elevation of 724.5. The test pits were excavated to depths between 10.0 and 13.0 feet below grade and had base elevations between 715.8 and 713.4 (Exhibit 4). No bedrock or groundwater was found in any of the test pits, verifying a minimum separation distance of 8.7 feet, exceeding the criteria.

The test pits found clay formations extending to the base of each test pit. A sample from the clay formation had 82.6 percent P200 fines and a PI of 28.9, exceeding the criteria.

Number of test pits used in evaluation: 3 (TP 59-61)
Verified separation from bedrock: 8.7 feet
Verified separation from groundwater: 8.7 feet

Sub Liner Soils
Minimum P200 fines: 82.6 percent
Minimum PI: 28.9
Thickness of sub-liner soils: 9.8 feet

NR 213

Three (3) test pits (TP 59-61) were used to evaluate site conditions for the DB. Given the small footprint of the DB, only two of the test pits (TP 59 & 60) were within 100 feet of the DB with the third test pit (TP 61) located approximately 180 feet from the DB.

The DB has a base elevation of 724.5. The liner includes a five (5) inch reduced seepage concrete liner and eight (8) inches of sub-liner soils. Therefore, the base of the liner is at approximately 723.4. The test pits were excavated to depths between 10.0 and 13.0 feet below grade and had base elevations between 715.8 and 713.4 (Exhibit 4). No bedrock or groundwater was found in any of the test pits, verifying a minimum separation distance from the base of the liner of 7.6 feet, exceeding the criteria. One of the test pits was excavated to ten (10) feet below the base of the liner and the other test pit was excavated to a depth 7.6 feet below the base of the liner. Given the small footprint of the DB, the number and depth of the test pits meets the intent of NR 213.

Number of test pits used in evaluation: 3
Verified separation from bedrock: 7.6 feet
Verified separation from groundwater: 7.6 feet

Waste Transfer Pipes
Each Waste Transfer Pipe (WTP) is designed according to NRCS, FOTG, Section IV, Standard 634 (1/14), Table 1 criteria which requires six inches of separation from bedrock; no separation from groundwater is required. There are no soil characteristic requirements.

Detention Basin-WSF 2 Waste Transfer Pipe
The WTP will be installed along the east side of the Feed Storage Area and the L1 Barn. Much of the area has a concrete surface that limited the area accessible for test pits. Two (2) test pits (TP 2, 60) were excavated within 100 feet of the WTP, one near each end of the pipe (Exhibit 4). The elevation of the WTP will vary from 720.4 in the south to 711.0 at the WSF 2 discharge. The test pits were excavated to base elevations of 715.4 and 710.6 and verified a minimum separation from bedrock and groundwater of 1.3 feet, exceeding the criteria. Since no bedrock has been found at the within the project area at the site, no bedrock is expected to be found along the WTP route. If bedrock is encountered, it will be removed according to the criteria.

Number of test pits used in evaluation: 2 (TP 2, 60)
Verified separation from bedrock: 1.3 feet
Verified separation from groundwater: 1.3 feet

Collection Basin-WSF 2 Waste Transfer Pipe
The WTP will be designed according to NRCS, FOTG, Section IV, Standard 634 (1/14), Table 1 criteria which requires six inches of separation from bedrock; no separation from groundwater is required. The elevation of the WTP will vary from 719.0 at the CB to approximately 707.4 at the discharge point to WSF 2.

Three test pits (TP 10, 11, 20) were excavated within 100 feet of the proposed WTP and no portion of the WTP was more than 100 feet from a test pit (Exhibit 4). The test pits were excavated to a depth of 11.0 feet or more below existing grade. No groundwater or bedrock was found in any of the test pits, verifying a minimum separation distance from bedrock and groundwater of 5.6 feet, exceeding the criteria.

Number of test pits used in evaluation: 3 (TP 10, 11, 20)
Verified separation from bedrock: 5.6 feet
Verified separation from groundwater: 5.6 feet

Waste Storage Facility 2
Waste Storage Facility 2, will have a reduced seepage concrete with waterstop liner, designed according to NRCS, FOTG, Section IV, Standard 313 Waste Storage Facility (10/17) and NRCS, FOTG, Standard 522 Pond Sealing or Lining – Concrete (10/17), Table 2, column 1 criteria. The required criteria include a minimum separation from groundwater and bedrock of 2.5 feet. The characteristics for the Sub Liner Soils include a minimum 8 inches of soil with ≥40% P200 fines and a Plasticity Index (PI) of ≥12. The floor has a minimum elevation of 706.6.

While WSF 2 is designed according to the criteria cited above, it must also comply with the requirements of s. NR 213 Lining of Industrial Lagoons and Design of Storage Structures. The applicable s. NR 213 criteria include a minimum separation distance from bedrock and groundwater of five (5) feet, measured from the base of the liner system. The site investigation criteria require evaluation of site conditions to a depth of ten (10) feet below the base of the liner system.

Given the different criteria applicable to WSF 2, including the number of required test pits, the evaluation of the site conditions will be evaluated for each standard separately.

NRCS Standards 313 and 522

A total of fifteen (15) test pits were excavated within 100 feet of the proposed WSF 2. The test pits were excavated to depths between 8.5 and 14.5 feet, with base elevations between 701.9 and 695.3. No bedrock was found in any of the test pits, verifying a minimum separation distance of 4.7 feet, exceeding the criteria (Exhibit 4). Groundwater was found only in one test pit (TP 23) at an elevation of 698.4, 9.2 feet below the base of WSF 2. Therefore, the minimum verified separation distance from groundwater will be 4.7 feet, based on the depth of other test pits.

The reduced seepage concrete-waterstop liner does not include a soil component. The sub-liner soil criteria include a minimum of 8 inches of soil with $\geq$ 40 % P200 fines and a PI $\geq$ 12. The test pits found soil formations, characterized as clay, which will function as the sub-liner soils, present to the base of each test pit used in the evaluation. Therefore, the minimum thickness of the sub-liner soils is equal to the verified separation distance of 4.7 feet. The soil formations had a minimum of 78.9 P200 fines and a minimum PI of 17, exceeding the criteria (Exhibit 5).

Based on the site investigations and proposed construction, the soils and site conditions exceed the NRCS, FOTG, Section IV, Standard 522 Pond Sealing or Lining – Concrete (10/17), Table 2, column 1 and Table 2A, column 3 criteria.

WSF 2 Area: 202,623 ft^2
Number of test pits used in the evaluation: 15
Minimum verified separation from bedrock: 4.7 feet
Minimum verified separation from groundwater: 4.7 feet

Sub Liner Soils
Minimum P200 fines: 78.9 percent
Minimum PI: 17
Minimum Thickness of Sub Liner Soils: 4.7 feet

NR 213

A total of seven (7) test pits excavated within 100 feet of the proposed WSF 2 were used in the NR 213 evaluation of site conditions. The test pits were excavated to depths between 8.5 and 14.5 feet, with base elevations between 700.2 and 695.3. No bedrock was found in any of the test pits, verifying a minimum separation distance of 5.1 feet from the base of the liner, exceeding the criteria (Exhibit 4). Groundwater was found only in one test pit (TP 23) at an elevation of 698.4, 9.2 feet below the base of WSF 2. Other test pits were terminated when the soil characteristics, including Munsell colors, indicated the proximity of groundwater. The test pits were terminated to avoid multiple penetrations of the groundwater within and near the footprint of WSF 2. One test pit (TP 17) was excavated at least 10 feet below the base of the WSF 2 liner and the remaining test pits verified the required separation distance from groundwater. The minimum verified separation distance from groundwater will be 5.1 feet, based on the depth of other test pits.

The site investigations meet the intent of NR 213 Lining of Industrial Lagoons and Design of Storage Structures. The test pits verify the required separation distance from groundwater and the proposed liner will exceed the criteria.

WSF 2 Area: 202,623ft^2 (4.65 acres)
Number of test pits used in the evaluation: 7
Minimum verified separation from bedrock: 5.1 feet
Minimum verified separation from groundwater: 5.1 feet

Site Investigation Summary
The site investigations are summarized below:

Test Pits – See Exhibit 4 – Test Pit Log Sheets

1. Test Pits
   a. Unless otherwise specified, the number of test pits needs to be sufficient to evaluate site soil characteristics and establish separation distances from groundwater and bedrock.
   b. The number of test pits met or exceeded the specified design criteria for each system evaluated.
   c. Test pit logs are included in Exhibit 4.
   d. Unified Soil Classification System has been used to describe the soils.
2. Detention Basin
   a. Separation from groundwater (NRCS 522): 10.3 feet
   b. Separation from groundwater (NR 213): 9.2 feet
   c. Separation from bedrock (NR 213): 9.2 feet
   d. Sub Liner Soil-Minimum P200 fines: 82.6 percent
   e. Sub Liner Soil-Minimum PI: 28.9
   f. Thickness of Sub Liner Soils: 9.8 feet
3. Detention Basin Waste Transfer Pipe
   a. Separation from bedrock: 1.3 feet
4. Collection Basin Waste Transfer Pipe
   a. Separation from bedrock: 5.6 feet
5. Waste Storage Facility 2
   a. Separation from groundwater (NRCS 522): 4.7 feet
   b. Separation from groundwater (NR 213): 5.1 feet
   c. Separation from bedrock (NRCS 522): 4.7 feet
   d. Sub Liner Soil-Minimum P200 fines: 78.9 percent
   e. Sub Liner Soil-Minimum PI: 17
   f. Thickness of Sub Liner Soils: 4.7 feet
6. Laboratory analysis of soil samples (Exhibit 5).

Sink holes and other Karst features

1. There are no documented Karst features at this site or located within 1,000 ft. of the proposed improvements.

Locations, dimensions & elevations, soil volumes

1. See the Construction Plan Set for locations, dimensions and elevations.
2. Waste Storage Facility 2 will generate excess fill that will be used for back slopes.

Failure
Failure of either the Detention Basin or WSF 2 would result in the release of contaminated runoff or manure to the environment. The Detention Basin and WSF 2 will be constructed in accordance with current regulatory criteria to provide stable structures.

Operation and Maintenance Plan

Operation and Maintenance Plan

Introduction
Provided is an Operation and Maintenance Plan for the proposed Waste Storage Facility and Runoff Management Systems at Ledgeview Farm, LLC.

The Operation and Maintenance Plan outlines the activities required for proper operation of the Waste Transfer and Storage Systems. A general schedule of anticipated maintenance and record keeping is provided that identifies specific maintenance and record keeping activities. The manufacturer's manuals also contain information for repair of the mechanical components.

In the event of a spill or accidental discharge, call the WDNR Spill Emergency Hotline and refer to the Ledgeview Farm Emergency Response Contact Summary (ERCS) (Exhibit 11).



Daily Maintenance

Detention and Collection Basins	
If: Solids/snow present	**Then**: Remove solids or snow as necessary to maintain flow equalization capacity and minimize the potential blockage of transfer lines

Weekly Maintenance

Waste Storage Facility	
What: Record liquid level in each WSF	
What: Inspect exterior slopes for deterioration	**Then**: Repair when possible
If: Rodent damage is present on the earthen slopes	**Then:** Repair when possible
If: Solids are accumulated	**Then:** Remove solids when possible
If: Transfer Lines or outlets are damaged or obstructed	**Then:** Repair when possible

Waste Transfer Systems
The plan for operation and maintenance of the Waste Transfer Systems is as follows:

Detention Basin
Leachate and runoff from the Feed Storage Area flow into the Detention Basin and are discharged by gravity WSF 2. The Detention Basin provides flow equalization; the basin

provides short term storage during peak flows. This reduces the peak discharge rate. During periods of low flow, solids may settle in the basin, reducing the storage capacity and level of flow equalization provided. Solids and snow must be removed periodically to maintain the flow equalization capacity of the Detention Basin.

Detention Basin Waste Transfer Pipe
The contents of the Detention Basin, leachate and runoff from the Feed Storage Area, will flow to WSF 2 by gravity through the Waste Transfer Pipe. Manholes along the Waste Transfer Pipe can be used as clean-outs if needed to clear a blockage in the pipe.

Collection Basin
Runoff from the Y1 Yard will flow into the Collection Basin and be discharged by gravity through the Collection Basin Waste Transfer Pipe to WSF 2. Solids that settle in the basin could reduce the hydraulic capacity of the outlet or of the Waste Transfer Pipe. Solids and snow must be removed periodically to maintain the flow equalization capacity of the Collection Basin.

Collection Basin Waste Transfer Pipe
Waste and runoff from the Y1 Yard will flow to WSF 2 by gravity through the Waste Transfer Pipe. Solids should be removed from the yard and Collection Basin on a regular basis to minimize the potential blocking of the Waste Transfer Pipe.

Other
WSF 2 will be used for storage of waste generated at the HQ Farm. Waste from the HQ Farm will be transferred to WSF 2 by tanker on an as needed basis.

Waste Storage Facility 2
WSF 2 is an impoundment with a reduced seepage concrete-waterstop liner that is intended to receive waste generated at the farm, including leachate and runoff from the Feed Storage Area and waste generated at the HQ Farm. The reduced seepage concrete liner will allow agitation from any location.

WSF 2 is designed to provide access for equipment for removal of settled sand and other heavy solids.

WSF 2 will be emptied periodically according to need and cropping schedule. The manure will be applied to cropland according to the current Nutrient Management Plan (NMP).

Contingency
Clean rainfall will be diverted from the Waste Storage Facilities. The design level of freeboard for the Waste Storage System is one foot for safety plus allow for the water from a 25 year 24 hour rain event (approximately 4"). The system will be managed with a minimum of two feet of freeboard in WSF 2 to account for unexpected volumes of water or conditions that may prevent field application of the manure. In the event that levels exceed the maximum operating levels, manure will be pumped and applied onto cropland according to the current NMP allowing for additional capacity.

Emergency Response Plan
An Emergency Response Contact Summary has been developed for Ledgeview Farm, LLC and is included in Exhibit 11.

Inspection and Monitoring
The Detention and Collection Basins will be checked for the following

- Deterioration or damage to the concrete liner
- Deterioration or erosion of any of the exterior slopes
- Accumulation of solids or snow that would reduce the flow equalization or hydraulic capacity of the basin

The Waste Storage Facility structures will be checked for the following:

- Deterioration or erosion of any of the exterior slopes
- Deterioration or damage to the concrete liner
- Rodent damage to any of the exterior earthen slopes
- Leakage around the outside
- Staff gauge
- All safety signage, guards and fencing

The Waste Storage System will be monitored as follows:

- The level of manure in the Waste Storage Facilities shall be monitored and recorded weekly. The record shall show the distance from the manure level to the maximum operating level.
- A record of the before and after levels of manure, each time the waste storage structure is emptied, will be kept.
- A record of the date that 180 days of available storage level in the Waste Storage System is available will be recorded.

Safety
Normal Safety Requirements

Confined space warning signage, decking and railing where needed, will be installed and maintained to protect against accidental entry into the Pumping Stations. The signs will be in languages that are spoken and used at the dairy. The Waste Storage Structures shall be surrounded by a fence, which will prevent humans or animals from accidentally entering the Waste Storage Facilities. The fence shall have the required warning signs.

Entry into Enclosed Tanks

When working in a confined space the following safety actions should still be taken:

- Always assign a standby person to remain outside of the confined space. It is this person's responsibility to be in constant contact (visually, verbally or both) with the workers inside the confined space as long as anyone is in the space.
- Wear ear protection as needed. Noise within a confined space can be amplified because of the space's design and acoustic properties.
- Use only an air-supplying respirator, such as a self-contained breathing apparatus (SCBA) or a supplied-air respirator with an auxiliary escape-only SCBA in confined spaces where there is

insufficient oxygen.

- Never enter a pit without proper ventilation. Before entering the pit, evaluate its atmosphere by testing for sufficient oxygen and the presence of toxic gases.
- When going into any manure tank, wear an air-supplied respirator or a SCBA, as well as a safety harness attached to a rope attended by two people at the pit's entrance. Note: Respirator masks must be checked for proper fit, and persons using respirators should receive training in their use. Attaching the safety rope to a winch or hoist is also recommended.
- Keep people and animals out of any building where manure is being agitated or emptied. If animals cannot be removed before agitating the storage, provide strong mechanical ventilation during agitation and pumping and for a few hours after pumping has stopped.
- Never fill a manure pit completely; allow 1 to 2 feet of airspace to accommodate gas concentrations. To reduce the possibility of gas being forced above floor level, lower liquid manure levels in a storage facility before starting agitation.
- Keep the agitator below the liquid surface because greater volumes of gas are released with vigorous surface agitation.

Construction Plan

Construction Plan

1. **Contacts**
   Contact Brown County Land and Water Conservation Department (LWCD), Ledgeview Township and the Wisconsin Department of Natural Resources (WDNR) for permits.

2. **New Construction and Modifications**
   The new construction included in the proposed project includes the following components:
   - A Detention Basin with a reduced seepage concrete-waterstop liner with sub-linter soils
   - A 18 inch ASTM F 679 PVC Waste Transfer Pipe from the Detention Basin to WSF 2
   - A 15 inch ASTM D3034 (SDR 35) PVC Waste Transfer Pipe with a sealed connection from the to the Y1 Yard Collection Basin
   - Waste Storage Facility 2 (WSF 2) with a reduced seepage concrete-waterstop liner with sub-liner soils

3. **Wells**
   No wells are located within 250 feet of the proposed Detention Basin or WSF. A portion of the Detention Basin Waste Transfer Pipe is greater than 25 feet, but less than 250 feet from a well. A variance has been requested.

4. **Contractor**
   The contractor(s) is responsible for following all project specifications as well as other applicable laws and regulations regardless of whether they are specifically referenced in this document or cited on the plans. Details of the proposed improvements are presented in the following sections and include references to specific specification sections. The lack of a reference to a specification section does not alleviate the contractor(s) from compliance with any specification, law or applicable regulation.

5. **Erosion Control**
   The contractor(s) shall install the prescribed erosion protection according to the Construction Drawings before any excavation or site disturbance occurs.

6. **Detention Basin**
   - The Detention Basin will have a reduced seepage concrete-waterstop liner with sub-liner soils.
   - The Waste Transfer Pipe (WTP) connection to the existing Collection Basin will use hydrophilic sealant to make a water-tight joint.

7. **Detention Basin Waste Transfer Pipe**
   - The Detention Basin WTP will be an 18 inch ASTM F 679 PVC pipe.
   - The connection to the Detention Basin will use hydrophilic sealant to make a water-tight joint.

8. **Collection Basin**
   - The Y1 Yard Collection Basin is an existing structure with a watertight concrete liner.

9. Collection Basin Waste Transfer Pipe

- The WTP will be a 15 inch ASTM D 3034 (SDR 35) PVC pipe.
- The connection to the Collection Basin will use hydrophilic sealant to make a water-tight joint.

10. Waste Storage Facility 2

Waste Storage Facility 2 will have a reduced seepage concrete-waterstop liner with sub-liner soils.

11. Concrete

- All concrete shall meet Wisconsin Construction Specification 4 concrete (10/17)
- Concrete mix shall be pre-approved by the project engineer
- Contractor shall provide documentation that the concrete meets the specifications

12. Waterstop

- All waterstop shall meet Wisconsin Construction Specification 004 Embedded or Expansive Waterstop (10/17)
- Waterstop intersections will be prefabricated by the manufacturer

11. Pipe Transfer Systems

Transfer Pipes and Joints

- Pipe and joints shall conform to Wisconsin Construction Specifications 634 (8/16), Table 1 criteria.

Pipe Installation:

- When excavating and installing pipe, follow safe trenching practices as specified by OSHA and Wisconsin Construction Specification 634 Waste Transfer Pipe (8/16).
- Use reducers for changing diameter of pipe.
- Backfill 6 inches over pipe with clean sand in accordance with Wisconsin Construction Specification 634 Waste Transfer Pipe (8/16).
- Provide concrete blocking or mechanical joint restrains at all changes in direction of pressure piping in accordance with the details in the construction drawings.

Pipe Connections:

- All piping connections shall be made in accordance with the manufacturer's recommendations and requirements to form a liquid tight joint.

Construction Verification and Documentation Plan

Construction Verification and Documentation Plan

Introduction

Ledgeview Farm, LLC proposes to construct a new Waste Storage Facility and Runoff Management Systems to provide additional and waste storage capacity and runoff controls. The following outline, along with the detailed construction plan sheets, will be used by the construction inspector and the design engineer to ensure that the facilities are constructed and installed according to the plans and specifications. In addition, the construction verification and documentation system will be used in the preparation of the "As-built" plans following the completion of the construction. Roach & Associates, LLC (R&A) will provide all engineering review and inspection services.

Pre-Construction Contractor's Meeting

A pre-construction meeting shall take place prior to construction of the planned work. Attendees shall include a representative of R&A, the contractor(s) involved in the work, the landowner and representatives of regulatory agencies, including The Town of Ledgeview, Brown County Land and Water Conservation Department (LWCD), Wisconsin Department of Natural Resources (WDNR) and Natural Resource Conservation Service (NRCS). The meeting agenda shall consist of a review of all plan details and all referenced and associated specifications and standards.

The representative from R&A shall address any questions regarding plan details and construction methods that may be necessary to complete the project according to the plans and specifications. The processes and components that will require inspection will be reviewed. The document Authority of the Inspector – Memorandum of Understanding (Exhibit 13) will be reviewed and signed.

Inspection Frequency

An R&A inspector will be on site as necessary to inspect the process and components, as they are being carried out or constructed. The construction schedule will dictate the inspector's presence at the site to observe, measure, document and record the installation of the below described components, systems and facilities.

Authority of the Inspector

The inspector has full and complete authority to stop construction anytime deviations from the design plans are identified and the inspector believes the deviations will compromise the integrity of the planned structure. The inspector has the authority to develop, with the contractor, an acceptable solution to correct the deviations. If an acceptable solution cannot be developed, the inspector shall notify the owner and the owner shall be brought into the discussion to arrive at a solution to correct the deviations. At the beginning of the project, all contractors shall sign a memorandum of understanding recognizing the Authority of the Inspector and agreeing to be bound by his decisions, (Exhibit 13 – Authority of the Inspector Memorandum of Understanding).

Inspector Qualifications

1. The inspector must be experienced in the following areas of construction:
   - Evaluation and identification of soils.
   - Excavation – cutting, filling, compaction and grading.
   - Staking and setting construction grades and elevations.
   - Inspection of reinforced concrete slabs, walls, tanks, tops and ramps.
   - Inspection of PVC waterstop installation
   - Bedding, PVC and HDPE pipes of all types and with all types of water tight joints.
   - Installation of underground tile lines and culverts.
   - Awareness and dangers of underground utility lines and wires.
   - Be aware of and be able to perform required on-site concrete testing.
   - Be aware of and be able to perform or call for soil compaction testing when necessary.
   - Be aware of and able to oversee pressure testing of pipelines as required.
2. The inspector must have good oral and written communication skills.
3. The inspector must be physically able to perform the required testing and observations.

Areas to be Inspected

1. Observe excavation for evidence of perched water, inappropriate soils, groundwater, bedrock or other conditions that would prevent construction within the design criteria. If said conditions are found, the design engineer shall be contacted and an onsite conference shall be held to determine the solution.
2. Verify subgrade shaping, dimensions and elevations.
3. Verify compliance with specifications for subgrade excavation, filling and compaction. Verify moisture levels of soil being filled and compacted.
4. Verify the type of soil being placed and test subgrade compaction according to plan specifications if required or necessary.
5. Verify pipe materials conform to the specifications.
6. Verify installation of thrust blocks or mechanical joint restraints in accordance with the detail.
7. Verify and document the following as it relates to concrete slabs and walls:
   - All reinforcement steel size, spacing and placement.
   - Elevation and dimensions of forms, prior to concrete placement.
   - Quality of the concrete used and proper method of placement.
   - Type of waterstop, including minimum web thickness
   - Placement of waterstop, including minimum clearance to reinforcement
8. Verify type, capacity and style of pumping equipment.
9. Verify and document the following during the placement of the concrete slabs and walls:
   - Verify the proper concrete mix is being delivered – collect batch tickets.
   - Perform slump and air entrainment tests for conformance with NRCS or plan specifications.
10. General: Prepare daily observation reports and submit to the design engineer.
11. Check for proper pipe connections at Pump Connection Stations, if required.
12. Advise design engineer promptly of all defects and deficiencies to ensure that they are addressed to the contractor in a timely manner.
13. Provide As-built plans and materials.

Exhibit 1



©2006 Brown County Wisconsin
T23N R21E (SW)
Ledgeview & Bellevue(SW)
See Page 17
See Page 12
See Page 16
See Page 7
David J Van Rite
Village of Bellevue
Hs Realty Partnership LLP
Hs Realty
Harold Peeters Jr Etal
David L Swagel
Louanne Kuzmic
Diana K Ferry
Timothy J & Deanne M Mckenna
Titulaer Mary V Revocable Trust
Dickinson Development LLC
Mark A & Julie Ann Giardino
Daniel L & Dennis R Mcallister Etal
Leanna Family Ltd Partnership
Ledgeview Facility LLC
Edmund J Gersek
Michael G & Susan M Tesar
Garot Land Development LLC
Sandra M Arendt
Marion V Coates
Diane L Layman
Kenneth & Dolores Matzke
SCI Properties
Kolb
Joseph J Charles
Vernon A Den Bus
Steven & Cheryl Corrigan & Donald W Corrigan
Roy & Glen Pansier
Josephine Grohusky
Bernard Van Straten 43
Donald Van Straten
Bernard
Win C & Muriel H
Daanen & Northeast
Roy
Town of Ledgeview
Town of Glenmore
Green Bay Country Club Inc
Dutchman Rd
Dollar Rd
Dickinson Rd
Hawthorne Heights Dr
Scrayshirt Rd
Lime Kiln Rd
Mother Rd
Bower Creek Rd
Meadowbrook Ct
Woodchuck Ct
Creek Ct
Ledgeview Site
HQ
0
2,640
5,280
Feet
**The acreages shown on this map are based on the latest and most accurate parcel mapping which may differ slightly from the acreages shown on the tax roll.
For more detailed or up-to-date maps please visit us online at:
www.gis.co.brown.wi.us
15
Map Legend
Property Boundaries (with acreages**)
Municipal Boundaries
Interstate, U.S or State Highway
County Highway
Other Road or Street
Railroads
Lakes, Ponds, & Rivers
Trails
Woodlands/Natural Areas
Address Grid numbering
Section or other PLSS line
Section numbers
15

Exhibit 2

Ledgeview Farm, LLC

Main Farm



N

Ledgeview Farm

Heifer Farm



Exhibit 3

Soil Map—Brown County, Wisconsin
(Ledgeview Heifer Soite-Soils Map)



Map Scale: 1:5,450 if printed on A portrait (8.5" x 11") sheet.

Meters: 0, 50, 100, 200, 300

Feet: 0, 250, 500, 1000, 1500

Map projection: Web Mercator Corner coordinates: WGS84

MAP LEGEND

Area of Interest (AOI)
- Area of Interest (AOI)

Soils
- Soil Map Unit Polygons
- Soil Map Unit Lines
- Soil Map Unit Points

Special Point Features
- Blowout
- Borrow Pit
- Clay Spot
- Closed Depression
- Gravel Pit
- Gravelly Spot
- Landfill
- Lava Flow
- Marsh or swamp
- Mine or Quarry
- Miscellaneous Water
- Perennial Water
- Rock Outcrop
- Saline Spot
- Sandy Spot
- Severely Eroded Spot
- Sinkhole
- Slide or Slip
- Sodic Spot
- Spoil Area
- Stony Spot
- Very Stony Spot
- Wet Spot
- Other
- Special Line Features

Water Features
- Streams and Canals

Transportation
- Rails
- Interstate Highways
- US Routes
- Major Roads
- Local Roads

Background
- Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Brown County, Wisconsin
Survey Area Data: Version 11, Oct 5, 2017

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Dec 31, 2009—Oct 31, 2016

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
AeA	Allendale fine sandy loam, 0 to 3 percent slopes	7.7	5.5%
Bd	Bellevue silty clay loam, mottled subsoil variant	0.1	0.0%
BnA	Bonduel loam, 0 to 3 percent slopes	0.8	0.6%
KhB	Kewaunee silt loam, 2 to 6 percent slopes	76.2	54.2%
KhB2	Kewaunee silt loam, 2 to 6 percent slopes, eroded	1.4	1.0%
KhC2	Kewaunee silt loam, 6 to 12 percent slopes, eroded	5.4	3.9%
MaA	Manawa sandy loam, 1 to 3 percent slopes	34.9	24.9%
McA	Manawa silty clay loam, 0 to 3 percent slopes	7.6	5.4%
Po	Poygan silty clay loam, 0 to 2 percent slopes, drained	0.2	0.1%
Wa	Wauseon fine sandy loam	6.2	4.4%
Totals for Area of Interest		**140.5**	**100.0%**

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
AeA	Allendale fine sandy loam, 0 to 3 percent slopes	7.7	5.5%
Bd	Bellevue silty clay loam, mottled subsoil variant	0.1	0.0%
BnA	Bonduel loam, 0 to 3 percent slopes	0.8	0.6%
KhB	Kewaunee silt loam, 2 to 6 percent slopes	76.2	54.2%
KhB2	Kewaunee silt loam, 2 to 6 percent slopes, eroded	1.4	1.0%
KhC2	Kewaunee silt loam, 6 to 12 percent slopes, eroded	5.4	3.9%
MaA	Manawa sandy loam, 1 to 3 percent slopes	34.9	24.9%
McA	Manawa silty clay loam, 0 to 3 percent slopes	7.6	5.4%
Po	Poygan silty clay loam, 0 to 2 percent slopes, drained	0.2	0.1%
Wa	Wauseon fine sandy loam	6.2	4.4%
Totals for Area of Interest		**140.5**	**100.0%**

Exhibit 4

Test Pit Summary Worksheet

Owner: Ledgeview Farm

Project: 2017 Waste Storage Facility and Runoff Management Systems

Prepared By: Roach

Date Prepared: 2017

Test Pit (Number)	Surface Elev.	Depth	Base Elev.	Facility* Base	Measure Point	GW Depth	BR Depth	Sep Dist	G.W. Elev.	B.R. Elev.	Verifies				
											DB		WTP	WSF	
											NRCS 313	NR 213	NRCS 634	NRCS 313	NR 213
59	725.8	10.0	715.8	724.5	1			8.7			x				
60	726.4	13.0	713.4	724.5	1			11.1			x				
61	729.6	10.0	719.6	724.5	1			4.9			x				
59	725.8	10.0	715.8	723.4	2			7.6				x			
60	726.4	13.0	713.4	723.4	2			10.0				x			
61	729.6	10.0	719.6	723.4	2			3.8				x			
2	722.6	12.0	710.6	711.9	3			1.3					x		
10	712.7	11.6	701.1	707.4	4			6.3					x		
11	716.5	14.7	701.8	707.4	4			5.6					x		
20	713.1	13.5	699.6	707.4	4			7.8					x		
54	715.4	11.0	704.4	720.5	4			16.1					x		
60	726.4	13.0	713.4	720.5	3			7.1					x		
6	711.3	11.1	700.2	706.6	5			6.4						x	
7	708.9	8.5	700.4	706.6	5			6.2						x	
8	710.4	9.4	701.0	706.6	5			5.6						x	
9	712.5	12.0	700.5	706.6	5			6.1						x	
10	712.7	11.6	701.1	706.6	5			5.5						x	
12	715.5	14.5	701.0	706.6	5			5.6						x	
13	714.3	14.5	699.8	706.6	5			6.8						x	
14	713.9	12.9	701.0	706.6	5			5.6						x	
17	706.8	11.5	695.3	706.6	5			11.3						x	
18	708.8	12.0	696.8	706.6	5			9.8						x	
19	708.9	11.0	697.9	706.6	5			8.7						x	

Test Pit (Number)	Surface Elev.	Depth	Base Elev.	Facility* Base	Measure Point	GW Depth	BR Depth	Sep Dist	G.W. Elev.	B.R. Elev.	Verifies				
											DB		WTP	WSF	
											NRCS 313	NR 213	NRCS 634	NRCS 313	NR 213
20	713.1	13.5	699.6	706.6	5			7.0						x	
21	713.3	12.0	701.3	706.6	5			5.3						x	
22	715.4	13.5	701.9	706.6	5			4.7						x	
23	711.4	13.0	698.4	706.6	5	13		8.2	698.4					x	
6	711.3	11.1	700.2	705.3	6			5.1							x
13	714.3	14.5	699.8	705.3	6			5.5							x
17	706.8	11.5	695.3	705.3	6			10.0							x
18	708.8	12.0	696.8	705.3	6			8.5							x
19	708.9	11.0	697.9	705.3	6			7.4							x
20	713.1	13.5	699.6	705.3	6			5.7							x
23	711.4	13.0	698.4	705.3	6	13		6.9	698.4						x

*Floor of structure or lowest pipe invert elevation

[1] Top of 5" concrete liner, Table 2

[2] Bottom of liner system, 5" concrete liner, Table 2, Column 1, Reduced Seepage Concrete with Waterstop and 8" of sub-liner, Table 2A, Column 3

[3] Detention Basin -WSF 2 WTP

[4] Collection Basin -WSF 2 WTP

[5] Top of 7" concrete liner, Table 2

[6] Bottom of liner system, 7" concrete liner, Table 2, Column 1, Reduced Seepage Concrete with Waterstop and 8" of sub-liner, Table 2A, Column 3

** Floor of facility or lowest elvation of waste transfer pipe system

(x) test pit not deep enough to verify facility

LOG OF SOIL TEST PIT

Project: Ledgeview Farms (Pansier)
Site Location: NW¼ SW¼ Sec 28 T23N R21E
Date: 5/14/17
Weather:
Land Use: Ag field
Coordinate System: Brown Co. / USGS

Boring No: TP2
Proposed Practice: 313
Logged By: Drew Zeller
Surface Elevation: (1) 717.8 (2) 722.6
Bench Mark: GPS

LIMITING FACTORS
Ground Water: N/A / Present - EL.____
Perched Water: N/A / Present - EL.____ to EL.____
Bedrock: N/A / Present - EL.____
Type of Bedrock:
Sink Hole('s) Within 1000FT: Yes / No / Not Visible

DEPTH FEET	USCS	USDA	MUNSELL COLOR			MOISTURE (USDA - FROZEN, DRY, MOIST, OR SATURATED)	STRUCTURE (USDA - GRANULAR, ANGULAR BLOCKY, SUBANGULAR BLOCKY, PLATY, WEDGE, PRISMATIC, COLUMNAR, SINGLE GRAIN, MASSIVE, OR CLODDY)	% SUBSURFACE COARSE FRAGMENTS (USCS - Gravel 4.8mm-76mm (3"); Cobbles 3"-11.8"; Boulders 11.8"+)	COMMENTS
			MATRIX COLOR	REDOXOMORPHIC FEATURES: COLOR	REDOXOMORPHIC FEATURES: QUANITY (FEW <2%, COMMON 2-20%, MANY >20%)				
	TP3		717.8	CLY	16.7				
0 / 1	~~CL~~	~~CLAY~~ LOAM	Topsoil						
1 / 16.7	CL	CLAY LOAM	5YR 4.4	—	—	DRY	MASSIVE	—	—
TP2	SURFACE	CL	722.6						
0 / 1	Topsoil								
1 / 12	CL	CLAY LOAM	5YR 4.4						

ADDITIONAL COMMENTS
TP#2 stopped due to storm approaching, rained 2.9" over next 2-3 days. When gone back to site to observe test holes some had caved in varying amounts and water was present on top of caved soil due to rains. TP#1 still needs to be excavated and logged DLW 5/19/17

652

LOG OF SOIL TEST PIT

Project: Parker Ledgeview Farms
Site Location: NW¼SW¼ Sec 28 T23N R2E
Date: 5/14/17
Weather: Overcast
Land Use: Ag Field
Coordinate System: Brown Co. / USGS

Boring No: 5 & 4
Proposed Practice: 313
Logged By: Drew Zeller
Surface Elevation: (5) 713.2 (4) 714.3
Bench Mark: GPS

LIMITING FACTORS
Ground Water: N/A / Present - EL. ____
Perched Water: N/A / Present - EL. ____ to EL. ____
Bedrock: N/A / Present - EL. ____
Type of Bedrock: ____
Sink Hole('s) Within 1000FT: Yes / No / Not Visible

DEPTH FEET	USCS	USDA	MUNSELL COLOR			MOISTURE (USDA - FROZEN, DRY, MOIST, OR SATURATED)	STRUCTURE (USDA - GRANULAR, ANGULAR BLOCKY, SUBANGULAR BLOCKY, PLATY, WEDGE, PRISMATIC, COLUMNAR, SINGLE GRAIN, MASSIVE, OR CLODDY)	% SUBSURFACE COARSE FRAGMENTS (USCS - Gravel 4.8mm-76mm (3"), Cobbles 3"-11.8", Boulders 11.8"+)	COMMENTS
			MATRIX COLOR	REDOXOMORPHIC FEATURES					
				COLOR	QUANITY (FEW <2%, COMMON 2-20%, MANY >20%)				
TP 5		713.20							
0 / 1	TOPSOIL								
1 / 13.3	CL	CLAY LOAM	5YR 4.4	—	—	DRY	MASSIVE	—	
TP 4	714.3								
1 / 13.8	CL	CLAY LOAM	5YR 4.4	—	—	DRY	MOIST	—	

ADDITIONAL COMMENTS

LOG OF SOIL TEST PIT

Project: Dawson (Ledgeview Farms)
Site Location: NW¼ SW¼ Sec 28 T23N R21E
Date: 5/14/17
Weather: Overcast
Land Use: Ag Field
Coordinate System: Brown Co. / USGS

Boring No: TP6
Proposed Practice: 313
Logged By: Dana Zelle
Surface Elevation: (T) 708.9(6) 711.3
Bench Mark: GPS

LIMITING FACTORS
Ground Water: N/A / Present - EL.____
Perched Water: N/A / Present - EL.____ to EL.____
Bedrock: N/A / Present - EL.____
Type of Bedrock:____
Sink Hole('s) Within 1000FT: Yes / No / Not Visible

DEPTH FEET	USCS	USDA	MUNSELL COLOR			MOISTURE (USDA - FROZEN, DRY, MOIST, OR SATURATED)	STRUCTURE (USDA - GRANULAR, ANGULAR BLOCKY, SUBANGULAR BLOCKY, PLATY, WEDGE, PRISMATIC, COLUMNAR, SINGLE GRAIN, MASSIVE, OR CLODDY)	% SUBSURFACE COARSE FRAGMENTS (USCS - Gravel 4.8mm - 76mm (3"), Cobbles 3"-11.8", Boulders 11.8"+)	COMMENTS
			MATRIX COLOR	REDOXOMORPHIC FEATURES: COLOR	REDOXOMORPHIC FEATURES: QUANITY (FEW <2%, COMMON 2-20%, MANY >20%)				
TP #7	SURFACE EL.	708.9							
0 / .7	TOPSOIL								
.7 / 8.5	CL	CLAY LOAM	5YR 4.4	—	—	MOIST	MASSIVE	—	
TP #6	SURFACE EL	711.3		10.3 cm					
0 / 1	TOP SOIL					DRY			
1 / 11.1	CL	CLAY LOAM	5YR 4.4	—	—	DRY	MASSIVE	—	

ADDITIONAL COMMENTS

Ledgeview Dairy

WETLAND DELINEATION CONFIRMATION REQUEST CHECK LIST

WDNR WETLAND IDENTIFICATION PROGRAM

The following is the preferred order for all information provided in wetland delineation reports submitted for wetland confirmation. All of the following must be included with all wetland delineation reports that are submitted for confirmation:

X Introductory Section
- Why the delineation was undertaken
- Date the field work was completed
- Who conducted field work
- Qualifications

X Methods used during the wetland delineation
- Description of methods
- Sources Reviewed (WWI mapping, Soil Survey, etc.)
- Description of any site specific agency guidance (site meetings, etc.)

X Results and Discussion
- Antecedent hydrologic condition analysis
- Previous wetland delineation mapping
- Existing environmental mapping (WWI mapping, Soil survey, etc.)
- Amount and types of wetland located within the project area
- Discussion explaining how the wetland/upland boundary was differentiated
- Disturbed and problematic areas encountered during the delineation
- Other water resources located in the project area (navigable streams, etc.)

X Topographic mapping
- Map scale
- Clearly identified project area
- A north arrow

X WWI mapping
- Map scale
- Clearly identified project area
- A north arrow

X Soil Survey mapping
- Map scale
- Clearly identified project area
- A north arrow

X Wetland Delineation Map
- Map scale
- Clearly identified project area
- A north arrow
- Accurate depiction of wetland boundaries and data points identified during the field investigation

X Complete, legible wetland delineation data forms from the appropriate regional supplement

X Site photos

X Any previous delineation information

X Areas that are currently, or were recently (less than three years prior to the delineation) under agricultural production must include a Farm Service Agency Slide Review. All FSA Slide Reviews should include the following:

- Copies or photos of slides if available
- A completed wetland documentation form (NRCS form NRCS-CPA-32W)
- A copy of the draft NRCS Wetland Inventory map if available

X Literature Cited

Please include this completed checklist with all wetland delineation report submittals.

Wetland Determination Report

Ledgeview Dairy
3499 Lime Kiln Road
Green Bay, WI 54311

Section 28 & 29, T.23N.-R.21E.
Town of Ledgeview, Brown County

September 19, 2017

Prepared by:
Rachel Ecker
Roach & Associates, LLC
856 N. Main Street
Seymour, WI 54165
Office (920) 833-6340

Wetland Determination Table of Contents
Ledgeview Dairy

Page

Wetland Determination Report 1-5

Attachments	Exhibit
Project Location Map	1
Maps, Historical Aerial Photos & Site Photos	2
Historical Aerial Photo Hydrologic Review	3
Soils Characteristics & Hydric Soil Rating	4
Weather Information	5
Wetland Determination Data Forms	6
Sample Point Location & Proposed Pipeline Location	7

Wetland Determination Report

Wetland Determination Report

Introduction

Ledgeview Dairy has retained Roach & Associates, LLC to design a waste storage facility. Ledgeview Dairy is located at 3499 Lime Kiln Road, Green Bay, WI. The proposed waste storage facility will be constructed in a cropfield north of the satellite heifer site. Exhibit 1 – Project Location Map. Ledgeview Dairy is located in Section 28, T23N-R21E, Town of Ledgeview, Brown County. The Wisconsin Department of Natural Resources (WDNR) Surface Water Data Viewer (SWDV) has identified wetland indicator soils in the proposed project area.

On September 5, 2017, Rachel Ecker of Roach & Associates, LLC conducted a site visit to complete a wetland investigation at Ledgeview Dairy. Rachel completed the UW LaCrosse Wetland Delineation Training Workshops in 2015.

Methodology

The wetland investigation followed the protocols outlined in the United States Army Corps of Engineers (USACE) Corps of Engineers 1987 Wetland Delineation Manual and 2012 Regional Supplement to the Corps of Engineers 1987 Wetland Delineation Manual: Northcentral and Northeast Region (Version 2.0).

- Vegetation was observed within a 5', 15' and 30' radius of the sample points.
- All species identified and percent cover was recorded on the wetland determination data form identifying the dominant species.
- Each sample point area was observed for indicators of hydrology, surface water, water table or saturation. If an indicator was observed or water was present, the depth and indicator was recorded on the data form.
- Test pits were excavated to a minimum depth of 24" to confirm the presence or absence of hydric soil indicators and the water table.
- The soil matrix color and texture were determined and recorded on the data form.
- The Northcentral/Northeast Region Wetland Determination Data Form was used to record information at each sample point.

Sources Reviewed – Exhibit 2

Prior to completing the field investigation, aerial photographs, soils map, topographic maps and wetland maps were reviewed to identify specific areas on site requiring an investigation within the Project Area. Site photos were taken to provide a visual of the site and show existing conditions at the time of the field investigations.

Aerial Photographs, Maps and Related

- Plat Map – Town of Ledgeview, Brown County
- Historical Aerial Photo: FSA aerial imagery – 1981 – 2002
  Google Earth Pro – 2005, 2006, 2008, 2010, 2011, 2015 & 2017
- Soils: NRCS web soil survey map
- Topography: Brown County GIS Topographical Map
- Wetland: WDNR SWDV Wetland Indicator Map

Twenty eight (28) historical aerial images were reviewed and an aerial photo hydrologic review was completed for the project areas, see Exhibit 3. A total of nineteen (19) aerial photos were identified as receiving normal precipitation amounts in the three month period prior. Wet signatures were identified on three (3) out of the 19 normal precipitation historical images for Project Area 1 and Project Area 2.

The NRCS web soil survey map, hydric soils rating and hydric soils list was reviewed to identify the soils onsite and soil characteristics. Soil KhB – Kewanee silt loam, 2-6% slopes was investigated in Project Area 1. Soil MaA – Manawa sandy loam, 1-3% slopes was investigated in Project Area 1 and 2. KhB is defined as adequately drained and is not considered to be hydric. MaA is defined as somewhat poorly drained and rated as 1-32% hydric. Hydric soil rating and soils characteristic information can be found in Exhibit 4 for the above listed soils.

Weather Information – (Exhibit 5)

Weather information from the Natural Resources Conservation Service (NRCS), Field Office Technical Guide (FOTG), Section II, Climatic Data, for the period prior to the field investigation was recorded. Weather data from the Green Bay A S Intl AP WETS Station was used. The NRCS Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination is used to evaluate the precipitation Condition Value for the three (3) months prior to the field investigation and the historical aerial photo hydrologic review. The three month period prior to the field investigations was considered normal.

Agency Guidance

No agency guidance was obtained.

Site History and Current Land Use

In 1985, Ledgeview Dairy purchased the housing facilities and associated cropland to house steers and young stock. In 1988, 1994 and 2000, the dairy operation expanded their milking cow herd which required an increase in the heifers. In those three years, the operation constructed additional housing for the heifers located on Lime Kiln Road reaching their current cattle numbers and existing housing facilities. The feed storage area was expanded in the early 1990's to accommodate for additional feed needed for the increase in the number of heifers. The feed storage area was recently expanded to the west.

Results and Discussion

Project Area 1 Observation & Results

Project Area 1 is located north of the existing housing facilities. One wetland was identified within project area 1 and labeled Wetland 1. Two (2) sample points were excavated within the wetland to identify the wetland boundary (see Exhibit 6 – Wetland Determination Data Forms). The waste storage facility is proposed to be constructed north of Wetland 1 in the cropfield.

Wetland 1

Sample points 102A and 103A were excavated within Wetland 1 to identify the wetland boundary. Sample point 103A was observed as an upland point. Sample point 102A was observed as a wetland point. Hydrology indicators present were D2 – Geomorphic position and D5 – FAC-Neutral Test. Hydric soil indicator F6 – Redox Dark Surface was observed and the dominant hydrophytic vegetation observes was Phragmites australis. Wetland 1 is located at the toe of slope of the berm constructed to reach the required elevation for the housing facilities.

Wetland 1 is a wetland that appears to have been created due to the construction of the housing facilities. Roof runoff from the machine shed and freestall barn flows north and west to Wetland 1. Additional sample points were excavated to the south and west of Wetland 1. Sample point 101A was excavated west of the machine shed. Hydrology indicator B9 – Water Stained Leaves and dominant hydrophyte Phragmites australis was observed within the sample point. No hydric soils were identified. Sample point 104A was excavated along the toe of slope showing no indicators of hydrology or hydric soils. Vegetation was dominated by hydrophyte Phragmites australis. Sample point 105A was excavated west of 104A along the toe of slope. No hydrology indicators were observed. Hydric soil indicator F6 – Redox Dark

Surface and vegetation was dominated by hydrophyte Phragmites australis. Sample points 101A, 104A and 105A were not identified as wetland sample points since all wetland indicators were not observed. A site plan with the Project Area, sample point locations, wetland boundary and proposed facilities location can be found in Exhibit 7.

Sample Points 201B-205B

Sample points 201B-205B were excavated west of the proposed waste storage facility in the same cropfield (see Exhibit 6 – Wetland Determination Data Forms). Sample points 201B and 203B showed no indicators of hydrology, hydric soils or hydrophytic vegetation. Sample point 202B, 204B and 205B showed no indicators of hydrology or hydrophytic vegetation. Hydric soil indicator F6 – Redox Dark Surface was observed. At the time of the field investigations, the cropfield was plowed and no vegetation was present for observation within the five (5) sample points. Sample points 202B, 204B and 205B were not identified as wetland sample points since two (2) out of three (3) wetland indicators were not observed.

A site plan with the Project Area, sample point locations, wetland boundary and proposed facilities location can be found in Exhibit 7.

Sample Points 301C-303C

Sample points 301C-303C were excavated within the footprint of the proposed waste storage facility in the cropfield north of the existing facilities (see Exhibit 6 – Wetland Determination Data Forms). Sample points 301C-303C showed no indicators of hydrology, hydric soils or hydrophytic vegetation. At the time of the field investigations, the cropfield was plowed and no vegetation was present for observation within the three (3) sample points. No hydrology indicators were observed. Soils identified was a silt loam colored as 10YR 3/2 down to 7"-16" and a clay colored as 5YR 4/4 down to 24". A wetland was not identified since no wetland indicators were observed within the sample point locations.

A site plan with the Project Area, sample point locations, wetland boundary and proposed facilities location can be found in Exhibit 7.

Project Area 2 Observation & Results

Project Area 2 is located within the feed storage area, south of the existing housing facilities and cow yard. One wetland was identified near the project area and labeled Wetland 2. Six (6) sample points were excavated within the wetland to identify the wetland boundary (see Exhibit 6 – Wetland Determination Data Forms). Ledgeview Dairy proposes to expand the feed storage area to the south of the existing feed storage area.

Wetland 2

Sample points 402D, 404D and 406D were observed as upland points. Sample point 404D showed no indicators present. Sample points 402D and 406D showed no hydrology or hydric soil indicators but Ambrosia trifida was observed as a dominant hydrophyte. Sample points 401D, 403D and 405D were observed as wetland points. Hydrology indicators present were C3 – Oxidized Rhizospheres on Living Roots, D2 – Geomorphic Position and D5 – FAC-Neutral Test. Hydric soil indicators observed were F6 – Redox Dark Surface and A11 – Depleted Below Dark Surface with Phragmites australis and Phalaris arundinacea as dominant hydrophytic vegetation.

Wetland 2 has been identified as a farm drainage ditch that starts approximately 475' south of the existing feed storage and flows northwest. An artesian well is located at the start of the farm drainage ditch. The proposed expansion of the feed storage area will extend approximately 100 feet south of the existing feed storage area.

A site plan with the Project Areas, Wetlands and Sample Point locations along with the proposed facilities location can be found in Exhibit 7.

Conclusion

Roach & Associates, LLC identified one wetland within the Project Area 1 and one wetland west of Project Area 2. WDNR and/or ACOE must provide the final wetland determination and a WDNR and/or ACOE concurrence is required before the construction of the proposed waste storage facility and feed storage area. When the wetland determination receives concurrence and dependent on the proposed construction activities, necessary permits must be obtained prior to construction.

To the best of my professional knowledge, judgment and belief, wetland 1 and wetland 2 boundaries have been identified as accurately as possible based on the field data recorded. My opinion is based upon the wetland protocols outlined in the United States Army Corps of Engineers (USACE) 2012 Regional Supplement to the Corps of Engineers 1987 Wetland Delineation Manual: Northcentral and Northeast Region (Version 2.0).

Rachel Ecker

Rachel Ecker, Wetland Coordinator

9-19-17

Date

References

1. US Army Corps of Engineers (USACOE), Regional Supplement to the Corps of Engineers Wetland Delineation Manual, 1987

2. US Army Corps of Engineers (USACOE), Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region, (version 2.0), 2012

3. USDA, NRCS, Field Indicators of Hydric Soils in the United States, A Guide for Identifying and Delineating Hydric Soils, Version 8.1, 2017

4. Lichvar, R.W., M. Butterwick, N.C. Melvin, and W.N. Kirchner, USACOE The National Wetland Plant List: 2016 Update of Wetland Ratings, Phytoneuron 2016-30: 1-17. Published 28 April 2016.

5. USDA, FSA Aerial Imagery

6. Google Earth Pro Aerial Images

7. WDNR, SWDV, wetland indicator soil map and topographical map

8. USDA, NRCS, Web Soil Survey

9. USDA, NRCS, Hydric Rating by Map Unit

10. Brown County GIS

11. USDA, NRCS, FOTG, Section II, Climatic Data, Agricultural Applied Climate Information System

12. Judziewicz, Emmet J., Clark, Lynn G., Freckmann, Robert W., and Black, Merel R., 2014, Field Guide to Wisconsin Grasses, Madison, Wisconsin, The University of Wisconsin Press

13. Hipp, Andrew L., 2008, Field Guide to Wisconsin Sedges, An Introduction to the Genus *Carex* (Cyperaceae), Madison, Wisconsin, The University of Wisconsin Press

14. Black, Merel R. and Judziewics, Emmet J., 2009, Wildflowers of Wisconsin and The Great Lakes Region, Madison, Wisconsin, The University of Wisconsin Press

Exhibit 1




Ledgeview Dairy
Location Map
Legend
Greenbrier Rd
Bellevue
Gunn St
Hazel Rd
Bellevue St
Hoffman Rd
Allouez Ave
Brown
172
43
29
Klondike Rd
Ledgeview Dairy
Google earth
© 2017 Google
N
2 mi

Exhibit 2

©2006
Brown
County
Wisconsin

T23N R21E (SW)

Ledgeview & Bellevue(SW)



Map Legend

- Property Boundaries (with acreages**)
- Municipal Boundaries
- Interstate, U.S or State Highway
- County Highway
- Other Road or Street
- Railroads
- Lakes, Ponds, & Rivers
- Trails
- Woodlands/Natural Areas
- Address Grid numbering
- Section or other PLSS line
- Section numbers

**The acreages shown on this map are based on the latest and most accurate parcel mapping which may differ slightly from the acreages shown on the tax roll.

For more detailed or up-to-date maps please visit us online at:
www.gis.co.brown.wi.us

15

Copyright 2006 Brown County
Planning & Land Services
Aug 04, 2006

Ledgeview Dairy, LLC – Historical Aerial Photos



FSA Aerial Photo July 1981




FSA Aerial Photo July 1982

Ledgeview Dairy, LLC – Historical Aerial Photos



FSA Aerial Photo July 1983



FSA Aerial Photo June 1984



FSA Aerial Photo July 1985




FSA Aerial Photo August 1986




FSA Aerial Photo 1987 – Unknown Month of Photo



FSA Aerial Photo June 1989



FSA Aerial Photo June 1990




FSA Aerial Photo August 1991




FSA Aerial Photo 1992 – Unknown Month of Photo



FSA Aerial Photo 1993 – Unknown Month of Photo




FSA Aerial Photo 1994 – Unknown Month of Photo




FSA Aerial Photo 1995 – Unknown Month of Photo




FSA Aerial Photo June 1996




FSA Aerial Photo June 1997



FSA Aerial Photo August 1998



FSA Aerial Photo July 1999




FSA Aerial Photo August 2000




FSA Aerial Photo June 2001

Ledgeview Dairy, LLC – Historical Aerial Photos




FSA Aerial Photo July 2002




Google Earth Aerial Photo May 2005



Google Earth Aerial Photo June 2006



Google Earth Aerial Photo June 2008



Google Earth Aerial Photo June 2010




Google Earth Aerial Photo October 2011

Ledgeview Dairy, LLC – Historical Aerial Photos



Google Earth Aerial Photo April 2015



Google Earth Aerial Photo April 2017

Soil Map—Brown County, Wisconsin
(Ledgeview Dairy - Soils Map)



Map Scale: 1:4,650 if printed on A portrait (8.5" x 11") sheet.

N

Meters: 0 50 100 200 300

Feet: 0 200 400 800 1200

Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 16N WGS84

MAP LEGEND

Area of Interest (AOI)
- Area of Interest (AOI)

Soils
- Soil Map Unit Polygons
- Soil Map Unit Lines
- Soil Map Unit Points

Special Point Features
- Blowout
- Borrow Pit
- Clay Spot
- Closed Depression
- Gravel Pit
- Gravelly Spot
- Landfill
- Lava Flow
- Marsh or swamp
- Mine or Quarry
- Miscellaneous Water
- Perennial Water
- Rock Outcrop
- Saline Spot
- Sandy Spot
- Severely Eroded Spot
- Sinkhole
- Slide or Slip
- Sodic Spot
- Spoil Area
- Stony Spot
- Very Stony Spot
- Wet Spot
- Other
- Special Line Features

Water Features
- Streams and Canals

Transportation
- Rails
- Interstate Highways
- US Routes
- Major Roads
- Local Roads

Background
- Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Brown County, Wisconsin
Survey Area Data: Version 10, Sep 27, 2016

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.


Date(s) aerial images were photographed: Sep 9, 2011—Aug 14, 2014

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Brown County, Wisconsin (WI009)			
Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
AeA	Allendale fine sandy loam, 0 to 3 percent slopes	5.8	7.5%
KhB	Kewaunee silt loam, 2 to 6 percent slopes	39.3	51.1%
KhB2	Kewaunee silt loam, 2 to 6 percent slopes, eroded	1.5	1.9%
KhC2	Kewaunee silt loam, 6 to 12 percent slopes, eroded	2.0	2.6%
MaA	Manawa sandy loam, 1 to 3 percent slopes	25.9	33.6%
McA	Manawa silty clay loam, 0 to 3 percent slopes	1.9	2.5%
Po	Poygan silty clay loam, 0 to 2 percent slopes, drained	0.6	0.8%
Totals for Area of Interest		**77.0**	**100.0%**

Ledgeview Dairy Topographical Map



Legend

- Municipality
- State Boundaries
- County Boundaries
- Major Roads
  - Interstate Highway
  - State Highway
  - US Highway
- County and Local Roads
  - County HWY
  - Local Road
- Railroads
- Tribal Lands
- Rivers and Streams
- Intermittent Streams
- Lakes and Open water
- Index to EN_Image_Basemap_Leaf_Off

Notes


0.3 0 0.13 0.3 Miles

NAD_1983_HARN_Wisconsin_TM

1: 7,920

DISCLAIMER: The information shown on these maps has been obtained from various sources, and are of varying age, reliability and resolution. These maps are not intended to be used for navigation, nor are these maps an authoritative source of information about legal land ownership or public access. No warranty, expressed or implied, is made regarding accuracy, applicability for a particular use, completeness, or legality of the information depicted on this map. For more information, see the DNR Legal Notices web page: http://dnr.wi.gov/legal/

Ledgeview Dairy Wetland Map



Legend

- Wetland Class Points
  - Dammed pond
  - Excavated pond
  - Filled excavated pond
  - Filled/drained wetland
  - Wetland too small to delineate
- Filled Points
- Wetland Class Areas
  - Wetland
  - Upland
- Filled Areas
- NRCS Wetspots
- Wetland Indicators
- Municipality
- State Boundaries
- County Boundaries
- Major Roads
  - Interstate Highway
  - State Highway
  - US Highway
- County and Local Roads
  - County HWY
  - Local Road
- Railroads
- Tribal Lands
- Rivers and Streams
- Intermittent Streams
- Lakes and Open water
- Index to EN_Image_Basemap_Leaf_Off

Notes

0.1 0 0.06 0.1 Miles


NAD_1983_HARN_Wisconsin_TM

1: 3,960


DISCLAIMER: The information shown on these maps has been obtained from various sources, and are of varying age, reliability and resolution. These maps are not intended to be used for navigation, nor are these maps an authoritative source of information about legal land ownership or public access. No warranty, expressed or implied, is made regarding accuracy, applicability for a particular use, completeness, or legality of the information depicted on this map. For more information, see the DNR Legal Notices web page: http://dnr.wi.gov/legal/



At west side of sample point 101A looking southeast.



At west side of Wetland 1 looking east.



West of sample point 105A looking east.




North side of sample point 201B looking south.




At sample point 203B looking northeast.




At southside of sample point 205B looking southwest.



At southside of sample point 301C looking south towards housing facilities.



At sample point 401D looking west.



At sample point 403D looking southeast towards Lime Kiln Road.



At sample point 403D looking northwest.

LOG OF SOIL TEST PIT

Project: PRIESS (Ledgeview Farms)
Site Location: NW¼ SW¼ Sec 28 T23N R21E
Date: 5/14/17
Weather: Overcast
Land Use: Ag Field
Coordinate System: BrownCo. / USGS

Boring No: 9 & 8
Proposed Practice: 317
Logged By: Drew Zelle
Surface Elevation: (9) 712.5 (8) 710.4
Bench Mark: GPS

LIMITING FACTORS
Ground Water: N/A / Present - EL.____
Perched Water: N/A / Present - EL.____ to EL.____
Bedrock: N/A / Present - EL.____
Type of Bedrock:____
Sink Hole('s) Within 1000FT: Yes / No / Not Visible

DEPTH FEET	USCS	USDA	MUNSELL COLOR			MOISTURE (USDA - FROZEN, DRY, MOIST, OR SATURATED)	STRUCTURE (USDA: GRANULAR, ANGULAR BLOCKY, SUBANGULAR BLOCKY, PLATY, WEDGE, PRISMATIC, COLUMNAR, SINGLE GRAIN, MASSIVE OR CLOSED)	% SUBSURFACE COARSE FRAGMENTS (USCS - Gravel 4.8mm-76mm (3"), Cobbles 3"-11.8", Boulders 11.8"+)	COMMENTS
			MATRIX COLOR	REDOXOMORPHIC FEATURES: COLOR	REDOXOMORPHIC FEATURES: QUANITY (FEW <2%, COMMON 2-20%, MANY >20%)				
TP 9	SR. GL		712.5	C = 11.5					
0 / .5'			~~5YR 4.4~~	TOPSOIL					
.5 / 12.0	CL	Clay Loam	5YR 4.4						
TP 8	SURFACE EL.		710.4	C = 9.4					
0 / .7	TOPSOIL								
.7 / 9.4	CL	Clay Loam	5YR 4.4	—	—	MOIST	M10,SS-MD	—	

ADDITIONAL COMMENTS

LOG OF SOIL TEST PIT

Project: Pansier / Ledgeview Farms
Site Location: NW¼SW¼ Sec 28 T23N R21E
Date: 5/14/17
Weather: Overcast
Land Use: Ag field
Coordinate System: Brown Co. / USGS

Boring No: TP10 & 11
Proposed Practice: 313
Logged By: Drew Zelle
Surface Elevation: (10) 712.7 (11) 716.5
Bench Mark: GPS

Clay = 11.6'

LIMITING FACTORS
Ground Water: N/A / Present - EL.____
Perched Water: N/A / Present - EL.____ to EL.____
Bedrock: N/A / Present - EL.____
Type of Bedrock:____
Sink Hole('s) Within 1000FT: Yes / No / Not Visible

DEPTH FEET	USCS	USDA	MUNSELL COLOR: MATRIX COLOR	REDOXIMORPHIC FEATURES: COLOR	REDOXIMORPHIC FEATURES: QUANITY (FEW <2% COMMON 2-20% MANY >20%)	MOISTURE (USDA - FROZEN, DRY, MOIST, OR SATURATED)	STRUCTURE (USDA - GRANULAR, ANGULAR BLOCKY, SUBANGULAR BLOCKY, PLATY, WEDGE, PRISMATIC, COLUMNAR, SINGLE GRAIN, MASSIVE, OR CLODDY)	% SUBSURFACE COARSE FRAGMENTS (USCS - Gravel 4.8mm-(3") Cobbles 3"-11.8" Boulders 11.8"+)	COMMENTS
TP10									
0 / 1	Topsoil								
1 / 11.6	CL	Clay loam	5YR 4.4	—	—	Moist	Mass-Wb	—	Minimal Calcium CL Streaks Small seep @ base
TP 11	716.5 GND GL.								
0 / .5	minimal topsoil								
.5 / 12.7	CL	Clay loam	5YR 4.4	—	—	Moist	Mass-Wb	—	—
12.7 / 14.7	ML	Silt	7.5YR 3/1	10YR 7.1	10YR 7.1 Common				Seep @ 12.4
ADDITIONAL COMMENTS 14.7-16.0 CL		Clay loam	7.5YR 4/1	—	—	Moist	Mass-Wb		

LOG OF SOIL TEST PIT

Project: PRINSEN (Hedgerow Farm)
Site Location: NW¼ SW¼ Sec 28 T23N R21E
Date: 5/14/17
Weather: Overcast
Land Use: Ag Field
Coordinate System: Brown Co. / USGS

Boring No: TP 12
Proposed Practice: 313
Logged By: Drew Zelle
Surface Elevation: 715.85
Bench Mark: GPS

LIMITING FACTORS
Ground Water: N/A / Present - EL.____
Perched Water: N/A / Present - EL.____ to EL.____
Bedrock: N/A / Present - EL.____
Type of Bedrock:____
Sink Hole('s) Within 1000FT: Yes / No / Not Visible

DEPTH FEET	USCS	USDA	MUNSELL COLOR			MOISTURE (USDA - FROZEN, DRY, MOIST, OR SATURATED)	STRUCTURE (USDA - GRANULAR, ANGULAR BLOCKY, SUBANGULAR BLOCKY, PLATY, WEDGE, PRISMATIC, COLUMNAR, SINGLE GRAIN, MASSIVE, OR CLODDY)	% SUBSURFACE COARSE FRAGMENTS (USCS - Gravel 4.8mm-75mm (3"), Cobbles 3"-11.8", Boulders 11.8"+)	COMMENTS
TP12			MATRIX COLOR	REDOXOMORPHIC FEATURES: COLOR	REDOXOMORPHIC FEATURES: QUANITY (FEW <2%, COMMON 2-20%, MANY >20%)				
0 / 1	Topsoil								
1 / 14.5	CL / ML	clay loam	5YR 4/4	—	—	Moist	Blocky	—	Calcium chloride streaks
14.5	~~ML~~ CL	clay loam	5YR 6.1	—	—	Moist	Massive	—	—

ADDITIONAL COMMENTS:

LOG OF SOIL TEST PIT

Project: PAWS: GR (Ledgeview Farms)
Site Location: NW¼SW¼ Sec 28 T23N R21E
Date: 5/14/17
Weather: Overcast
Land Use: Ag Field
Coordinate System: Brown Co. / USGS

Boring No: 14 & 13
Proposed Practice: 313
Logged By: Drew Zelle
Surface Elevation: (14) 713.9 (13) 714.3
Bench Mark: GPS

713.9

LIMITING FACTORS
Ground Water: N/A / Present - EL.____
Perched Water: N/A / Present - EL.____ to EL.____
Bedrock: (N/A) / Present - EL.____
Type of Bedrock:____
Sink Hole('s) Within 1000FT: Yes / No / (Not Visible)

DEPTH FEET	USCS	USDA	MUNSELL COLOR: MATRIX COLOR	REDOXOMORPHIC FEATURES: COLOR	REDOXOMORPHIC FEATURES: QUANITY (FEW <2% COMMON 2-20% MANY >20%)	MOISTURE (USDA - FROZEN, DRY, MOIST, OR SATURATED)	STRUCTURE (USDA - GRANULAR, ANGULAR BLOCKY, SUBANGULAR BLOCKY, PLATY, WEDGE PRISMATIC, COLUMNAR, SINGLE GRAIN, MASSIVE OR CLODDY)	% SUBSURFACE COARSE FRAGMENTS (USCS - Gravel 4.8mm-76mm (3"), Cobbles 3"-11.8", Boulders 11.8"+)	COMMENTS
TP 14	SURFACE EL.		713.9	CM 12.8					
0 / 1'	TOPSOIL								
1 / 12.9	CL	CLAY LOAM	5YR 4.4	—	—	DRY	MASSIVE		
TP 13 0 / 1	714.3 TOPSOIL		13.3 CM						
1 / 14.5	CL	CLAY LOAM	5YR 4.4						

ADDITIONAL COMMENTS:

SAMPLE Sent to LAB

Roach & Associates, LLC - Log of the Test Pits

Land Owner: LEDGEVIEW Date: 10/11/17

Logged by: JR & MP

Test Pit Number: 17 TP Elv. 7068

Test Pit Location: North of TP 18 West of TP 23

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sample ID & Elv
	0	1		TOPSOIL				
	1	5.0	CL	MOSTLY RED BROWN MASSIVE	2.5YR 4/4			
	5.0	9.0	CL	clay, DRY	5YR 4/4			1@7'
	9.0	11.5	CL	clay, DRY PLATY	2.5YR 3/3			
				NO Groundwater				
				NO Bedrock				
				Proctor test @ 7.5'				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained soils 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Ledgeview
Logged by: JR & MP
Test Pit Number: 18
Test Pit Location: North of TP 19

Date: 10/11/17
TP Elv. 708.8

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sample ID & Elv
	0	1		TOPSOIL				
	1	4.5	CL	RED BROWN MASSIVE MOIST	2.5yr 4/4			
	4.5	7.5	CL	clay DRY PLASTY	5YR 4/4			
	7.5	12	CL	clay DRY PLASTY	2.5yr 3/3			1@8.
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained soils 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

SAMPLE Sent to LAB

Roach & Associates, LLC - Log of the Test Pits

Land Owner: LEDGEVIEW
Logged by: MP & JR
Test Pit Number: 19
Test Pit Location: WEST OF TP 21

Date: 10/11/17
TP Elv. 708.9

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sample ID & Elv
	0	1.5		TOPSOIL				
	1.5	4.5	CL	RED BROWN Moist Mottles	2.5YR 4/4			
	4.5	11	CL	BROWN Dry Platy	7.5YR 3/3			1@9.5
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained soils 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

SAMPLE Sent to LAB

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Ledgeview
Logged by: JR & MP
Test Pit Number: 20
Test Pit Location: South of TP 19

Date: 10/11/17
TP Elv. 713.07

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sample ID & Elv
	0	1		TOPSOIL				
	1	3.5	CL	clay Moist Massive	2.5YR 4/4			
	3.5	12.5	CL	clay DRY PLAT 1	5YR 4/4			Sample 1@7
	12.5	13.5	CL	Clay DRY PLAT Y	2.5YR 3/3			
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained soils 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

SAMPLE Sent to LAB

Roach & Associates, LLC - Log of the Test Pits

Land Owner: LEDGELIEN

Date: 10/11/17

Logged by: JR & MP

Test Pit Number: 21

TP Elv. 713.3

Test Pit Location: South of TP 22

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sample ID & Elv
	0	1.0		CLAY LOAM TOPSOIL				
	1.0	2.0	CL	Moist RED BROWN MASSIVE clay	2.5YR 4/4	—	—	
	2.0	12.0	CL	Dry Red Brown Platy. Clay	2.5YR 4/4			1@7.
				NO BR OR GW				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained soils 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: LEDGEVIEW
Logged by: JMR & MP
Test Pit Number: 22
Test Pit Location: South of TP23

Date: 10/10/17
TP Elv. 715.4

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sample ID & Elv
	0	1.0		CLAY LOAM TOPSOIL				
	1.0	2.0	CL	MOIST RED BROWN MASSIVE clay	2.5YR 4/4	–	–	1 @ 10.0'
	2.0	12.0	CL	DRY RED BROWN PLATY clay	2.5YR 4/4	–	–	
	12.0	13.5	CL	DRY RED BROWN PLATY clay	2.5YR 3/3	–	–	
				NO BR OR GW				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained soils 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

SAMPLES SENT TO LAB

Roach & Associates, LLC - Log of the Test Pits

Land Owner: LodgeView Dairy Date: 10.10.17
Logged by: JMR + MD
Test Pit Number: 23 TP Elv. 711.4
Test Pit Location: NETP in Tilled Soil East of Barn

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sample ID & Elv
711.4	0	1.0		CL LOAM TOPSOIL				
	1.0	2.0	CL	MOIST SML MOTTELS MASSIVE	2.5YR 4/4			
	2.0	7.0	CL	DRY MASSIVE	5YR 4/4			1@ 6.0'
	7.0	11.0	CL	DRY PLATY	5YR 4/4			
	11.0	13.0	CL	DRY PLATY	2.5YR 3/3			2@ 12.5
				WATER @ 13'				
				NO BEDROCK				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained soils 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: LEDGEVIEW
Logged by: MHP/TJS
Test Pit Number: #54
Test Pit Location:

Date: 6/9/17
TP Elv. 715.38

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Samp ID & E
	0	1		Topsoil				
	1	5	SC	moist	5YR 4/4			
	5	11	CL	Platey Clay firm moist	5YR 4/4			#1 @ 8ft
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Ledgeview
Logged by: TJS, MHP
Test Pit Number: # 55
Test Pit Location: West of Heifer Lot (Heifer Farm)

Date: 10/19/17
TP Elv. 725.32

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sampl ID & El
	0	5	SC	10% Gravel	2.5 Y/R 4/8			#1 @ 2.5ft
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Ledgeview
Logged by: MHP, TJS
Test Pit Number: #56
Test Pit Location: Heifer FARM: West of Bunker

Date: 10/19/2017
TP Elv. 728.53

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sampl ID & El
	0	5	CL	Dry, Massive, firm	5YR 4/4			#1 @ 3ft
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained [illegible]0% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Edgeview
Logged by: MHP/TTS
Test Pit Number: #57
Test Pit Location:

Date: 10/17/17
TP Elv. 725.20

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Samp ID & E
	0	5	CL	Dry, massive, fill Fill	5YR 3/3			#1 C3(
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained ≥ 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Ledgeview
Logged by: MHP, TJS
Test Pit Number: 58
Test Pit Location: Helfer Farm: South of FSA

Date: 10/19/2017
TP Elv. 723.42

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sampl ID & El
	0	1.5		Topsoil				
	1.5	2.0	CL MK/C	Massive Dry	5YR 4/6			
	2.0	5.0	CL	Platey 20% mottles → 2.5YR 4/6	2.5YR 4/4			
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Ledgeview
Logged by: MHP, TJS
Test Pit Number: #59
Test Pit Location: West of TP #60

Date: 10/19/2017
TP Elv. 725.79

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Samp ID & E
	0	1	ML	Top Soil				
	1	3	CL	Platey, Dry 50% 2.5YR4/6	2.5YR 4/4			#1 @ 2ft
	3	~~10~~ 9	CL	Massive, Dry	2.5YR 4/4			
	9	10	SC	Dry Massive	5YR 4/4			#2 @ 10ft
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained ≥ 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Ledgeview
Logged by: JJS, MHP
Test Pit Number: 60
Test Pit Location: South of bunker

Date: 10/19/2017
TP Elv. 726.42

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sampl ID & El
	0	1.5	ML	Topsoil Dry				
	1.5	10	CL	Dry, massive, firm 9ft Seam of CL Platey 2.5YR 4/6	2.5YR 4/6			#1 @ 8ft Bw
	10	13.0	CH	clay, dry massive 7.5YR 5/2	~~10YR 4/2~~			#2 Bw @ 11.5
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Ledge View
Logged by: TJS, MHP
Test Pit Number: 61
Test Pit Location: Heifer Farm: South of FSA

Date: 10/18/2017
TP Elv. 729.56

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sample ID & Elv.
	0	1	ML	Topsoil Dry				
	1	10	CL	Dry, massive, Firm ~5ft seam of CL Platey 2.5YR4/6	2.5YR 4/4			#1@ 5ft
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained [illegible]0% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: LEDGEVIEW
Logged by: MHP / JS
Test Pit Number: 62
Test Pit Location: North of the Main Farm FSA

Date: 10/19/17
TP Elv. 810.49

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sampl ID & El
	0	0.15'		TOPSOIL				
	0.15'	1.0'	CL	MASSIVE, MOIST	5YR 5/3			SAMPLE
	1.0	3.0	SC	CLAY SAND	7.5YR 5/3			
				NO Groundwater				
				NO Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained soils 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: LEDGEVIEW
Logged by: MHP + TJS
Test Pit Number: G3
Test Pit Location: North of TP G2

Date: 10/19/17
TP Elv.

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sampl ID & El
	0	0.15"		TOPSOIL				
	0.15	1'	CL	CLAY	5YR 5/3			SAMP. 6"
	1'	3'	SC	CLAY SAND	7.5YR 5/3			SAMP 2.5'
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Lodgeview Farms
Logged by: MHP
Test Pit Number: C4
Test Pit Location: East of Heifer Lot on the Main Farm

Date: 10/25/17
TP Elv. 825.75

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Samp ID & E
	0	1.5		TOPSOIL				
	1.5	3	CL	MASSIVE Moist	7.5 yr 5/6			1@3
	3	10	ML	DAMP	7.5 yr 4/6			2@7
				NO Groundwater				
				Bedrock @ 10'				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Ledgeview Main Site
Logged by: MHP
Test Pit Number: 65
Test Pit Location: South of L1

Date: 10/25/17
TP Elv. 820.1

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sampl ID & El
818.1	0	2	ML	Topsoil / Fill	-	-	-	-
817.1	2	3	CL	Dry, massive, Firm, lean	2.5YR 4/4	-	-	-
				NO Ground water. NO Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained 50% more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Ledgeview Main Site
Logged by: MHP
Test Pit Number: 66
Test Pit Location: North of L7

Date: 10/25/19
TP Elv. 819.0

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sampl ID & El
818.0	0	1	ML	Topsoil	–	–	–	–
809.0	1	10	CL	Dry, massive, firm, lean	2.5YR 4/4	–	–	–
				No Ground water No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained >50% more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Roach & Associates, LLC - Log of the Test Pits

Land Owner: Ledgeview Dairy Date: 9/15/17
Logged by: RE
Test Pit Number: 406D TP Elv. 716.4
Test Pit Location: West of FSA - Heifer Farm

Elev.	TP Depth From	TP Depth To	Unif'd Sys ID	Description of Soils color, structure, stones, moisture	Munsell ID	Water Table	Bedrock	Sampl ID & E
716.4	0	16"		Topsoil				
	16"	24"	CL	Clay, dry massive, firm	5 YR 4/4			
				No Groundwater				
				No Bedrock				

Major Divisions			Group Symbol	Group Name
Coarse grained soils more than 50% retained on No. 4 sieve	Gravel >50% of coarse fraction retained on No. 4 sieve	clean gravel <5% smaller than No. 200 sieve	GW	well-graded gravel (diverse particle size)
			GP	poorly graded gravel (uniform particle size)
		gravel with > 12% fines	GM	silty gravel (gravel-sand-silt mix)
			GC	clayey gravel (gravel-sand-silt mix)
	Sand > 50% of coarse fraction passes No. 4 sieve	clean sand	SW	well-graded sand (diverse particle size)
			SP	poorly graded sand (uniform particle size)
		sand with >12% fines	SM	silty sand (sand-silt mix)
			SC	clayey sand (sand clay mix)
Fine grained ≥ 50% or more passing the No. 200 sieve	silt and clay liquid limit < 50	inorganic	ML	silt (silt and fine sand)
			CL	clay of low plasticity, lean clay
		organic	OL	organic silt, organic clay (low plasticity)
	silt and clay liquid limit > 50	inorganic	MH	silt of high plasticity, elastic silt
			CH	clay of high plasticity, fat clay
		organic	OH	organic clay, organic silt
			Pt	peat and other highly organic soils

Exhibit 3

Aerial Photo Hydrologic Review

Date: 8.31.17

Landowner: Ledgeview Dairy

Location: Section 28, T23N-R21E, Town of Ledgeview, Brown County

Site Idenfication: Project Area 1 & 2

# of Photos	Aerial Photo Month/Year	Photo Source	Wet, Normal or Dry	Project Area 1 Photo Observations	Project Area 2 Photo Observations
1	July 1981	FSA	N	None	None
2	July 1982	FSA	N	None	None
3	July 1983	FSA	N	None	None
4	June 1984	FSA	N	None	SS
5	July 1985	FSA	N	None	None
6	August 1986	FSA	N	None	SS
7	1987	FSA	Unknown Month of Photo		
8	1988	FSA	Unknown Month of Photo		
9	June 1989	FSA	N	None	None
10	June 1990	FSA	N	None	None
11	August 1991	FSA	N	None	None
12	1992	FSA	Unknown Month of Photo		
13	1993	FSA	Unknown Month of Photo		
14	1994	FSA	Unknown Month of Photo		
15	1995	FSA	Unknown Month of Photo		
16	June 1996	FSA	N	None	None
17	June 1997	FSA	N	SS	None
18	August 1998	FSA	N	None	None
19	July 1999	FSA	N	None	None
20	August 2000	FSA	W	None	SS
21	June 2001	FSA	W	None	None
22	July 2002	FSA	W	None	None
23	May 2005	Google Earth	N	SS	None
24	June 2006	Google Earth	N	None	None
25	June 2008	Google Earth	N	None	None
26	June 2010	Google Earth	N	None	SS
27	October 2011	Google Earth	N	None	None
28	April 2015	Google Earth	D	SS	SS
29	April 2017	Google Earth	N	SS	None

 # normal years: 19

 # normal years with wet signatures Project Area 1: 3

 # normal years with wet signatures Project Area 2: 3

Key

CS - Crop Stress
DO - Drowned Out
NC - Not Cropped
SW - Standing Water
WS - Wetland Signature
NV - Normal Vegetative Cover
NSS - No Soil Wetness
AP - Altered Pattern
SS - Soil Wetness Signature
O - Other Signature

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1981
Photo/obs Date	July 1981	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	June	2.05	4.16	2.63	N	2	3	6
2nd Prior Month*	May	1.60	3.34	0.56	D	1	2	2
3rd Prior Month*	April	1.89	3.01	4.22	W	3	1	3
							Sum	**11**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions: **prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1982
Photo/obs Date	July 1982	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	June	2.05	4.16	2.67	N	2	3	6
2nd Prior Month*	May	1.60	3.34	2.74	N	2	2	4
3rd Prior Month*	April	1.89	3.01	2.66	N	2	1	2
							Sum	**12**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions: **prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1983
Photo/obs Date	July 1983	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	June	2.05	4.16	1.82	D	1	3	3
2nd Prior Month*	May	1.60	3.34	4.80	W	3	2	6
3rd Prior Month*	April	1.89	3.01	1.39	D	1	1	1
							Sum	**10**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1984
Photo/obs Date	June 1984	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	May	1.60	3.34	1.55	D	1	3	3
2nd Prior Month*	April	1.89	3.01	3.33	W	3	2	6
3rd Prior Month*	March	1.21	2.50	1.64	N	2	1	2
							Sum	11

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1985
Photo/obs Date	July 1985	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	June	2.05	4.16	2.21	N	2	3	6
2nd Prior Month*	May	1.60	3.34	2.58	N	2	2	4
3rd Prior Month*	April	1.89	3.01	2.24	N	2	1	2
							Sum	**12**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1986
Photo/obs Date	August 1986	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	July	2.39	4.09	4.95	W	3	3	9
2nd Prior Month*	June	2.05	4.15	4.06	N	2	2	4
3rd Prior Month*	May	1.60	3.34	1.15	D	1	1	1
							Sum	**14**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1989
Photo/obs Date	June 1989	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	May	1.60	3.34	4.22	W	3	3	9
2nd Prior Month*	April	1.89	3.01	0.49	D	1	2	2
3rd Prior Month*	March	1.21	2.50	2.88	W	3	1	3
							Sum	14

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1990
Photo/obs Date	June 1990	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	May	1.60	3.34	3.99	W	3	3	9
2nd Prior Month*	April	1.89	3.01	1.28	D	1	2	2
3rd Prior Month*	March	1.21	2.50	3.25	W	3	1	3
							Sum	**14**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions: **prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1991
Photo/obs Date	August 1991	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	July	2.39	4.09	4.16	W	3	3	9
2nd Prior Month*	June	2.05	4.15	1.08	D	1	2	2
3rd Prior Month*	May	1.60	3.34	2.42	N	2	1	2
							Sum	**13**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1996
Photo/obs Date	June 1996	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	May	1.60	3.34	1.40	D	1	3	3
2nd Prior Month*	April	1.89	3.01	3.85	W	3	2	6
3rd Prior Month*	March	1.21	2.50	1.16	D	1	1	1
							Sum	**10**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1997
Photo/obs Date	June 1997	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	May	1.60	3.34	2.60	N	2	3	6
2nd Prior Month*	April	1.89	3.01	1.57	D	1	2	2
3rd Prior Month*	March	1.21	2.50	1.92	N	2	1	2
							Sum	**10**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1998
Photo/obs Date	August 1998	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	July	2.39	4.09	1.86	D	1	3	3
2nd Prior Month*	June	2.05	4.15	6.17	W	3	2	6
3rd Prior Month*	May	1.60	3.34	2.21	N	2	1	2
							Sum	**11**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	1999
Photo/obs Date	July 1999	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	June	2.05	4.16	3.98	N	2	3	6
2nd Prior Month*	May	1.60	3.34	3.77	W	3	2	6
3rd Prior Month*	April	1.89	3.01	2.11	N	2	1	2
							Sum	**14**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions: **prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	2000
Photo/obs Date	August 2000	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	July	2.39	4.09	6.27	W	3	3	9
2nd Prior Month*	June	2.05	4.15	5.33	W	3	2	6
3rd Prior Month*	May	1.60	3.34	4.41	W	3	1	3
							Sum	**18**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions: **prior period has been wetter than normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	2001
Photo/obs Date	June 2001	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	May	1.60	3.34	4.74	W	3	3	9
2nd Prior Month*	April	1.89	3.01	3.66	W	3	2	6
3rd Prior Month*	March	1.21	2.50	0.42	D	1	1	1
							Sum	**16**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been wetter than normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	2002
Photo/obs Date	July 2002	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	June	2.05	4.16	4.69	W	3	3	9
2nd Prior Month*	May	1.60	3.34	2.81	N	2	2	4
3rd Prior Month*	April	1.89	3.01	3.02	W	3	1	3
							Sum	**16**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been wetter than normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	2005
Photo/obs Date	May 2005	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	April	1.89	3.01	1.53	D	1	3	3
2nd Prior Month*	March	1.21	2.55	1.33	N	2	2	4
3rd Prior Month*	February	0.61	1.22	1.33	W	3	1	3
							Sum	10

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions: **prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	2006
Photo/obs Date	June 2006	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	May	1.60	3.34	5.90	W	3	3	9
2nd Prior Month*	April	1.89	3.01	1.97	N	2	2	4
3rd Prior Month*	March	1.21	2.50	1.16	D	1	1	1
							Sum	**14**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions: **prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	2008
Photo/obs Date	June 2008	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	May	1.60	3.34	1.43	D	1	3	3
2nd Prior Month*	April	1.89	3.01	4.61	W	3	2	6
3rd Prior Month*	March	1.21	2.50	2.52	W	3	1	3
							Sum	**12**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	2010
Photo/obs Date	June 2010	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	May	1.60	3.34	1.99	N	2	3	6
2nd Prior Month*	April	1.89	3.01	3.63	W	3	2	6
3rd Prior Month*	March	1.21	2.50	0.31	D	1	1	1
							Sum	**13**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	2011
Photo/obs Date	October 2011	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	September	1.89	3.76	4.54	W	3	3	9
2nd Prior Month*	August	2.49	4.52	1.71	D	1	2	2
3rd Prior Month*	July	2.39	4.09	5.30	W	3	1	3
							Sum	**14**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions:	**prior period has been normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	2015
Photo/obs Date	April 2015	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	March	1.21	2.50	0.90	D	1	3	3
2nd Prior Month*	February	0.50	1.22	0.41	D	1	2	2
3rd Prior Month*	January	0.78	1.45	0.56	D	1	1	1
							Sum	**6**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions: **prior period has been drier than normal**

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	2017
Photo/obs Date	April 2017	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	March	1.21	2.50	2.30	N	2	3	6
2nd Prior Month*	February	0.50	1.22	0.82	N	2	2	4
3rd Prior Month*	January	0.78	1.45	2.43	W	3	1	3
							Sum	13

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions: **prior period has been normal**

Exhibit 4

Hydric Rating by Map Unit—Brown County, Wisconsin
(Ledgeview Dairy - Hydric Soil Ratings)



Map Scale: 1:4,670 if printed on A portrait (8.5" x 11") sheet.

Meters: 0 50 100 200 300

Feet: 0 200 400 800 1200

Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 16N WGS84

MAP LEGEND

Area of Interest (AOI)
- Area of Interest (AOI)

Soils

Soil Rating Polygons
- Hydric (100%)
- Hydric (66 to 99%)
- Hydric (33 to 65%)
- Hydric (1 to 32%)
- Not Hydric (0%)
- Not rated or not available

Soil Rating Lines
- Hydric (100%)
- Hydric (66 to 99%)
- Hydric (33 to 65%)
- Hydric (1 to 32%)
- Not Hydric (0%)
- Not rated or not available

Soil Rating Points
- Hydric (100%)
- Hydric (66 to 99%)
- Hydric (33 to 65%)
- Hydric (1 to 32%)
- Not Hydric (0%)
- Not rated or not available

Water Features
- Streams and Canals

Transportation
- Rails
- Interstate Highways
- US Routes
- Major Roads
- Local Roads

Background
- Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Brown County, Wisconsin
Survey Area Data: Version 10, Sep 27, 2016

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 9, 2011—Aug 14, 2014

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydric Rating by Map Unit

Hydric Rating by Map Unit— Summary by Map Unit — Brown County, Wisconsin (WI009)				
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
AeA	Allendale fine sandy loam, 0 to 3 percent slopes	2	5.3	7.0%
KhB	Kewaunee silt loam, 2 to 6 percent slopes	3	39.0	51.8%
KhB2	Kewaunee silt loam, 2 to 6 percent slopes, eroded	2	1.6	2.1%
KhC2	Kewaunee silt loam, 6 to 12 percent slopes, eroded	0	2.4	3.2%
MaA	Manawa sandy loam, 1 to 3 percent slopes	0	24.6	32.7%
McA	Manawa silty clay loam, 0 to 3 percent slopes	4	2.0	2.7%
Po	Poygan silty clay loam, 0 to 2 percent slopes, drained	88	0.5	0.6%
Totals for Area of Interest			75.2	100.0%

Description

This rating indicates the percentage of map units that meets the criteria for hydric soils. Map units are composed of one or more map unit components or soil types, each of which is rated as hydric soil or not hydric. Map units that are made up dominantly of hydric soils may have small areas of minor nonhydric components in the higher positions on the landform, and map units that are made up dominantly of nonhydric soils may have small areas of minor hydric components in the lower positions on the landform. Each map unit is rated based on its respective components and the percentage of each component within the map unit.

The thematic map is color coded based on the composition of hydric components. The five color classes are separated as 100 percent hydric components, 66 to 99 percent hydric components, 33 to 65 percent hydric components, 1 to 32 percent hydric components, and less than one percent hydric components.

In Web Soil Survey, the Summary by Map Unit table that is displayed below the map pane contains a column named 'Rating'. In this column the percentage of each map unit that is classified as hydric is displayed.

Hydric soils are defined by the National Technical Committee for Hydric Soils (NTCHS) as soils that formed under conditions of saturation, flooding, or ponding long enough during the growing season to develop anaerobic conditions in the upper part (Federal Register, 1994). Under natural conditions, these soils are either saturated or inundated long enough during the growing season to support the growth and reproduction of hydrophytic vegetation.

The NTCHS definition identifies general soil properties that are associated with wetness. In order to determine whether a specific soil is a hydric soil or nonhydric soil, however, more specific information, such as information about the depth and duration of the water table, is needed. Thus, criteria that identify those estimated soil properties unique to hydric soils have been established (Federal Register, 2002). These criteria are used to identify map unit components that normally are associated with wetlands. The criteria used are selected estimated soil properties that are described in "Soil Taxonomy" (Soil Survey Staff, 1999) and "Keys to Soil Taxonomy" (Soil Survey Staff, 2006) and in the "Soil Survey Manual" (Soil Survey Division Staff, 1993).

If soils are wet enough for a long enough period of time to be considered hydric, they should exhibit certain properties that can be easily observed in the field. These visible properties are indicators of hydric soils. The indicators used to make onsite determinations of hydric soils are specified in "Field Indicators of Hydric Soils in the United States" (Hurt and Vasilas, 2006).

References:

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18.

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service. U.S. Department of Agriculture Handbook 436.

Soil Survey Staff. 2006. Keys to soil taxonomy. 10th edition. U.S. Department of Agriculture, Natural Resources Conservation Service.

Rating Options

Aggregation Method: Percent Present

Component Percent Cutoff: None Specified

Tie-break Rule: Lower

Brown County, Wisconsin

AeA—Allendale fine sandy loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2wpwp
Elevation: 590 to 870 feet
Mean annual precipitation: 29 to 31 inches
Mean annual air temperature: 43 to 46 degrees F
Frost-free period: 135 to 160 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Allendale and similar soils: 93 percent
Minor components: 7 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Allendale

Setting

Landform: Flats
Landform position (three-dimensional): Talf
Down-slope shape: Concave
Across-slope shape: Linear
Parent material: Sandy lacustrine deposits over clayey lacustrine deposits

Typical profile

Ap - 0 to 11 inches: fine sandy loam
E - 11 to 15 inches: fine sand
Bhs - 15 to 32 inches: fine sand
E' - 32 to 35 inches: fine sand
Bt - 35 to 39 inches: sandy loam
2Bt - 39 to 44 inches: silty clay
2C - 44 to 79 inches: silty clay

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: 37 to 41 inches to abrupt textural change
Natural drainage class: Somewhat poorly drained
Runoff class: Negligible
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 4 to 24 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 30 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Low (about 4.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3w
Hydrologic Soil Group: C/D
Hydric soil rating: No

Minor Components

Allendale

Percent of map unit: 5 percent
Landform: Flats
Landform position (three-dimensional): Talf
Down-slope shape: Concave
Across-slope shape: Linear
Hydric soil rating: No

Wauseon

Percent of map unit: 2 percent
Landform: Flats
Landform position (three-dimensional): Rise
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Data Source Information

Soil Survey Area: Brown County, Wisconsin
Survey Area Data: Version 10, Sep 27, 2016

Brown County, Wisconsin

KhB—Kewaunee silt loam, 2 to 6 percent slopes

Map Unit Setting

National map unit symbol: 2t040
Elevation: 580 to 1,210 feet
Mean annual precipitation: 27 to 35 inches
Mean annual air temperature: 43 to 46 degrees F
Frost-free period: 130 to 194 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Kewaunee and similar soils: 94 percent
Minor components: 6 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Kewaunee

Setting

Landform: Ground moraines
Landform position (two-dimensional): Backslope, summit
Landform position (three-dimensional): Crest
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Thin loess over calcareous clayey till

Typical profile

Ap - 0 to 10 inches: silt loam
Bt - 10 to 13 inches: silty clay loam
2Bt - 13 to 29 inches: clay
2Cd - 29 to 79 inches: silty clay loam

Properties and qualities

Slope: 2 to 6 percent
Depth to restrictive feature: 26 to 40 inches to densic material
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 60 to 67 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 30 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: C
Hydric soil rating: No

Minor Components

Poygan, drained
Percent of map unit: 3 percent
Landform: Till plains
Landform position (two-dimensional): Toeslope
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Manawa
Percent of map unit: 3 percent
Landform: Drainageways
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope
Down-slope shape: Linear
Across-slope shape: Concave
Hydric soil rating: No

Data Source Information

Soil Survey Area: Brown County, Wisconsin
Survey Area Data: Version 10, Sep 27, 2016

Brown County, Wisconsin

MaA—Manawa sandy loam, 1 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2tjxl
Elevation: 560 to 950 feet
Mean annual precipitation: 29 to 31 inches
Mean annual air temperature: 43 to 46 degrees F
Frost-free period: 140 to 160 days
Farmland classification: Prime farmland if drained

Map Unit Composition

Manawa and similar soils: 90 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Manawa

Setting

Landform: Drainageways
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope
Down-slope shape: Linear
Across-slope shape: Concave
Parent material: Loamy glaciofluvial deposits over clayey till

Typical profile

Ap - 0 to 8 inches: sandy loam
2Bt - 8 to 30 inches: silty clay
2Cd - 30 to 79 inches: silty clay

Properties and qualities

Slope: 1 to 3 percent
Depth to restrictive feature: 20 to 40 inches to densic material
Natural drainage class: Somewhat poorly drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 0 to 12 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 35 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Low (about 4.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2w
Hydrologic Soil Group: D
Hydric soil rating: No

Minor Components

Allendale

Percent of map unit: 5 percent
Landform: Drainageways
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope
Down-slope shape: Linear
Across-slope shape: Concave
Hydric soil rating: No

Kewaunee

Percent of map unit: 5 percent
Landform: Moraines
Landform position (two-dimensional): Summit, backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Linear
Hydric soil rating: No

Data Source Information

Soil Survey Area: Brown County, Wisconsin
Survey Area Data: Version 10, Sep 27, 2016

Exhibit 5

Soil Analysis Summary Worksheet

Owner: Ledgeview Farm

Project: 2017 Waste Storage Facilty and Runoff Management Systems

Prepared By: Roach

Date Prepared: 2017

Test Pit (Number)	Sample No	P200 Fines (%)	Plasticity Index						
6	3889	96	33						
7	3900	99	30						
8	3901	100	27						
9	3902	98	18						
10	3903	100	24						
11	3904	96	23						
11	3905	100	17						
12	3906	99	17						
12	3907	91	22						
13	3908	98	19						
17	1	78.9	21.6						
19	1	89.3	19.2						
20	1	84.1	23.8						
21	1	80.5	23.1						
23	1	85.5	25.2						
54	2	99.5	29.3						
55	1	82.2	21.8						
57	1	85.3	33.7						
57	1	81.9	27.4						
59	1	82.6	28.9						
62	1	76.5	24.5						
LV CF	1	61.5	11.5						

RVT
Engineering Resources, Testing Solutions

REPORT OF LABORATORY ANALYSIS OF SOIL

1280 Parkview Road
Green Bay, WI 54304
ph 920-347-9040
fax 920-347-9044
www.rvtcorp.com

Project: **LEDGEVIEW FARMS**
DE PERE, WISCONSIN

Copies: Mr. Dave Wetenkamp
Brown County Land & Water Conervation Dept.
e) Wetenkamp_dl@co.brown.wi.us

Client: Mr. Jason Pansier
Ledgeview Farms
e) jasonpansier@gmail.com

Date: June 27, 2017

RVT File No: G17-194

GENERAL:

Scope of Work: Perform percent material passing the #200 sieve, atterberg limits, and visual classification of soils on the submitted samples.

Date of Tests: 6/26/17
Technician: N Flory
Sampled By: Mr. Dave Wetenkamp with BCLWC
Material Source: Native
Sample Description: 3899) LEAN CLAY, brown (CL)
Date Delivered: 6/20/17
3900) LEAN CLAY, brown (CL)
3901) LEAN CLAY, brown (CL)
3902) LEAN CLAY, brown (CL)

RESULTS:

Test Method:

ASTM D2487	Classification of Soils for Engineering Purposes
ASTM D1140	Percent Material Finer than the No 200 Sieve
ASTM D4318	Liquid Limit, Plastic Limit, and Plasticity Index of Soils

Sample Number	3899	3900	3901	3902	Project Specifications
Sample Depth	TP6 (6' – 10')	TP7 (6' – 8')	TP8 (6' – 8')	TP9 (6' – 12')	
USCS Classification	CL	CL	CL	CL	---
% Passing #200 Sieve	96	99	100	98	50 min
Liquid Limit (LL)	47	46	46	38	---
Plastic Limit (PL)	14	16	19	20	---
Plasticity Index (PI)	33	30	27	18	12 min

REMARKS:

The above samples meet project specifications. A portion of the sample will be held for 30 days after the date of this report and then will be discarded unless notified otherwise.

Respectfully Submitted,
River Valley Testing Corp.

RVT
Engineering Resources, Testing Solutions

REPORT OF LABORATORY ANALYSIS OF SOIL

1280 Parkview Road
Green Bay, WI 54304
ph 920-347-9040
fax 920-347-9044
www.rvtcorp.com

Project: **LEDGEVIEW FARMS**
DE PERE, WISCONSIN

Copies: Mr. Dave Wetenkamp
Brown County Land & Water Conervation Dept.
e) Wetenkamp_dl@co.brown.wi.us

Client: Mr. Jason Pansier
Ledgeview Farms
e) jasonpansier@gmail.com

Date: June 27, 2017

RVT File No: G17-194

GENERAL:

Scope of Work: Perform percent material passing the #200 sieve, atterberg limits, and visual classification of soils on the submitted samples.

Date of Tests: 6/26/17
Technician: N Flory
Sampled By: Mr. Dave Wetenkamp with BCLWC
Material Source: Native
Sample Description: 3903) LEAN CLAY, brown (CL)
Date Delivered: 6/20/17
3904) LEAN CLAY, brown (CL)
3905) LEAN CLAY, brown (CL)
3906) LEAN CLAY, brown (CL)

RESULTS:

Test Method:

ASTM D2487	Classification of Soils for Engineering Purposes
ASTM D1140	Percent Material Finer than the No 200 Sieve
ASTM D4318	Liquid Limit, Plastic Limit, and Plasticity Index of Soils

Sample Number	3903	3904	3905	3906	Project Specifications
Sample Depth	TP10 (8' – 12')	TP11 (4' – 12')	TP11 (12' – 15')	TP12 (4' – 12')	
USCS Classification	CL	CL	CL	CL	---
% Passing #200 Sieve	100	96	100	99	50 min
Liquid Limit (LL)	43	37	35	37	---
Plastic Limit (PL)	19	14	18	20	---
Plasticity Index (PI)	24	23	17	17	12 min

REMARKS:

The above samples meet project specifications. A portion of the sample will be held for 30 days after the date of this report and then will be discarded unless notified otherwise.

Respectfully Submitted,
River Valley Testing Corp.

RVT
Engineering Resources, Testing Solutions

REPORT OF LABORATORY ANALYSIS OF SOIL

1280 Parkview Road
Green Bay, WI 54304
ph 920-347-9040
fax 920-347-9044
www.rvtcorp.com

Project: **LEDGEVIEW FARMS**
DE PERE, WISCONSIN

Copies: Mr. Dave Wetenkamp
Brown County Land & Water Conervation Dept.
e) Wetenkamp_dl@co.brown.wi.us

Client: Mr. Jason Pansier
Ledgeview Farms
e) jasonpansier@gmail.com

Date: June 27, 2017

RVT File No: G17-194

GENERAL:

Scope of Work: Perform percent material passing the #200 sieve, atterberg limits, and visual classification of soils on the submitted samples.

Date of Tests: 6/26/17
Technician: N Flory
Sampled By: Mr. Dave Wetenkamp with BCLWC
Material Source: Native
Sample Description: 3907) LEAN CLAY, brown (CL)
Date Delivered: 6/20/17
3908) LEAN CLAY, brown (CL)
3909) LEAN CLAY, brown (CL)
3917) LEAN CLAY, brown (CL)

RESULTS:

Test Method:

ASTM D2487	Classification of Soils for Engineering Purposes
ASTM D1140	Percent Material Finer than the No 200 Sieve
ASTM D4318	Liquid Limit, Plastic Limit, and Plasticity Index of Soils

Sample Number	3907	3908	3909	3917	Project Specifications
Sample Depth	TP12 (13' – 12')	TP13 (4' – 12')	Composite A	Composite A	
USCS Classification	CL	CL	CL	CL	---
% Passing #200 Sieve	91	98	88	88	50 min
Liquid Limit (LL)	36	41	40	41	---
Plastic Limit (PL)	14	22	13	15	---
Plasticity Index (PI)	22	19	27	26	12 min

REMARKS:

The above samples meet project specifications. A portion of the sample will be held for 30 days after the date of this report and then will be discarded unless notified otherwise.

Respectfully Submitted,
River Valley Testing Corp.

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	**Roach & Associates**
Project:	**Ledgeview Dairy**
Location Sampled:	**Test Pit 17**
Sample No:	**TP-17-S1**
Depth of Sample:	
Date Received:	**10/13/17**
Sample Designated For:	**Soil Classification**
Source of Sample:	
Munsell Color Code:	**5YR 4/4**
Date Sampled:	**10/11/17**

LABORATORY DATA:

Date Tested:	October 16-18, 2017
Test Performed By:	TAH

24 Hrs. Turn Around:	NO
Washed Gradation:	YES


Dry Weight of Soil (gms): 506.7

Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"	0.0	0.0	100.0		
1/2"	14.4	2.8	97.2		
3/8"	4.4	0.9	96.3		
#4	1.2	0.2	96.1		
#10	4.8	0.9	95.2		
#40	14.9	2.9	92.3		
#100	41.5	8.2	84.1		
#200	26.3	5.2	78.9		

REVIEWED BY:	Robert A Roese
DATE REVIEWED:	10/26/17

Remarks:

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt - Clay
	3.9%	0.9%	2.9%	13.4%	78.9%

Soil Classification: LEAN CLAY W/SAND, a little gravel, reddish brown (CL)

Location Sampled: Test Pit 17

Sample Number: TP-17-S1

Sample Source:

Elevation or Depth:

Date Sampled: 10/11/17

Sampled Moisture Content (%): 16.4

Report No.: TP17-S1

Atterberg Limits: LL= 40.0 PL= 18.4 PI= 21.6

Munsell Color Code: 5YR 4/4

Date Received: 10/13/17

Coefficients: Cc= Cu=

CQM, INC.

Client: Roach & Associates

Project: Ledgeview Dairy

Page: 2

Prepared by: Bob J. Peeters

Date: 10/24/17

Checked by: Robert R Rowe

Date: 10/26/17

761

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	**Roach & Associates**
Project:	**Ledgeview Dairy**
Location Sampled:	**Test Pit 19**
Sample No:	**TP-19-S1**
Depth of Sample:	
Date Received:	**10/13/17**
Sample Designated For:	**Soil Classification**
Source of Sample:	
Munsell Color Code:	**5YR 4/4**
Date Sampled:	**10/11/17**

LABORATORY DATA:

Date Tested:	October 16-18, 2017
Test Performed By:	TAH

24 Hrs. Turn Around:	NO
Washed Gradation:	YES


Dry Weight of Soil (gms): 445.5

Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"					
1/2"					
3/8"					
#4	0.0	0.0	100.0		
#10	0.7	0.2	99.8		
#40	6.3	1.4	98.4		
#100	24.7	5.5	92.9		
#200	16.1	3.6	89.3		

REVIEWED BY:	Robert A Rowe
DATE REVIEWED:	10/26/17

Remarks:

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt - Clay
		0.2%	1.4%	9.1%	89.3%

Soil Classification: LEAN CLAY, reddish brown (CL)

Location Sampled: Test Pit 19

Sample Number: TP-19-S1

Sample Source:

Elevation or Depth:

Sampled Moisture Content (%): 16.6

Date Sampled: 10/11/17

Report No.: TP19-S1

Atterberg Limits: LL= 35.5 PL= 16.3 PI= 19.2

CQM, INC.

Munsell Color Code: 5YR 4/4

Client: Roach & Associates

Date Received: 10/13/17

Project: Ledgeview Dairy

Page: 2

Coefficients: Cc= Cu=

Prepared by: Bob J. Peeters

Date: 10/26/17

Checked by: Robert R Rouse

Date: 10/26/17

763

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	Roach & Associates
Project:	Ledgeview Dairy
Location Sampled:	Test Pit 20
Sample No:	TP-20-S1
Depth of Sample:	
Date Received:	10/13/17
Sample Designated For:	Soil Classification
Source of Sample:	
Munsell Color Code:	5YR 4/4
Date Sampled:	10/11/17

LABORATORY DATA:

Date Tested:	October 16-18, 2017
Test Performed By:	TAH

24 Hrs. Turn Around:	NO
Washed Gradation:	YES


Dry Weight of Soil (gms): 406.6

Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"					
1/2"	0.0	0.0	100.0		
3/8"	2.0	0.5	99.5		
#4	2.4	0.6	98.9		
#10	3.5	0.9	98.0		
#40	9.9	2.4	95.6		
#100	27.3	6.7	88.9		
#200	19.7	4.8	84.1		

REVIEWED BY:	Robert A Rouse
DATE REVIEWED:	10/26/17

Remarks:

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt-Clay
	1.1%	0.9%	2.4%	11.5%	84.1%

Soil Classification: LEAN CLAY W/SAND, reddish brown (CL)

Location Sampled: Test Pit 20

Sample Number: TP-20-S1

Sample Source:

Elevation or Depth:

Date Sampled: 10/11/17

Sampled Moisture Content (%): 16.6

Report No.: TP20-S1

CQM, INC.

Atterberg Limits:	LL= 39.1	PL= 15.3	PI= 23.8

Munsell Color Code: 5YR 4/4

Date Received: 10/13/17

Coefficients: Cc= Cu=

Client: Roach & Associates

Project: Ledgeview Dairy

Page: 2

Prepared by: Bob J. Peeters

Date: 10/26/17

Checked by: Robert R Rouse

Date: 10/26/17

765

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	Roach & Associates
Project:	Ledgeview Dairy
Location Sampled:	Test Pit 21
Sample No:	TP-21-S1
Depth of Sample:	
Date Received:	10/13/17
Sample Designated For:	Soil Classification
Source of Sample:	
Munsell Color Code:	5YR 4/4
Date Sampled:	10/11/17

LABORATORY DATA:

Date Tested:	October 16-18, 2017
Test Performed By:	TAH

24 Hrs. Turn Around:	NO
Washed Gradation:	YES

Dry Weight of Soil (gms): 470.7


Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"					
1/2"					
3/8"	0.0	0.0	100.0		
#4	3.7	0.8	99.2		
#10	3.2	0.7	98.5		
#40	13.9	3.0	95.5		
#100	41.5	8.8	86.7		
#200	29.0	6.2	80.5		

REVIEWED BY:	Robert A Rowe
DATE REVIEWED:	10/26/17

Remarks:

10/26/2017 TLS G-RA-LV-TP21-S1

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt
	0.8%	0.7%	3.0%	15.0%	80.5%

Soil Classification: LEAN CLAY W/SAND, reddish brown (CL)

Location Sampled: Test Pit 21

Sample Number: TP-21-S1

Sample Source:

Elevation or Depth:

Sampled Moisture Content (%): 15.0

Date Sampled: 10/11/17

Report No.: TP21-S1

Atterberg Limits: LL= 37.2 PL= 14.1 PI= 23.1

CQM, INC.

Munsell Color Code: 5YR 4/4

Client: **Roach & Associates**

Project: **Ledgeview Dairy**

Page: 2

Date Received: 10/13/17

Prepared by: Bob J. Peeters

Date: 10/26/17

Coefficients: Cc= Cu=

Checked by: Robert R. Down

Date: 10/26/17

767

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	**Roach & Associates**
Project:	**Ledgeview Dairy**
Location Sampled:	**Test Pit 23**
Sample No:	**TP-23-S1**
Depth of Sample:	
Date Received:	**10/13/17**
Sample Designated For:	**Soil Classification**
Source of Sample:	
Munsell Color Code:	**5YR 4/4**
Date Sampled:	**10/11/17**

LABORATORY DATA:

Date Tested:	October 16-18, 2017
Test Performed By:	TAH

24 Hrs. Turn Around:	NO
Washed Gradation:	YES


Dry Weight of Soil (gms): 411.0

Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"					
1/2"	0.0	0.0	100.0		
3/8"	3.1	0.8	99.2		
#4	1.3	0.3	98.9		
#10	2.2	0.5	98.4		
#40	8.6	2.1	96.3		
#100	27.2	6.6	89.7		
#200	17.4	4.2	85.5		

REVIEWED BY:	Robert A Rouse
DATE REVIEWED:	10/26/17

Remarks:

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt - Clay
	1.1%	0.5%	2.1%	10.8%	85.5%

Soil Classification: LEAN CLAY, reddish brown (CL)

Location Sampled: Test Pit 23

Sample Number: TP-23-S1

Sample Source:

Elevation or Depth:

Date Sampled: 10/11/17

Sampled Moisture Content (%): 17.8

Report No.: TP23-S1

Atterberg Limits:	LL= 41.3	PL= 16.1	PI= 25.2

Munsell Color Code: 5YR 4/4

Date Received: 10/13/17

Coefficients: Cc= Cu=

CQM, INC.

Client: Roach & Associates

Project: Ledgeview Dairy

Page: 2

Prepared by: Bob J. Peeters

Date: 10/26/17

Checked by: Robert R Rouse

Date: 10/26/17

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	Roach & Associates
Project:	Ledgeview Dairy
Location Sampled:	Test Pit 23
Sample No:	TP-23-S2
Depth of Sample:	
Date Received:	10/13/17
Sample Designated For:	Soil Classification
Source of Sample:	
Munsell Color Code:	5YR 4/4
Date Sampled:	10/11/17

LABORATORY DATA:

Date Tested:	October 16-18, 2017
Test Performed By:	TAH

24 Hrs. Turn Around:	NO
Washed Gradation:	YES


Dry Weight of Soil (gms): 374.8

Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"					
1/2"					
3/8"					
#4					
#10	0.0	0.0	100.0		
#40	0.3	0.1	99.9		
#100	0.8	0.2	99.7		
#200	0.8	0.2	99.5		

REVIEWED BY:	Robert A Rouse
DATE REVIEWED:	10/26/17

Remarks:

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt - Clay
			0.1%	0.4%	99.5%

Soil Classification: LEAN CLAY, reddish brown (CL)

Location Sampled: Test Pit 23

Sample Number: TP-23-S2

Sample Source:

Elevation or Depth:

Date Sampled: 10/11/17

Sampled Moisture Content (%): 22.9

Report No.: TP23-S2

Atterberg Limits:	LL= 46.2	PL= 18.9	PI= 29.3

Munsell Color Code: 5YR 4/4

Date Received: 10/13/17

Coefficients: Cc= Cu=

CQM, INC.

Client: Roach & Associates

Project: Ledgeview Dairy

Page: 2

Prepared by: Bob J. Peeters

Date: 10/26/17

Checked by: Robert R Bouse

Date: 10/26/17

77

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	Roach & Associates
Project:	Ledgeview Dairy
Location Sampled:	Test Pit 54
Sample No:	TP-54 S-1
Depth of Sample:	
Date Received:	10/20/17
Sample Designated For:	Soil Classification
Source of Sample:	
Munsell Color Code:	2.5YR 4/8
Date Sampled:	10/19/17

LABORATORY DATA:

Date Tested:	October 23-25, 2017
Test Performed By:	TAH

24 Hrs. Turn Around:	NO
Washed Gradation:	YES


Dry Weight of Soil (gms): 376.3

Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"					
1/2"	0.0	0.0	100.0		
3/8"	6.4	1.7	98.3		
#4	0.8	0.2	98.1		
#10	2.2	0.6	97.5		
#40	7.9	2.1	95.4		
#100	29.4	7.8	87.6		
#200	20.3	5.4	82.2		

REVIEWED BY:	Robert A Rowe
DATE REVIEWED:	10/26/17

Remarks:

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt - Clay
	1.9%	0.6%	2.1%	13.2%	82.2%

Soil Classification: LEAN CLAY W/SAND, red (CL)

Location Sampled: Test Pit 54

Sample Number: TP-54 S-1

Sample Source:

Elevation or Depth:

Date Sampled: 10/19/17

Sampled Moisture Content (%): 17.2

Report No.: TP54-S1

Atterberg Limits:	LL= 38.7	PL= 16.9	PI= 21.8

Munsell Color Code: 2.5YR 4/8

Date Received: 10/20/17

Coefficients: Cc= Cu=

CQM, INC.

Client: Roach & Associates

Project: Ledgeview Dairy

Page: 2

Prepared by: Bob J. Peeters

Date: 10/26/17

Checked by: Robert R Bruce

Date: 10/26/17

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	Roach & Associates
Project:	Ledgeview Dairy
Location Sampled:	Test Pit 56
Sample No:	TP-56 S-1
Depth of Sample:	
Date Received:	10/20/17
Sample Designated For:	Soil Classification
Source of Sample:	
Munsell Color Code:	2.5YR 4/8
Date Sampled:	10/19/17

LABORATORY DATA:

Date Tested:	October 23-25, 2017
Test Performed By:	TAH

24 Hrs. Turn Around:	NO
Washed Gradation:	YES

Dry Weight of Soil (gms): 388.4


Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"					
1/2"					
3/8"	0.0	0.0	100.0		
#4	0.3	0.1	99.9		
#10	1.5	0.4	99.5		
#40	6.1	1.6	97.9		
#100	28.3	7.3	90.6		
#200	20.7	5.3	85.3		

REVIEWED BY:	Robert R Rowe
DATE REVIEWED:	10/26/17

Remarks:

10/26/2017 TLS G-TP56 S-1

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt - Clay
	0.1%	0.4%	1.6%	12.6%	85.3%

Soil Classification: FAT CLAY, red (CL)

Location Sampled: Test Pit 56

Sample Number: TP-56 S-1

Sample Source:

Elevation or Depth:

Sampled Moisture Content (%): 22.8

Date Sampled: 10/19/17

Report No.: TP56-S1

Atterberg Limits: LL= 51.3 PL= 17.6 PI= 33.7

CQM, INC.

Munsell Color Code: 2.5YR 4/8

Client: Roach & Associates

Date Received: 10/20/17

Project: Ledgeview Dairy

Page: 2

Coefficients: Cc= Cu=

Prepared by: Bob J. Peeters

Date: 10/26/17

Checked by: Robert A Roum

Date: 10/26/17

775

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	Roach & Associates
Project:	Ledgeview Dairy
Location Sampled:	Test Pit 57
Sample No:	TP-57 S-1
Depth of Sample:	
Date Received:	10/20/17
Sample Designated For:	Soil Classification
Source of Sample:	
Munsell Color Code:	5YR 5/6
Date Sampled:	10/19/17

LABORATORY DATA:

Date Tested:	October 23-25, 2017
Test Performed By:	TAH

24 Hrs. Turn Around:	NO
Washed Gradation:	YES


Dry Weight of Soil (gms): 361.7

Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"					
1/2"					
3/8"	0.0	0.0	100.0		
#4	0.2	0.1	99.9		
#10	1.6	0.4	99.5		
#40	7.0	1.9	97.6		
#100	34.3	9.5	88.1		
#200	22.3	6.2	81.9		

REVIEWED BY:	Robert A Bowser
DATE REVIEWED:	10/26/17

Remarks:

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt - Clay
	0.1%	0.4%	1.9%	15.7%	81.9%

Soil Classification: LEAN CLAY W/SAND, yellowish red (CL)

Location Sampled: Test Pit 57

Sample Number: TP-57 S-1

Sample Source:

Atterberg Limits: LL= 45.2 PL= 17.8 PI= 27.4

Munsell Color Code: 5YR 5/6

Date Received: 10/20/17

Coefficients: Cc= Cu=

Elevation or Depth:

Sampled Moisture Content (%): 24.3

Date Sampled: 10/19/17

Report No.: TP57-S1

CQM, INC.

Client: Roach & Associates

Project: Ledgeview Dairy

Page: 2

Prepared by: Bob J. Peeters

Date: 10/26/17

Checked by: Robert L. Rowe

Date: 10/26/17

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	Roach & Associates
Project:	Ledgeview Dairy
Location Sampled:	Test Pit 59
Sample No:	TP-59 S-1
Depth of Sample:	
Date Received:	10/20/17
Sample Designated For:	Soil Classification
Source of Sample:	
Munsell Color Code:	5YR 6/6
Date Sampled:	10/19/17

LABORATORY DATA:

Date Tested:	October 23-25, 2017
Test Performed By:	TAH

24 Hrs. Turn Around:	NO
Washed Gradation:	YES


Dry Weight of Soil (gms): 403.1

Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"					
1/2"					
3/8"	0.0	0.0	100.0		
#4	2.6	0.6	99.4		
#10	3.5	0.9	98.5		
#40	9.2	2.3	96.2		
#100	31.7	7.9	88.3		
#200	23.1	5.7	82.6		

REVIEWED BY:	Robert R Rouse
DATE REVIEWED:	10/26/17

Remarks:

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt - Clay
	0.6%	0.9%	2.3%	13.6%	82.6%

Soil Classification: LEAN CLAY, reddish yellow (CL)

Location Sampled: Test Pit 59

Sample Number: TP-59 S-1

Sample Source:

Elevation or Depth:

Date Sampled: 10/19/17

Sampled Moisture Content (%): 15.9

Report No.: TP59-S1

Atterberg Limits:	LL= 45.2	PL= 16.3	PI= 28.9

Munsell Color Code: 5YR 6/6

Date Received: 10/20/17

Coefficients: Cc= Cu=

CQM, INC.

Client: Roach & Associates

Project: Ledgeview Dairy

Page: 2

Prepared by: Bob J. Peeters

Date: 10/26/17

Checked by: Robert A Pease

Date: 10/26/17

779

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	Roach & Associates
Project:	Ledgeview Dairy
Location Sampled:	Test Pit 62
Sample No:	TP-62 S-1
Depth of Sample:	
Date Received:	10/20/17
Sample Designated For:	Soil Classification
Source of Sample:	
Munsell Color Code:	7.5YR 5/3
Date Sampled:	10/19/17

LABORATORY DATA:

Date Tested:	October 23-25, 2017
Test Performed By:	TAH

24 Hrs. Turn Around:	NO
Washed Gradation:	YES

Dry Weight of Soil (gms): 368.0


Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"	0.0	0.0	100.0		
1/2"	7.9	2.1	97.9		
3/8"	5.7	1.5	96.4		
#4	2.5	0.7	95.7		
#10	4.8	1.3	94.4		
#40	10.0	2.7	91.7		
#100	32.3	8.8	82.9		
#200	23.6	6.4	76.5		

REVIEWED BY:	Robert R Rouse
DATE REVIEWED:	10/26/17

Remarks:

10/26/2017 TLS G-TP62 S-1

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt - Clay
	4.3%	1.3%	2.7%	15.2%	76.5%

Soil Classification: LEAN CLAY W/SAND, a little gravel, brown (CL)

Location Sampled: Test Pit 62		Elevation or Depth:	Date Sampled: 10/19/17
Sample Number: TP-62 S-1		Sampled Moisture Content (%): 19.8	Report No.: TP62-S1
Sample Source:		*CQM, INC.*	
Atterberg Limits: LL= 43.5	PL= 19.1	PI= 24.5	Client: Roach & Associates
Munsell Color Code: 7.5YR 5/3		Project: Ledgeview Dairy	Page: 2
Date Received: 10/20/17		Prepared by: Bob J. Peeters	Date: 10/26/17
Coefficients: Cc=	Cu=	Checked by: Robert A. Rowe	Date: 10/26/17

781

CQM, INC.

SIEVE ANALYSIS OF COARSE TO FINE AGGREGATES (ASTM D1140)

GENERAL DATA:

Client:	**Roach & Associates**
Project:	**Ledgeview Dairy**
Location Sampled:	**Channel Fill**
Sample No:	**LV-CF-1**
Depth of Sample:	
Date Received:	**10/13/17**
Sample Designated For:	**Soil Classification**
Source of Sample:	
Munsell Color Code:	**5YR 4/4**
Date Sampled:	**10/11/17**

LABORATORY DATA:

Date Tested:	October 16-18, 2017
Test Performed By:	TAH
24 Hrs. Turn Around:	NO
Washed Gradation:	YES


Dry Weight of Soil (gms): 429.9

Sieve Size	Weight Retained	% Retained	% Passing	Project Specification % Passing by Weight	Source of Specification
3"					
1 1/2"					
1"					
3/4"					
1/2"	0.0	0.0	100.0		
3/8"	4.6	1.1	98.9		
#4	5.9	1.4	97.5		
#10	9.0	2.1	95.4		
#40	24.2	5.6	89.8		
#100	79.1	18.4	71.4		
#200	42.4	9.9	61.5		

REVIEWED BY:	Robert A. Rowe
DATE REVIEWED:	10/26/17

Remarks:

GRAIN SIZE DISTRIBUTION CURVE



Gravel		Sand			
Coarse	Fine	Coarse	Medium	Fine	Silt-Clay
	2.5%	2.1%	5.6%	28.3%	61.5%

Soil Classification: SANDY LEAN CLAY, reddish brown (CL)

Location Sampled: Channel Fill

Sample Number: LV-CF-1

Sample Source:

Elevation or Depth:

Date Sampled: 10/11/17

Sampled Moisture Content (%): 15.0

Report No.: CF-1

Atterberg Limits: LL= 23.5 PL= 12.0 PI= 11.5

Munsell Color Code: 5YR 4/4

Date Received: 10/13/17

Coefficients: Cc= Cu=

CQM, INC.

Client: Roach & Associates

Project: Ledgeview Dairy

Page: 2

Prepared by: Bob J. Peelers

Date: 10/24/17

Checked by: Robert R Rowe

Date: 10/26/17

783

Exhibit 5

NRCS method - Rainfall Documentation Worksheet Hydrology Tools for Wetland Determination
NRCS Engineering Field Handbook Chapter 19

Date	8.31.17	**Landowner/Project**	Ledgeview Dairy
Weather Station	Green Bay A S Intl AP	**State**	WI
County	Brown	**Growing Season**	2017
Photo/obs Date	9.5.17 Field Observations	**Soil Name**	

shaded cells are locked or calculated

Long-term rainfall statistics (from WETS table or State Climatology Office)

	Month	30% chance <	30% chance >	Precip	Condition Dry, Wet, Normal	Condition Value	Month Weight Value	Product of Previous 2 Columns
1st Prior Month*	August	2.49	4.52	4.05	N	2	3	6
2nd Prior Month*	July	2.39	4.09	4.56	W	3	2	6
3rd Prior Month*	June	2.05	4.16	3.78	N	2	1	2
							Sum	**14**

*compared to photo/observation date

Note: If sum is	
6 - 9	prior period has been drier than normal
10 - 14	prior period has been normal
15 - 18	prior period has been wetter than normal

Condition value:
Dry =1
Normal =2
Wet =3

Conclusions: **prior period has been normal**

Ledgeview Dairy

WETS Table

WETS Station: GREEN BAY A S INTL AP, WI

Requested years: 1971 - 2000

Month	Avg Max Temp	Avg Min Temp	Avg Mean Temp	Avg Precip	30% chance precip less than	30% chance precip more than	Avg number days precip 0. 10 or more	Avg Snowfall
Jan	23.7	7.2	15.4	1.21	0.78	1.45	4	14.0
Feb	28.5	11.9	20.2	1.01	0.61	1.22	3	8.6
Mar	39.4	22.4	30.9	2.06	1.21	2.50	5	9.2
Apr	54.0	33.7	43.8	2.56	1.89	3.01	6	2.9
May	67.6	44.5	56.1	2.75	1.60	3.34	6	0.2
Jun	76.6	54.0	65.3	3.43	2.05	4.16	6	0.0
Jul	81.0	59.0	70.0	3.44	2.39	4.09	6	0.0
Aug	78.3	57.3	67.8	3.77	2.49	4.52	7	0.0
Sep	69.8	48.6	59.2	3.11	1.89	3.76	6	0.0
Oct	57.5	38.0	47.7	2.17	1.36	2.62	5	0.2
Nov	41.9	26.4	34.2	2.27	1.35	2.76	5	5.4
Dec	28.6	13.7	21.1	1.41	0.90	1.70	4	12.6
Annual:					26.46	31.52		
Average	53.9	34.7	44.3	-	-	-	-	-
Total	-	-	-	29.18			64	53.1

GROWING SEASON DATES

Years with missing data:	24 deg = 0	28 deg = 0	32 deg = 0
Years with no occurrence:	24 deg = 0	28 deg = 0	32 deg = 0
Data years used:	24 deg = 30	28 deg = 30	32 deg = 30
Probability	24 F or higher	28 F or higher	32 F or higher
50 percent *	4/10 to 10/29: 202 days	4/24 to 10/13: 172 days	5/6 to 10/4: 151 days
70 percent *	4/6 to 11/2: 210 days	4/20 to 10/18: 181 days	5/3 to 10/8: 158 days

* Percent chance of the growing season occurring between the Beginning and Ending dates

STATS TABLE - total precipitation (inches)

Yr	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Annl
1886									3.58	5.40	2.88	1.36	13.22
1887	2.51	3.99	1.01	1.76	0.90	2.38	4.31	2.93	3.29	3.90	1.57	4.01	32.56
1888	2.38	2.11	5.69	2.90	3.79	1.14	3.13	2.34	5.36	1.45	2.12	3.01	35.42
1889	3.75	3.30	0.74	1.09	4.75	3.06	2.55	1.36	4.68	0.26	3.62	3.38	32.54
1890	3.29	3.16	1.87	2.75	3.08	5.18	4.50	4.61	1.77	3.55	1.72	0.75	36.23
1891	2.30	1.96	3.33	1.93	0.12	1.73	1.80	4.02	0.60	2.24	2.32	3.68	26.03
1892	1.80	1.84	0.86	1.67	5.10	5.84	2.76	3.87	3.40	1.62	2.93	1.33	33.02
1893	1.73	1.82	2.63	3.80	3.54	2.48	4.12	1.52	3.51	1.37	2.27	4.20	32.99
1894	1.98	1.40	2.39	2.75	6.93	5.32	1.86	1.34	3.	4.	2.	1.	35.

									27	33	86	46	89	
1895	1.96	0.74	0.41	1.21	4.28	2.37	1.44	3.71	1. 24	0. 40	1. 50	1. 78	21. 04	
1896	0.98	0.26	1.19	5.48	3.60	3.35	2.45	2.96	5. 21	3. 13	3 60	0. 88	33. 09	
1897	1.69	1.69	2.52	4.09	2.40	7.56	3.92	1.79	3. 21	2. 50	1. 56	1. 20	34. 13	
1898	1.20	1.09	2.96	2.57	3.13	3.60	3.16	2.65	3. 07	4. 04	0. 87	0. 74	29. 08	
1899	0.98	0.96	2.93	3.15	1.95	4.85	4.99	0.36	2. 16	1. 35	0. 54	1. 54	25. 76	
1900	0.77	1.67	1.07	2.88	2.10	2.30	5.70	4.28	5. 09	4. 29	1. 98	0. 63	32. 76	
1901	0.90	0.49	2.75	0.51	2.71	3.80	4.11	1.58	4. 15	3. 60	0. 80	1. 05	26. 46	
1902	0.45	1.39	2.65	1.49	4.20	4.71	4.10	1.23	2. 63	1. 56	1. 42	1. 78	27. 61	
1903	1.03	1.35	3.75	2.79	3.32	1.03	3.54	5.38	3. 39	1. 72	1. 25	0. 34	28. 89	
1904	0.45	1.43	3.05	2.07	6.53	1.55	3.83	1.41	4. 44	3. 19	0. 34	2. 34	30. 63	
1905	1.43	1.17	2.77	2.04	3.75	3.28	5.26	4.41	2. 42	2. 71	1. 70	0. 97	31. 91	
1906	2.58	0.87	3.39	2.05	2.84	4.38	3.59	7.93	2. 20	2. 68	3. 76	1. 63	37. 90	
1907	2.17	0.08	2.04	3.39	2.64	3.22	1.75	4.17	3. 80	0. 82	1. 29	2. 05	27. 32	
1908	0.90	1.75	2.38	2.84	3.64	1.74	2.44	1.19	1. 45	0. 57	1. 61	1. 40	21. 91	
1909	0.66	1.49	1.63	4.00	4.28	4.16	1.04	1.24	2. 68	0. 95	2. 55	2. 10	26. 78	
1910	1.02	1.07	0.19	4.90	1.87	0.94	2.02	6.08	6. 24	1. 41	2. 65	0. 75	29. 14	
1911	0.87	1.96	0.75	1.43	5.72	2.23	1.59	1.56	5. 16	4. 68	2. 54	2. 20	30. 69	
1912	0.59	0.61	0.88	2.06	7.24	1.03	7.46	3.92	4. 70	2 19	1. 15	1. 49	33. 32	
1913	1.17	1.67	3.03	2.37	5.49	2.70	4.91	1.01	3. 56	2. 55	1. 91	0. 46	30. 83	
1914	0.91	0.83	0.87	2.75	4.42	8.68	4.95	5.26	4. 86	1. 73	1. 78	0. 99	38. 03	
1915	1.29	2.44	0.86	1.33	3.32	2.54	2.62	3.66	5. 10	0. 85	2. 87	0. 86	27. 74	
1916	2.39	1.09	1.53	2.39	3.94	6.73	2.42	1.39	3. 27	4. 73	3. 27	1. 04	34. 19	
1917	1.96	0.50	2.45	2.32	1.12	4.92	1.52	2.07	1. 95	2. 38	0. 70	0. 38	22. 27	
1918	2.22	1.21	1.98	2.44	9.70	2.59	1.52	2.05	1. 71	2. 18	2. 16	1. 81	31. 57	
1919	0.67	1.51	1.26	3.20	4.53	0.83	5.39	1.60	2. 97	2. 37	2. 26	0. 36	26. 95	
1920	0.98	0.47	4.12	2.11	1.43	6.00	3.49	1.80	0. 91	2 27	3. 48	1. 70	28. 76	
1921	0.50	0.73	2.08	4.13	1.04	0.71	2.48	4.97	2. 62	2. 04	1. 14	3. 65	26. 09	
1922	0.88	4.54	1.74	4.62	1.79	4.88	5.88	4.10	2. 74	0. 47	2. 25	0. 59	34. 48	
1923	1.73	0.91	2.93	2.33	1.50	2.53	3.31	3.65	1. 48	1. 98	0. 60	1. 19	24. 14	
1924	0.78	1.55	2.49	4.64	4.72	2.74	2.96	4.82	3. 04	0. 08	2. 01	0. 80	30. 63	
1925	0.27	1.79	0.59	1.84	1.21	5.96	3.04	2.61	3. 38	2. 05	0. 48	1. 07	24. 29	
1926	0.53	1.59	1.28	1.95	3.83	4.50	2.13	3.36	4. 87	2. 76	2. 78	1. 67	31. 25	
1927	1.05	0.34	2.17	1.81	3.40	1.96	2.99	0.59	4. 82	1. 97	2. 32	1. 89	25. 31	
1928	0.36	1.89	2.40	2.29	1.17	5.50	3.46	3.82	2.	3.	1.	0.	29.	

									34	71	18	92	04	
1929	2.54	1.58	2.11	6.47	1.70	3.75	2.04	1.70	2. 38	1. 86	0. 53	0. 91	27. 57	
1930	0.90	1.67	0.72	1.01	1.94	3.02	2.15	0.59	1. 64	1. 70	0. 64	0. 33	16. 31	
1931	0.64	0.64	1.71	0.63	1.08	3.17	3.31	2.34	5. 84	3. 76	3. 61	1. 10	27. 83	
1932	2.15	1.23	0.95	1.28	2.79	1.76	2.21	1.26	1. 21	1. 58	1. 01	2. 04	19. 47	
1933	1.43	0.75	2.26	2.54	2.40	5.07	3.43	1.10	2. 01	3. 59	0. 70	1. 19	26. 47	
1934	0.92	0.44	2.37	1.91	2.01	4.47	2.34	3.85	1. 91	1. 60	6. 19	0. 98	28. 99	
1935	1.44	1.28	0.70	1.70	1.46	4.69	1.70	4.31	3. 29	1. 21	1. 53	0. 90	24. 21	
1936	1.42	1.45	1.18	1.26	1.73	1.24	1.02	3.28	2. 23	2. 04	0 59	1. 03	18. 47	
1937	2.43	2.33	0.44	3.42	1.12	1.39	2.16	2.62	2. 84	2. 30	1. 91	0. 85	23. 80	
1938	2.06	3.16	2.32	1.68	2.32	2.03	1.84	3.75	6. 31	0. 75	1. 50	1. 33	29. 05	
1939	1.83	1.33	0.77	1.94	2.39	4.56	0.79	2.27	3. 27	2. 83	0. 45	0. 68	23. 11	
1940	0.99	0.57	0.66	2.91	3.38	6.11	1.90	6.12	2. 36	1. 87	3. 25	1. 38	31. 50	
1941	1.70	0.67	1.34	2.31	3.77	1.47	1.14	4.08	4. 08	3. 39	1. 02	1. 45	26. 42	
1942	0.78	0.79	2.80	2.08	7.10	4.83	1.88	1.11	3. 43	1. 24	1. 81	2. 25	30. 10	
1943	1.86	0.60	1.85	1.53	4.44	4.04	2.54	3.21	0. 81	0. 83	2. 41	0. 03	24. 15	
1944	0.99	1.02	1.82	1.81	1.20	5.27	2.25	4.80	3. 99	0. 85	2. 43	0. 65	27. 08	
1945	0.52	2.23	1.12	4.12	4.38	4.92	1.18	3.96	2. 57	0. 99	3. 91	1. 37	31. 27	
1946	1.89	0.77	2.47	0.67	4.33	4.17	0.70	1.88	2. 81	1. 49	2. 60	1. 75	25. 53	
1947	1.08	0.51	1.46	3.25	4.43	3.10	3.26	4.66	2. 97	2. 08	1. 84	1. 29	29. 93	
1948	0.55	1.93	1.91	2.93	0.91	2.67	3.04	0.96	1. 40	0. 71	4. 99	1. 43	23. 43	
1949	1.84	1.07	3.75	2.69	0.71	3.58	4.89	2.45	1. 25	1. 05	1. 50	1. 17	25. 95	
1950	2.64	1.45	2.49	3.39	1.50	3.11	6.50	2.72	2. 20	1. 14	1. 12	1. 84	30. 10	
1951	0.87	1.72	2.66	4.79	0.89	2.30	4.12	6.50	2. 93	4. 82	1. 66	1. 09	33. 35	
1952	2.06	0.70	1.98	1.57	2.92	2.36	3.82	2.06	0. 82	T	2. 24	1. 45	21. 98	
1953	1.10	3.56	1.94	5.52	1.41	1.90	3.15	2.05	2. 02	0. 22	0. 39	1. 59	24. 85	
1954	0.43	0.98	1.11	4.45	3.22	4.38	2.94	1.61	5. 78	5. 00	0. 89	0. 42	31. 21	
1955	0.78	1.37	1.40	2.40	2.39	3.25	4.78	0.90	0. 76	3. 58	1. 04	0. 89	23. 54	
1956	0.56	0.60	1.86	1.45	4.66	3.90	5.85	3.09	1. 65	0. 65	2. 13	0. 87	27. 27	
1957	0.35	0.43	0.46	2.93	5.28	2.48	3.18	3.46	2. 15	1. 35	3. 52	1. 59	27. 18	
1958	0.42	0.16	0.50	2.56	1.27	1.82	2.07	2.68	3. 20	2. 25	1. 34	0. 16	18. 43	
1959	1.04	1.98	1.87	2.84	3.86	1.26	4.21	2.71	5. 17	3. 27	1. 47	2. 85	32. 53	
1960	1.04	0.48	1.21	3.13	7.75	3.07	1.87	3.52	3. 09	2. 32	0. 69	0. 10	28. 27	
1961	0.31	0.93	2.12	1.67	1.42	4.31	4.91	2.84	5. 02	3. 34	2. 60	1. 27	30. 74	
1962	1.27	2.02	1.13	2.55	2.86	4.35	2.70	2.88	3.	1.	0.	1.	27.	

	Jan	Feb	Mar	April	May	June	July	Aug	Sept	Oct	Nov	Dec	Annual
									87	94	84	03	44
1963	0.68	0.59	2.58	0.98	1.54	2.67	2.77	2.07	3.00	0.73	1.63	0.73	19.97
1964	1.14	0.26	1.76	2.55	4.14	1.05	4.55	2.72	6.74	0.44	2.07	0.70	28.12
1965	0.93	0.85	2.38	3.62	3.95	1.89	1.96	3.38	7.80	1.32	2.19	2.31	32.58
1966	1.18	2.25	2.46	1.38	1.28	1.09	4.19	2.65	1.21	0.72	1.58	1.65	21.64
1967	2.52	0.84	1.13	2.77	2.45	8.47	1.96	2.43	0.46	4.71	1.66	1.17	30.57
1968	0.94	0.45	0.97	4.84	3.10	6.97	2.00	2.66	3.31	1.01	1.01	2.69	29.95
1969	2.60	0.04	1.04	2.86	2.56	7.62	2.51	1.19	2.03	3.46	0.43	1.43	27.87
1970	0.73	0.23	1.07	1.61	5.76	1.11	4.02	1.25	6.11	2.98	2.68	1.24	28.79
1971	1.60	2.03	2.04	1.05	1.67	1.87	3.44	2.99	3.36	2.01	3.21	3.15	28.42
1972	0.65	0.96	2.19	1.45	0.82	2.25	1.85	5.86	5.76	1.84	1.15	2.49	27.27
1973	1.86	0.72	2.43	3.23	8.21	3.20	1.93	2.57	2.91	3.96	1.45	2.41	34,88
1974	1.71	1.17	1.07	2.62	4.46	4.91	4.25	1.61	1.05	1.72	2.09	1.67	28.33
1975	1.52	1.48	3.44	2.35	2.79	5.27	1.78	9.04	3.18	0.36	3.42	0.84	35.47
1976	1.72	1.33	3.65	2.44	2.42	0.31	2.96	1.15	0.28	0.82	0.16	0.61	17.85
1977	0.67	1.38	4.68	3.33	2.47	2.27	2.13	2.37	2.44	1.36	2.70	2.31	28.11
1978	1.33	0.35	0.31	3.44	3.38	2.72	6.03	4.36	4.82	2.33	2.93	1.30	33.30
1979	1.78	1.17	4.49	1.93	3.01	2.21	3.55	5.97	0.76	2.72	2.49	1.28	31,36
1980	1.92	0.35	1.00	2.73	1.77	3.82	1.87	7.31	3.42	1.79	1.25	1.35	28.58
1981	0.12	2.76	0.42	4.22	0.66	2.63	0.83	3.37	3.25	3.44	1.08	1.10	23.78
1982	1.34	0.14	1.95	2.66	2.74	2.67	5.10	2.91	1.43	1.20	4.51	2.50	29 15
1983	0.72	1.46	1.52	1.39	4.80	1.82	3.76	5.27	3.59	2.24	2.63	1.18	30.38
1984	0.59	1.59	1.64	3.33	1.65	5.60	3.17	3.78	5.66	4.92	2.55	1.72	36.20
1985	0.86	2.55	2.70	2.24	2.58	2.21	4.03	8.03	3.65	2.72	4.96	1.83	38.36
1986	0.60	0.83	2.48	2.26	1.15	4.06	4.95	3.85	7.51	1.89	1.27	0.48	31.33
1987	0.47	0.39	1.53	2.33	2.58	1.83	2.18	3.41	1.57	1.76	3.07	2.04	23.16
1988	1.79	0.73	1.10	2.53	0.06	0.67	2.34	3.47	4.11	1.96	4.43	0.84	24.03
1989	0.41	0.38	2.88	0.49	4.22	1.56	2.27	1.06	0.58	4.76	1.25	0.55	20.40
1990	0.64	0.58	3.25	1.28	3.99	10.29	2.93	2.51	5.13	2.34	1.61	2.10	36.65
1991	0.57	0.37	2.87	2.77	2.42	1.08	4.16	2.11	2.55	3.50	2.72	1.42	26.54
1992	0.72	0.55	2.48	3.01	1.54	1.61	4.18	2.10	5.61	0.92	5.32	2.27	30.31
1993	1.42	0.34	0.76	3.99	4.28	6.82	6.83	2.30	2.78	2.29	1.56	0.44	33.81
1994	1.47	1.11	1.14	5.91	1.69	2.84	7.00	3.69	2.19	0.98	1.43	0.34	29.79
1995	0.65	0.39	1.92	2.22	2.88	1.80	1.15	7.31	2.76	4.80	3.32	1.25	30.45
1996	1.77	0.76	1.16	3.85	1.40	5.57	2.49	1.40	1.	2.	0.	1.	25.

	Jan	Feb	mar	April	May	June	July	Aug	Sept	oct	Nov	Dec	Annual
										93	80	89	42
1997	1.81	1.40	1.92	1.67	2.60	5.61	2.11	5.73	2.76	0.93	0.30	0.61	27.35
1998	2.21	0.80	3.66	1.85	2.21	6.17	1.86	2.93	3.54	1.56	1.67	0.30	28.76
1999	2.37	1.10	0.15	2.11	3.77	3.98	5.67	1.32	1.24	0.67	1.57	0.83	24.78
2000	0.87	1.04	0.98	2.15	4.41	5.33	6.27	3.38	3.94	0.46	1.26	1.16	31.24
2001	1.19	1.26	0.42	3.66	4.74	5.17	0.85	3.42	2.35	1.71	1.70	1.23	27.70
2002	0.60	1.50	2.08	3.02	2.81	4.69	2.16	4.01	2.67	3.26	0.44	0.73	27.97
2003	0.58	0.56	2.32	2.36	3.17	3.71	4.26	4.15	3.32	1.05	3.83	1.68	30.99
2004	1.24	1.62	3.58	1.56	8.31	4.87	1.78	2.00	0.47	3.70	1.80	2.26	33.19
2005	1.60	1.33	1.33	1.53	2.52	3.44	1.46	4.23	3.08	1.69	3.07	1.04	26.22
2006	1.64	1.34	1.16	1.97	5.90	2.83	3.14	2.11	3.33	3.14	1.23	2.88	30.67
2007	0.63	1.39	2.74	1.72	2.39	3.71	2.41	2.72	3.16	3.62	0.11	2.54	27.14
2008	3.65	2.30	2.52	4.61	1.43	4.77	4.71	0.59	1.89	1.59	1.49	3.72	33.27
2009	0.66	1.55	2.59	2.62	3.01	2.53	1.33	3.33	1.22	5.16	1.38	2.28	27.66
2010	0.67	1.05	0.31	3.63	1.99	6.73	9.51	4.42	4.48	2.12	1.33	1.91	38.15
2011	1.23	1.34	3.08	6.24	2.81	5.12	5.30	1.71	4.54	1.66	3.42	1.40	37.85
2012	1.40	1.12	2.21	2.39	3.43	1.71	6.01	3.66	1.09	4.92	1.05	2.54	31.53
2013	2.36	2.30	2.01	3.38	3.72	3.82	3.35	3.05	2.89	2.95	3.44	1.89	35.16
2014	1.33	1.46	0.91	4.01	2.95	4.05	1.21	4.80	4.69	2.51	2.52	1.68	32.12
2015	0.56	0.41	0.90	1.63	3.44	3.24	1.80	4.22	5.85	2.64	2.49	5.71	32.89
2016	1.33	1.15	4.05	1.29	3.36	4.44	3.22	2.78	4.29	2.66	2.29	2.25	33.11
2017	2.43	0.82	2.30	4.48	2.97	3.78	4.56	4.05	MO.51				25.90

Notes: Data missing in any month have an "M" flag. A "T" indicates a trace of precipitation.

Data missing for all days in a month or year is blank.

Creation date: 2016-07-22

Ledgeview Dairy

Climatological Data for GREEN BAY A S INTL AP, WI - August 2017

Date	Max Temperature	Min Temperature	Avg Temperature	GDD Base 40	GDD Base 50	Precipitation	Snowfall	Snow Depth
2017-08-01	84	62	73.0	33	23	0.00	0.0	0
2017-08-02	76	63	69.5	30	20	0.03	0.0	0
2017-08-03	68	57	62.5	23	13	0.61	0.0	0
2017-08-04	68	53	60.5	21	11	0.59	0.0	0
2017-08-05	76	52	64.0	24	14	0.09	0.0	0
2017-08-06	80	53	66.5	27	17	0.02	0.0	0
2017-08-07	77	56	66.5	27	17	0.00	0.0	0
2017-08-08	82	56	69.0	29	19	0.00	0.0	0
2017-08-09	80	55	67.5	28	18	0.00	0.0	0
2017-08-10	78	59	68.5	29	19	0.54	0.0	0
2017-08-11	72	56	64.0	24	14	T	0.0	0
2017-08-12	78	55	66.5	27	17	0.00	0.0	0
2017-08-13	79	52	65.5	26	16	0.00	0.0	0
2017-08-14	76	58	67.0	27	17	0.25	0.0	0
2017-08-15	78	59	68.5	29	19	T	0.0	0
2017-08-16	77	60	68.5	29	19	0.35	0.0	0
2017-08-17	79	65	72.0	32	22	0.22	0.0	0
2017-08-18	73	62	67.5	28	18	0.00	0.0	0
2017-08-19	81	58	69.5	30	20	0.00	0.0	0
2017-08-20	79	56	67.5	28	18	0.00	0.0	0
2017-08-21	80	62	71.0	31	21	0.01	0.0	0
2017-08-22	75	57	66.0	26	16	0.00	0.0	0
2017-08-23	74	52	63.0	23	13	0.00	0.0	0
2017-08-24	68	47	57.5	18	8	0.00	0.0	0
2017-08-25	72	43	57.5	18	8	0.00	0.0	0
2017-08-26	68	47	57.5	18	8	0.11	0.0	0
2017-08-27	68	59	63.5	24	14	0.15	0.0	0
2017-08-28	72	55	63.5	24	14	0.17	0.0	0
2017-08-29	75	54	64.5	25	15	0.00	0.0	0
2017-08-30	81	53	67.0	27	17	0.91	0.0	0
2017-08-31	65	51	58.0	18	8	0.00	0.0	0
Average|Sum	75.5	55.7	65.6	803	493	4.05	0.0	0.0

Exhibit 6

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 101A

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: KhB - Kewaunee silt loam, 2-6% slopes NWI classification: Upland

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes X No _____

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes X No _____	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes _____ No X	
Wetland Hydrology Present?	Yes X No _____	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- X Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes X	No _____	Depth (inches): surface to 2"

Wetland Hydrology Present? Yes X No _____

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants.

Sampling Point: 101A

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Herb Stratum (Plot size: 5')			
1. Phragmites australis	80	Y	FacW
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
.5 = 40 .2 = 16	80 = Total Cover		
Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across All Strata: 1 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 100 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes X No ____

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 101A

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-15"	5YR 4/4	100					SiSaL	
15-24"	5YR 4/4	90	5YR 4/6	10	C	M	Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes _____ No X

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 102A

Investigator(s): Rachel Ecker Section, Township, Range: Section 28,T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): concave Slope (%): 0%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: MaA - Manawa sandy loam, 1-3% slopes NWI classification: Wetland Indicator Soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation _____, Soil _____, or Hydrology X significantly disturbed? Are "Normal Circumstances" present? Yes _____ No X

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes X	No _____	**Is the Sampled Area within a Wetland?** Yes X No _____
Hydric Soil Present?	Yes X	No _____	If yes, optional Wetland Site ID: _____
Wetland Hydrology Present?	Yes X	No _____	

Remarks: (Explain alternative procedures here or in a separate report.)

Hydrology is disturbed. Roof Runoff from the machine shed and freestall barn flow to this location.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- X FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes X	No _____	Depth (inches): _____

Wetland Hydrology Present? Yes X No _____

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants. Sampling Point: 102A

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Herb Stratum (Plot size: 5')			
1. Phragmites australis	85	Y	FacW
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
.5 = 42.5 .2 = 17	85 = Total Cover		

Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across All Strata: 1 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 100 (A/B)

Prevalence Index worksheet:

Total % Cover of:		Multiply by:	
OBL species		x 1 =	
FACW species		x 2 =	
FAC species		x 3 =	
FACU species		x 4 =	
UPL species		x 5 =	
Column Totals:	(A)		(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes X No ____

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 102A

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-8"	10YR 3/2	90	7.5YR 4/6	10	C	M	SiL	
8-24"	5YR 4/4	95	5YR 4/6	5	C	M	Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. [2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes X No ___

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 103A

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: KhB - Kewaunee silt loam, 2-6% slopes NWI classification: Upland

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation X, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes _____ No X

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes _____	No X	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes X	No _____	
Wetland Hydrology Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

Sample location is within a cropfield.

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants.

Sampling Point: 103A

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Herb Stratum (Plot size: 5')			
1. No vegetation within cropfield			
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
	= Total Cover		
Woody Vine Stratum (Plot size:)			
1.			
2.			
3.			
4.			
	= Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 0 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes ____ No X

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 103A

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-15"	10YR 3/1	80	7.5YR 4/6	20	C	M	SiL	
15-24"	5YR 4/4	95	5YR 4/6	5	C	M	Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. [2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes X No ___

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jaso Pansier - Ledgeview Dairy State: WI Sampling Point: 104A

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.49" Datum: Google Earth

Soil Map Unit Name: KhB - Kewaunee silt loam, 2-6% slopes NWI classification: Upland

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes X No _____

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes X	No _____	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes _____	No X	
Wetland Hydrology Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- X FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants. Sampling Point: 104A

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	.0 = Total Cover		

Herb Stratum (Plot size: 5')			
1. Phragmites australis	90	Y	FacW
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
.5 = 45 .2 = 18	90 = Total Cover		

Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across All Strata: 1 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 100 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

X 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes X No ___

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 104A

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-18"	10YR 3/2	100					SiL	
18-24"	5YR 4/4	100					Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes _____ No X

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 105A

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: KhB - Kewaunee silt loam, 2-6% slopes NWI classification: Upland

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes X No _____

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes X	No _____	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes X	No _____	
Wetland Hydrology Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- X FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants. Sampling Point: 105A

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Herb Stratum (Plot size: 5')			
1. Phragmites australis	80	Y	FacW
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
.5 = 40 .2 = 16	80 = Total Cover		
Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across All Strata: 1 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 100 (A/B)

Prevalence Index worksheet:

Total % Cover of:		Multiply by:	
OBL species		x 1 =	
FACW species		x 2 =	
FAC species		x 3 =	
FACU species		x 4 =	
UPL species		x 5 =	
Column Totals:	(A)		(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

- ___ 1 - Rapid Test for Hydrophytic Vegetation
- X 2 - Dominance Test is >50%
- ___ 3 - Prevalence Index is ≤3.0[1]
- ___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)
- ___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes X No ___

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 105A

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-16"	10YR 3/2	90	7.5YR 4/6	10	C	M	SiL	
16-24"	5YR 4/4	100						

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes X No ___

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 201B

Investigator(s): Rachel Ecker Section, Township, Range: Section 8, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.49" Datum: Google Earth

Soil Map Unit Name: MaA - Manawa sandy loam, 1-3% slopes NWI classification: Wetland Indicator Soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation X, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes _____ No X

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes _____	No X	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes _____	No X	
Wetland Hydrology Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants.

Sampling Point: 201B

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Herb Stratum (Plot size: 5')			
1. No vegetation	0		
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
	0 = Total Cover		

Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 0 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes ____ No X

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 201B

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-8"	10YR 3/2	100					SiL	
8-16"	5YR 4/4	90	5YR 4/6	10	C	M	SaSiCl	
16-24"	5YR 4/4	100					Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. [2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes ____ No X

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 202B

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: MaA - Manawa sandy loam, 1-3% slopes NWI classification: Wetland Indicator Soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation X, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes _____ No X

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes _____	No X	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes X	No _____	
Wetland Hydrology Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants. Sampling Point: 202B

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Herb Stratum (Plot size: 5')			
1. No vegetation	0		
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
	0 = Total Cover		
Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 0 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes ____ No X

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 202B

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-17"	10YR 3/1	90	10YR 4/6	10	C	M	SiL	
17-24"	10YR 4/1	85	10YR 4/6	15	D	M	Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes X No ___

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 203B

Investigator(s): Rachel Ecker Section, Township, Range: Section 28,T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: MaA - Manawa sandy loam, 1-3% slopes NWI classification: Wetland Indicator Soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation X, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes _____ No X

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes _____	No X	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____
Wetland Hydrology Present?	Yes _____	No X	

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants.

Sampling Point: 203B

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Herb Stratum (Plot size: 5')			
1. No vegetation present			
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
	0 = Total Cover		

Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 0 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0 (A/B)

Prevalence Index worksheet:

Total % Cover of:		Multiply by:	
OBL species		x 1 =	
FACW species		x 2 =	
FAC species		x 3 =	
FACU species		x 4 =	
UPL species		x 5 =	
Column Totals:	(A)		(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.


Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes ____ No X

Remarks: (Include photo numbers here or on a separate sheet.)

Exhibit 6

Ledgeview Heifer Farm-Wetlands Map



Legend

- Wetland Class Points
  - Dammed pond
  - Excavated pond
  - Filled excavated pond
  - Filled/drained wetland
  - Wetland too small to delineate
- Filled Points
- Wetland Class Areas
  - Wetland
  - Upland
- Filled Areas
- NRCS Wetspots
- Wetland Indicators
- Municipality
- State Boundaries
- County Boundaries
- Major Roads
  - Interstate Highway
  - State Highway
  - US Highway
- County and Local Roads
  - County HWY
  - Local Road
- Railroads
- Tribal Lands
- Rivers and Streams
- Intermittent Streams
- Lakes and Open water
- Index to EN_Image_Basemap_Leaf_Off

Notes

0.1 0 0.03 0.1 Miles

NAD_1983_HARN_Wisconsin_TM

1: 1,980

DISCLAIMER: The information shown on these maps has been obtained from various sources, and are of varying age, reliability and resolution. These maps are not intended to be used for navigation, nor are these maps an authoritative source of information about legal land ownership or public access. No warranty, expressed or implied, is made regarding accuracy, applicability for a particular use, completeness, or legality of the information depicted on this map. For more information, see the DNR Legal Notices web page: http://dnr.wi.gov/legal/

817

State of Wisconsin
DEPARTMENT OF NATURAL RESOURCES
Oshkosh Service Center
625 E County Road Y, Suite 700
Oshkosh, WI 54901-9731

Scott Walker, Governor
Daniel L. Meyer, Secretary
Telephone 608-266-2621
Toll Free 1-888-936-7463
TTY Access via relay - 711

November 7, 2017

WIC-NE-2017-5-03382

Ledgeview Dairy
Jason Pansier
3875 Dickinson Road
DePere, WI 54115

RE: Wetland Delineation Report for 7.0 acres located in the NW1/4 of the SW1/4 of Section 28, Township 23 North, Range 21 East, Town of Ledgeview, Brown County

Dear Mr. Pansier:

We have received and reviewed the wetland delineation report prepared for the above mentioned site by Roach & Associates, LLC. This letter will serve as confirmation that the wetland boundaries as shown on the revised wetland delineation map received October 20, 2017 are acceptable. This finding is based upon an October 11, 2017 field visit. Any filling or grading within these areas will require DNR approvals. Our wetland confirmation is valid for five years unless altered site conditions warrant a new wetland delineation be conducted. Be sure to send a copy of the report, as well as any approved revisions, to the U.S. Army Corps of Engineers.

In order to comply with Chapter 23.321, State Statutes, please supply the department with a polygon shapefile of the wetland boundaries delineated within the project area. Please do not include data such as parcel boundaries, project limits, wetland graphic representation symbols, etc. If internal upland polygons are found within a wetland polygon, then please label as UPLAND. The shapefile should utilize a State Plane Projection, and be overlain onto recent aerial photography. If a different projection system is used, please indicate what system the data are projected to. In the correspondence sent with the shapefile, please supply a brief description of each wetland's plant community (eg: wet meadow, floodplain forest, etc.). Please send these data to Calvin Lawrence (608-266-0756, or calvin.lawrence@wisconsin.gov).

There may be a navigable stream identified on the property. DNR Chapter 30 permits will be needed if earthwork (filling, dredging, etc.) or structures (culverts, bridges, erosion control, etc.) are proposed in or adjacent to the waterway.

If you are planning development on the property, you are required to avoid take of endangered and threatened species, or obtain an incidental take authorization or permit, to comply with the state's Endangered Species Law. To insure compliance with the law, you should submit an endangered resources review form (Form 1700-047), available at http://dnr.wi.gov/topic/ERReview/Review.html. The Endangered Resources Program will provide a review response letter identifying any endangered and threatened species and any conditions that must be followed to address potential incidental take.

In addition to contacting WDNR, be sure to contact your local zoning office and U.S. Army Corps of Engineers to determine if any local or federal permits may be required for your project.

If you have any questions, please contact me at (920) 424-3058 or email Allison.Willman@wisconsin.gov.

Sincerely,

Allison Willman
Wetland Identification Specialist

cc: Jessica Kempke, Project Manager, U.S. Army Corps of Engineers
Bill Bosiacki, Zoning Administrator, Brown County
Rachel Ecker, Roach & Associates, LLC.
Crystal Von Holdt, DNR Water Management Specialist



ROJECT NO.	X	REVISIONS BY	DATE	DESCRIPTION OF REVISION	REVISIONS BY	DATE	DESCRIPTION OF REVISION	LEDGEVIEW DAIRY SATILITE FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 125'	WETLAND MAP	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 1 OF 820
ATE:	09/19/2017	*	*	*	*	*	*					
RAWN BY:	MHP											
HECKED BY:	RE											

Exhibit 7

WELL CONSTRUCTOR'S REPORT TO WISCONSIN STATE BOARD OF HEALTH

See Instructions on Reverse Side

1. County Brown — Town ☒ / Village ☐ De Pere / City ☐ — Check one and give name

2. Location NE, S.W.¼ of the N.W. ¼ of Sec. 33, T. 24N, R. 21E (T23N) — Name of street and number of premise or Section, Town and Range numbers

3. Owner ☐ or Agent ☐ Pleasant View School District No. 3 — Name of individual, partnership or firm

4. Mail Address Route 3, Green Bay, Wis. — Complete address required

5. From well to nearest: Building 48 ft; sewer Privy 50 ft; drain ____ ft; septic tank ____ ft; dry well or filter bed ____ ft; abandoned well 95 ft. to be filled in by school board

6. Well is intended to supply water for: School

RECEIVED JAN 5 BUREAU SAN. ENG.

7. DRILLHOLE:

Dia. (in.)	From (ft.)	To (ft.)	Dia. (in.)	From (ft.)	To (ft.)
8	0	78½			
6	78½	174			

8. CASING AND LINER PIPE OR CURBING:

Dia. (in.)	Kind	From (ft.)	To (ft.)
6	Standard Weight Steel Pipe -- welded joints	0	78½

9. GROUT:

Kind	From (ft.)	To (ft.)
Puddled Clay	0	4
Neat Cement	4	78½

10. FORMATIONS:

Kind	From (ft.)	To (ft.)
Hard Pan	0	3
Shell Rock	3	25
Shale	25	76
Limestone	76	87
Shale & Limestone	87	140
Limestone	140	174

Construction of the well was completed on: December 15, 19 49

The well is terminated 6 inches ☒ above, below ☐ the permanent ground surface.

Was the well disinfected upon completion? Yes X No ____

Was the well sealed watertight upon completion? Yes X No ____

11. MISCELLANEOUS DATA:

Yield test: 4 Hrs. at 5 GPM.

Depth from surface to water-level: 67 ft.

Water-level when pumping: 78 ft.

Water sample was sent to the state laboratory at: Green Bay, Wis. (City) on Dec. 15 19 49

Signature Gleason Well Drilling Co. — Registered Well Driller

1169 Pine Street, Green Bay, Wis. — Complete Mail Address

Please do not write in space below

Rec'd ____ No. ____

Ans'd ____

Interpretation ____

	10 ml	10 ml	10 ml	10 ml	10 ml
Gas—24 hrs.					
48 hrs.					
Confirm					
B. Coli					

Examiner ____

WELL CONSTRUCTOR'S REPORT
FORM 3300-15

DEC 11 1975

NOTE
WHITE COPY – DIVISION'S COPY
GREEN COPY – DRILLER'S COPY
YELLOW COPY – OWNER'S COPY

DEC 30 1975 BN-1051-U
STATE OF WISCONSIN
DEPARTMENT OF NATURAL RESOURCES
Box 450
Madison, Wisconsin 53701

COUNTY: Brown
CHECK ONE: ☒ Town ☐ Village ☐ City
NAME: De Pere

2. LOCATION – ¼ Section: SE, SW, NE | Section: 32 | Township: 23N. | Range: 21E.
OR – Grid or street no: in 1992 = 3701 | Street name: Hwy G, Dickinson
AND – If available subdivision name, lot & block no:

3. OWNER AT TIME OF DRILLING: Dennis Panzier
ADDRESS: R1 Ledgeview Rd.
POST OFFICE: De Pere, Wis.

4. Distance in feet from well to nearest: (Record answer in appropriate block)

BUILDING	SANITARY SEWER C. I.	SANITARY SEWER TILE	FLOOR DRAIN C. I.	FLOOR DRAIN TILE	FOUNDATION DRAIN SEWER CONNECTED	FOUNDATION DRAIN INDEPENDENT	WASTE WATER DRAIN C. I.	WASTE WATER DRAIN TILE
12	–	–	–	–	–	11	–	–

CLEAR WATER DRAIN C. I.	CLEAR WATER DRAIN TILE	SEPTIC TANK	PRIVY	SEEPAGE PIT	ABSORPTION FIELD	BARN	SILO	ABANDONED WELL	SINK HOLE
–	–	40	–	–	75	–	–	–	–

OTHER POLLUTION SOURCES (Give description such as dump, quarry, drainage well, stream, pond, lake, etc.): –

5. Well is intended to supply water for: Home

6. DRILLHOLE

Dia. (in.)	From (ft.)	To (ft.)	Dia. (in.)	From (ft.)	To (ft.)
10	Surface	61	6	61	130

7. CASING, LINER, CURBING, AND SCREEN

Dia. (in.)	Kind and Weight	From (ft.)	To (ft.)
6	New Stanton Pipe	Surface	61
	Reamed & Drifted		
	Welded joint		
	wt 18.97 per ft.		
API	5A Jones-Laughlin		

8. GROUT OR OTHER SEALING MATERIAL

Kind	From (ft.)	To (ft.)
Drilling mud	Surface	61

9. FORMATIONS

Kind	From (ft.)	To (ft.)
clay	Surface	50
boulders & clay	50	61
shalerock	61	130

10. TYPE OF DRILLING MACHINE USED
☐ Cable Tool ☐ Direct Rotary ☐ Reverse Rotary
☐ Rotary – air w/drilling mud ☒ Rotary – hammer with drilling mud & air ☐ Jetting with ☐ Air ☐ Water

Well construction completed on: October 14 1975
Well is terminated: 8 inches ☒ above ☐ below final grade
Well disinfected upon completion: ☒ Yes ☐ No
Well sealed watertight upon completion: ☒ Yes ☐ No

11. MISCELLANEOUS DATA
Yield test: 4 Hrs. at 2 GPM
Depth from surface to normal water level: 23 ft.
Depth to water level when pumping: 23 ft.

Water sample sent to: Madison laboratory on: December 2, 1975

Your opinion concerning other pollution hazards, information concerning difficulties encountered, and data relating to nearby wells, screens, seals, type of casing joints, method of finishing the well, amount of cement used in grouting, blasting, sub-surface pumprooms, access pits, etc., should be given on reverse side.

SIGNATURE: Leonard Willems Registered Well Driller
COMPLETE MAIL ADDRESS: R.1 Brandley Wis.

Please do not write in space below

GAS – 24 HRS	GAS – 48 HRS	CONFIRMED	REMARKS

CC
RE BN 3934

Exhibit 8

Exhibit 8-1
Waste Storage Facility Summary-Annual Storage Period
Leachate, Runoff Generation and Storage Capacity
Ledgeview Farm

Source	Volume (ft^3)	Volume (gallons)	Comments
Waste Generation			
Manure and Wastewater-Dairy	2,051,871	15,347,995	Exhibit 8-2
Manure and Wastewater-Steers	382,284	2,859,484	Exhibit 8-3
FSA Leachate-Heifer Farm	16,786	125,556	Exhibit 8-4
FSA Runoff-Heifer Farm	285,046	2,132,140	Exhibit 8-6
FSA Leachate-HQ*	1,683	12,589	Exhibit 8-9
FSA Runoff-HQ*	13,029	97,453	Exhibit 8-11
Y1 Heifer Farm Lot Runoff	84,856	634,723	Exhibit 8-8
Y1 HQ Farm Lot Runoff*	14,822	110,869	Exhibit 8-13
Sub-total	**2,850,376**	**21,320,809**	
Net Precipitation**			
WSF 1	111,303	832,546	
WSF 2	351,609	2,630,038	
Sub-total	**462,912**	**3,462,583**	
Total Waste Gnerated	**3,313,288**	**24,783,392**	
Waste Stored Above the MOL			
FSA-Heifer Farm 25 yr-24 hr	41,427	309,873	Exhibit 8-5
FSA-HQ 25 yr-24hr*	3,199	23,927	Exhibit 8-10
Y1 Hefier Farm Lot Runoff 25 yr-24 hr	13,263	99,204	Exhibit 8-7
Y1 HQ Farm Lot 25 yr-24 hr*	2,070	15,483	Exhibit 8-12
Total Waste Above MOL	59,958	448,487	
Waste Storage Facilities***			
WSF 1	669,334	5,006,618	
WSF 2	1,971,800	14,749,062	
Total Storage Volume	**2,641,134**	**19,755,680**	
Storage Capacity Evaluation			
Total Storage Volume	2,641,134	19,755,680	
Average Annual Storage Period	291 days		

*Allowance for future runoff collection system
**Net precipitation; 1.7 ft/year x WSF surface area
***MOL volume, determined by CADD

Exhibit 8-1A
MOL Calculations
Ledgeview Farm

Summary Table - WSF			
Elevation	ft3	Gallons	Description
720.00	2,296,306	17,176,366	Lowest Berm
719.00	2,096,174	15,679,378	MOS
	(71,256)	(532,992)	WSF
	(40,208)	(300,756)	FSA
	(12,910)	(96,568)	Y1: Heifer Yard
718.36	1,971,800	14,749,062	MOL

	WSF			
Elevation	**Area ft^2 (from AutoCAD)**	**Volume ft^3**	**Volume gallons**	
706.60	141,524	-	-	
707.00	143,233	56,951	425,997	
708.00	147,535	202,336	1,513,470	
709.00	151,880	352,043	2,633,283	
710.00	156,266	506,116	3,785,750	
711.00	160,695	664,597	4,971,185	
712.00	165,166	827,527	6,189,905	
713.00	169,679	994,950	7,442,224	
714.00	174,234	1,166,906	8,728,458	
715.00	178,831	1,343,439	10,048,922	
716.00	183,471	1,524,590	11,403,930	
717.00	188,152	1,710,401	12,793,799	
718.00	192,876	1,900,915	14,218,843	
718.36		1,971,800	14,749,062	MOL
719.00	197,642	2,096,174	15,679,378	
720.00	202,623	2,296,306	17,176,366	Bank Top

25yr-24hr Storm Event	Rain Depth inches	Area sq.ft.	Volume cu.ft.	Volume gallons
WSF (RCN 100)	4.22	202,623	71,256	532,992
FSA (RCN 98)	3.98	121,230	40,208	300,756
Y1: Heifer Yard (RCN 98)	3.98	38,925	12,910	96,568
Total			124,374	930,316

Ex 8-2 **WASTE STORAGE FACILITY DESIGN - 313 STANDARD** Ver. March 2015

CLIENT: Ledgeview Farm COUNTY: BROWN DATE: 12/5/17

DSN BY: JMR CHK BY: _____ DATE: _____

COMMENTS Waste Generation - Dairy Projected

ANIMAL TYPE> 1 (1 = DAIRY, 2 = BEEF, 3 = VEAL, 4 = SWINE(finishing), 5 = SWINE(farrowing), 6 = POULTRY, 0 = OTHER)

For Dairy: Rolling Herd Average 25,000 lbs/cow/yr Is it a stanchion barn? n (Y or N)

MANURE AND WASTEWATER

LIVESTOCK		AVG. WT.	DAILY OUTPUT, CU FT			DAYS OF	VOLUME	ANIMAL
KIND	NUMBER	PER HEAD	MANURE	BEDDING	TOTAL	STORAGE	REQUIRED	UNITS
Cows Milk	1125	1,400	2.53	0.3	3183.8	365	1,162,069	1,575
Cows Dry	230	1,400	2.00	0.3	529.0	365	193,085	322
Heifers	450	1,000	1.60	0.3	855.0	365	312,075	450
Heifers	270	600	0.96	0.3	340.2	365	124,173	162
Calves	270	350	0.56	0.4	245.7	365	89,681	95
		WASTEWATER:	3500	GAL/DAY	467.9	CU FT/DAY		2,604 TOT. A.U.
			TOTAL DAILY VOLUME:		5621.6	CU FT / DAY		

	15,347,995	GALLONS
Total Manure and Wastewater	**2,051,871**	**CU FT**
Expected % solids in waste (Includes runoff and precip.)	9.9	%

Ex 8-3 **WASTE STORAGE FACILITY DESIGN - 313 STANDARD** Ver. March 2015

CLIENT: Ledgeview Farm COUNTY: BROWN DATE: 12/5/17

DSN BY: JMR CHK BY: _____ DATE: _____

COMMENTS Waste Generation Steers - Projected

ANIMAL TYPE > 2 (1 = DAIRY, 2 = BEEF, 3 = VEAL, 4 = SWINE(finishing), 5 = SWINE(farrowing), 6 = POULTRY, 0 = OTHER)

n

MANURE AND WASTEWATER

LIVESTOCK KIND	LIVESTOCK NUMBER	AVG. WT. PER HEAD	DAILY OUTPUT, CU FT MANURE	DAILY OUTPUT, CU FT BEDDING	DAILY OUTPUT, CU FT TOTAL	DAYS OF STORAGE	VOLUME REQUIRED	ANIMAL UNITS
Beef	550	350	0.35	0.3	357.5	365	130,488	193
Beef	525	750	1.00	0.3	682.5	365	249,113	394

WASTEWATER: 55 GAL/DAY 7.4 CU FT/DAY 586 TOT. A.U.

TOTAL DAILY VOLUME: 1047.4 CU FT / DAY

	2,859,483	GALLONS
Total Manure and Wastewater	**382,284**	**CU FT**
Expected % solids in waste (Includes runoff and precip.)	10.1	%

Exhibit 8-4

Leachate and First Flush Volume Calculation Worksheet
Ledgeview Farm - Heifer Farm

Prepared By: Roach
Date: 2017

Input Data	Dimensions		
	Length	Width	Area ft²
Existing FSA	varies	varies	93,253
			-
			-
			-

Total Area With Apron	93,253	ft²
Total Area With Apron	2.1	Acres
Total Feed Storage Area Less Apron	93,253	ft²

Volume of Feed Stored In the Facility

Silage Height	12	ft
Silage Density (defalt)	60	lbs/ft³
Silage Volume	33,571	tons

Calculated Annual Leachate Volume

Silage Stored	33,571	tons
Leachate Volume Generated per Ton	0.5	ft³/ton
Annual Leachate Generated	16,786	ft³
Annual Leachate Generated	125,556	gal
Leachate Generated Per Day (30 day period)	4,185	gal/day
Leachate Generated Per Day (30 day period)	560	ft³/day

Calculated First Flush Runoff Generation

Total Feed Storage Area Less Apron	93,253	ft²
First Flush Runoff Depth Collected per Rain Event	0	in
First Flush Volume Collected per Rain Event	-	ft³/event
First Flush Volume Collected per Rain Event	-	gal
Number of Rain Events (annual)		
Total Annual First Flush Volume Generated	-	ft³
Total Annual First Flush Volume Generated	-	gal

Total Annual Leachate & First Flush Volume	125,556	gal
Total Daily Leachate & First Flush Volume	4,185	gal
Volume to Use For Calculation	7,500	gal

Leachate Collection Tank Volume		
Leachate Volume	560	ft³/day
1st Flush Volume	-	ft³/event
Total Design Volume	**560**	**ft³**

20.72

Summary		
Annual Leachate Generated	16,786	ft³
Annual First Flush Runoff Generated	-	ft³
Total Annual Volume to Store	16,786	ft³
Total Annual Volume to Store	125,556	gal

Cell to Enter Data Into	
Cell has Formula and is Calculated	

Exhibit 8-5

TR 55 PEAK RUNOFF CALCULATION (GRAPHICAL METHOD)

ver 5-2008

CLIENT:	Ledgeview	COUNTY:	BROWN	DATE:	11/27/2017
DSN BY:	Roach	CHK BY:		DATE:	
COMMENTS:	Feed Storage Area-Heifer Farm				

Drainage Area	2.78	Acres
Runoff Curve Number	98.00	

Time of Concentration 0.07 Hours

Frequency	yr	2	5	10	25	50	100
Rainfall, P (24 hour)	in	2.5	3.2	3.7	4.3	4.8	5.1
Initial Abstraction, Ia	in	0	0	0	0	0	0
Ia/P ratio		0.000	0.000	0.000	0.000	0.000	0.000
Unit Peak Discharge, qu	cfs/ac/in	1.720	1.720	1.720	1.720	1.720	1.720
Runoff	in	2.31	3.01	3.51	4.11	4.60	4.90
	ac-ft	0.54	0.70	0.81	0.95	1.07	1.14
Peak Discharge, qp	cfs	11.1	14.4	16.8	19.6	22.0	23.4

Total Runoff One Inch Rain	=	0.19 ac-ft	8,381 cubic feet	62,690 gallons
Total Runoff 25 year Event	=	0.95 ac-ft	41,427 cubic feet	309,873 gallons
Peak Flow	=	19.63 cfs	8,810 gpm	

Exhibit 8-6
Monthly Feed Storage Area Runoff-Heifer Farm
Ledgeview Farm

	FSA Runoff Volume*		Runoff Volume to WSF	
Month	**(ft^3)**	**(gallons)**	**(ft^3)**	**(gallons)**
Jan**	7,129	53,325	0	0
Feb**	6,463	48,343	0	0
March***	14,992	112,140	7,496	56,070
April	26,343	197,046	26,343	197,046
May	33,722	252,241	33,722	252,241
June	43,560	325,829	43,560	325,829
July	41,109	307,495	41,109	307,495
Aug	42,379	316,995	42,379	316,995
Sept	38,740	289,775	38,740	289,775
Oct	27,062	202,424	27,062	202,424
Nov	19,428	145,321	19,428	145,321
Dec***	10,413	77,889	5,207	38,945
	311,340	2,328,823	285,046	2,132,140
Winter Months (Nov-April)			58,474	437,382

*121,097 sq ft FSA, RCN 98

***Fifty percent snow removal

25 year, 24 hour rainfall runoff	41,427	cu ft	309,873	gallons

Exhibit 8-7

TR 55 PEAK RUNOFF CALCULATION (GRAPHICAL METHOD)

ver 5-2008

CLIENT:	Ledgeview	COUNTY:	BROWN	DATE:	5/24/2011
DSN BY:	Roach	CHK BY:		DATE:	
COMMENTS:	Y1 Animal Lot - Heifer Farm				

Drainage Area	0.89	Acres
Runoff Curve Number	98.00	
Time of Concentration	0.07	Hours

Frequency	yr		2	5	10	25	50	100
Rainfall, P (24 hour)	in	1.00	2.5	3.2	3.7	4.3	4.8	5.1
Initial Abstraction, Ia	in	0.00	0	0	0	0	0	0
Ia/P ratio		0.00	0.000	0.000	0.000	0.000	0.000	0.000
Unit Peak Discharge, qu	cfs/ac/in	1.72	1.720	1.720	1.720	1.720	1.720	1.720
Runoff	in	0.83	2.31	3.01	3.51	4.11	4.60	4.90
	ac-ft	0.06	0.17	0.22	0.26	0.30	0.34	0.36
Peak Discharge, qp	cfs	1.27	3.5	4.6	5.4	6.3	7.0	7.5

Total Runoff One Inch Rain	=	0.06 ac-ft	2,683 cubic feet	20,070 gallons
Total Runoff 25 year Event	=	0.30 ac-ft	13,263 cubic feet	99,204 gallons
Peak Flow	=	6.28 cfs	2,821 gpm	

Exhibit 8-8
Monthly Animal Lot Runoff-Heifer Farm
Ledgeview Dairy

	Y1 Runoff Volume*		Runoff Volume to WSF	
Month	**(ft^3)**	**(gallons)**	**(ft^3)**	**(gallons)**
Jan**	2,291	17,137	0	0
Feb**	2,077	15,536	0	0
March***	4,819	36,046	2,410	18,023
April	8,468	63,341	8,468	63,341
May	10,840	81,083	10,840	81,083
June	14,002	104,735	14,002	104,735
July	13,214	98,841	13,214	98,841
Aug	13,622	101,893	13,622	101,893
Sept	8,699	65,069	8,699	65,069
Oct	6,245	46,713	6,245	46,713
Nov	3,347	25,036	3,347	25,036
Dec***	8,019	59,982	4,010	29,991
	95,643	715,410	84,856	634,723
Winter Months (Nov-April)			18,234	136,390

*38,925 sq ft FSA, RCN 98
**Snow removal
***Fifty percent snow removal

25 year, 24 hour rainfall runoff	13,263	cu ft	99,204	gallons

Exhibit 8-9

Leachate and First Flush Volume Calculation Worksheet
Ledgeview - Headquarters Farm

Prepared By: Roach
Date: 2017

Input Data	Dimensions* Length	Width	Area ft^2
FSA Home Farm	170	55	9,350
			-
			-
			-
			-

Total Area With Apron	9,350	ft^2
Total Area With Apron	0.2	Acres
Total Feed Storage Area Less Apron	9,350	ft^2

Volume of Feed Stored In the Facility

Silage Height	12	ft
Silage Density (defalt)	60	lbs/ft^3
Silage Volume	3,366	tons

Calculated Annual Leachate Volume

Silage Stored	3,366	tons
Leachate Volume Generated per Ton	0.5	ft^3/ton
Annual Leachate Generated	1,683	ft^3
Annual Leachate Generated	12,589	gal
Leachate Generated Per Day (30 day period)	420	gal/day
Leachate Generated Per Day (30 day period)	56	ft^3/day

Calculated First Flush Runoff Generation

Total Feed Storage Area Less Apron	9,350	ft^2
First Flush Runoff Depth Collected per Rain Event	0	in
First Flush Volume Collected per Rain Event	-	ft^3/event
First Flush Volume Collected per Rain Event	-	gal
Number of Rain Events (annual)		
Total Annual First Flush Volume Generated	-	ft^3
Total Annual First Flush Volume Generated	-	gal

Total Annual Leachate & First Flush Volume	12,589	gal
Total Daily Leachate & First Flush Volume	420	gal
Volume to Use For Calculation		gal

Leachate Collection Tank Volume		
Leachate Volume	56	ft^3/day
1st Flush Volume	-	ft^3/event
Total Design Volume	**56**	**ft^3**

2.08

Summary		
Annual Leachate Generated	1,683	ft^3
Annual First Flush Runoff Generated	-	ft^3
Total Annual Volume to Store	1,683	ft^3
Total Annual Volume to Store	12,589	gal

Cell to Enter Data Into	
Cell has Formula and is Calculated	

Exhibit 8-10

TR 55 PEAK RUNOFF CALCULATION (GRAPHICAL METHOD)

ver 5-2008

CLIENT:	Ledgeview Farm	COUNTY:	BROWN	DATE:	5/24/2011
DSN BY:	Roach	CHK BY:		DATE:	
COMMENTS:	Feed Storage Area Headquartrs Farm				

Drainage Area	0.21	Acres
Runoff Curve Number	98.00	
Time of Concentration	0.07	Hours

Frequency	yr	2	5	10	25	50	100
Rainfall, P (24 hour)	in	2.5	3.2	3.7	4.3	4.8	5.1
Initial Abstraction, Ia	in	0	0	0	0	0	0
Ia/P ratio		0.000	0.000	0.000	0.000	0.000	0.000
Unit Peak Discharge, qu	cfs/ac/in	1.720	1.720	1.720	1.720	1.720	1.720
Runoff	in	2.31	3.01	3.51	4.11	4.60	4.90
	ac-ft	0.04	0.05	0.06	0.07	0.08	0.09
Peak Discharge, qp	cfs	0.9	1.1	1.3	1.5	1.7	1.8

Total Runoff One Inch Rain	=	0.01 ac-ft	647 cubic feet	4,841 gallons
Total Runoff 25 year Event	=	0.07 ac-ft	3,199 cubic feet	23,927 gallons
Peak Flow	=		1.5 cfs	680 gpm

Exhibit 8-11
Monthly Feed Storage Area Runoff-Headquarters Farm
Ledgeview Dairy

	FSA Runoff Volume*		Runoff Volume to WSF	
Month	**(ft^3)**	**(gallons)**	**(ft^3)**	**(gallons)**
Jan**	834	6,238	0	0
Feb**	779	5,827	0	0
March***	1,340	10,023	670	5,012
April	1,792	13,404	1,792	13,404
May	1,434	10,726	1,434	10,726
June	1,348	10,083	1,348	10,083
July	982	7,345	982	7,345
Aug	1,286	9,619	1,286	9,619
Sept	1,683	12,589	1,683	12,589
Oct	1,675	12,529	1,675	12,529
Nov	1,621	12,125	1,621	12,125
Dec***	1,075	8,041	538	4,021
	15,849	118,551	13,029	97,453
Winter Months (Nov-April)			4,621	34,561

*9,350 sq ft FSA, RCN 98
**Snow removal
***Fifty percent snow removal

25 year, 24 hour rainfall runoff	2,070	cu ft	15,481	gallons

Exhibit 8-12

TR 55 PEAK RUNOFF CALCULATION (GRAPHICAL METHOD)

ver 5-2008

CLIENT:	Ledgeview Farm	COUNTY:	BROWN	DATE:	5/24/2011
DSN BY:	Roach	CHK BY:		DATE:	
COMMENTS:	Animal Lot Headquarters Farm				

Drainage Area	0.14	Acres
Runoff Curve Number	98.00	

Time of Concentration 0.07 Hours

Frequency	yr		2	5	10	25	50	100
Rainfall, P (24 hour)	in	1.00	2.5	3.2	3.7	4.3	4.8	5.1
Initial Abstraction, Ia	in	0.00	0	0	0	0	0	0
Ia/P ratio		0.00	0.000	0.000	0.000	0.000	0.000	0.000
Unit Peak Discharge, qu	cfs/ac/in	1.72	1.720	1.720	1.720	1.720	1.720	1.720
Runoff	in	0.83	2.31	3.01	3.51	4.11	4.60	4.90
	ac-ft	0.01	0.03	0.03	0.04	0.05	0.05	0.06
Peak Discharge, qp	cfs	0.20	0.6	0.7	0.8	1.0	1.1	1.2

Total Runoff One Inch Rain	=	0.01 ac-ft	419 cubic feet	3,132 gallons
Total Runoff 25 year Event	=	0.05 ac-ft	2,070 cubic feet	15,483 gallons
Peak Flow	=		1.0 cfs	440 gpm

Exhibit 8-13
Monthly Animal Lot Runoff-Headquarters Farm
Ledgeview Dairy

	FSA Runoff Volume*		Runoff Volume to WSF	
Month	**(ft^3)**	**(gallons)**	**(ft^3)**	**(gallons)**
Jan**	356	2,663	0	0
Feb**	323	2,416	0	0
March***	749	5,603	375	2,801
April	1,316	9,844	1,316	9,844
May	1,685	12,604	1,685	12,604
June	2,176	16,276	2,176	16,276
July	2,054	15,364	2,054	15,364
Aug	2,117	15,835	2,117	15,835
Sept	1,935	14,474	1,935	14,474
Oct	971	7,263	971	7,263
Nov	520	3,890	520	3,890
Dec***	3,347	25,036	1,674	12,518
	17,549	131,267	14,822	110,869
Winter Months (Nov-April)			3,884	29,052

*6,050 sq ft FSA, RCN 98
**Snow removal
***Fifty percent snow removal

25 year, 24 hour rainfall runoff	2,070	cu ft	15,481	gallons

Exhibit 9

Exhibit 9-1
Piping System
Detention Basin - WSF 2
Ledgeview Farm

Piping System

Pipe Diameter	**12**		**18**		**20**	
Item	**Ke**	**Le**	**Ke**	**Le**	**Ke**	**Le**
entrance			0.5			
bends (6)			3			
Manholes (2)			1			
1064				1064		
exit			1			
Total	0	0	5.5	1,064	0	0

Piping System
Detention Basin - WSF 2

Diameter (in)	Flow (gpm)	Velocity (ft/sec)	s* (ft/ft)	HK e (ft)	HL e (ft)	Static Min (ft)	Static Max (ft)	Discharge Pressure (ft)	Discharge Pressure (psi)	TDH Min (ft)	TDH Max (ft)	TDH Min (psi)	TDH Max (psi)
12	3000	8.5	0.0225	0.0	0.0								
18	3000	3.8	0.0031	1.2	3.3								
20	3000	3.1	0.0019	0.0	0.0								
				1.2	3.3	-9.6	-9.6	0	0	-5	-5	-2	-2
12	4000	11.4	0.0384	0.0	0.0								
18	4000	5.0	0.0053	2.2	5.7								
20	4000	4.1	0.0032	0.0	0.0								
				2.2	5.7	-9.6	-9.6	0	0	-2	-2	-1	-1
12	4450	12.6	0.0467	0.0	0.0								
18	4450	5.6	0.0065	2.7	6.9								
20	4450	4.5	0.0039	0.0	0.0								
				2.7	6.9	-9.6	-9.6	0	0	0	0	0	0
12	5000	14.2	0.0580	0.0	0.0								
18	5000	6.3	0.0080	3.4	8.6								
20	5000	5.1	0.0048	0.0	0.0								
				3.4	8.6	-9.6	-9.6	0	0	2	2	1	1

*Friction loss using Hazen-Williams, C = 120

Exhibit 9-2
Piping System
Collection Basin - WSF 2
Ledgeview Farm

Piping System

Pipe Diameter	**12**		**15**		**20**	
Item	**Ke**	**Le**	**Ke**	**Le**	**Ke**	**Le**
entrance			0.5			
300				300		
exit			1			
Total	0	0	1.5	300	0	0

Piping System
Collection Basin - WSF 2

Diameter (in)	Flow (gpm)	Velocity (ft/sec)	s* (ft/ft)	HK e (ft)	HL e (ft)	Static Min (ft)	Static Max (ft)	Discharge Pressure (ft)	Discharge Pressure (psi)	TDH Min (ft)	TDH Max (ft)	TDH Min (psi)	TDH Max (psi)
12	1500	4.3	0.0062	0.0	0.0								
15	1500	2.7	0.0021	0.2	0.6								
20	1500	1.5	0.0005	0.0	0.0								
				0.2	0.6	-0.6	-7.5	0	0	0	-7	0	-3
12	2000	5.7	0.0106	0.0	0.0								
15	2000	3.6	0.0036	0.3	1.1								
20	2000	2.0	0.0009	0.0	0.0								
				0.3	1.1	-0.6	-7.5	0	0	1	-6	0	-3
12	2821	8.0	0.0201	0.0	0.0								
15	2821	5.1	0.0068	0.6	2.0								
20	2821	2.9	0.0017	0.0	0.0								
				0.6	2.0	-0.6	-7.5	0	0	2	-5	1	-2
12	3500	9.9	0.0300	0.0	0.0								
15	3500	6.4	0.0101	0.9	3.0								
20	3500	3.6	0.0025	0.0	0.0								
				0.9	3.0	-0.6	-7.5	0	0	3	-4	1	-2

*Friction loss using Hazen-Williams, C = 120

Exhibit 10

Exhibit 10-1
Detention Basin Volume
Client: Ledgeview Farm

Detention Basin

Elevation	Acres	Area ft^2 (from AutoCAD)	Volume ft^3	Volume gallons	ac-ft	18" Pipe (CFS)
724.50	0.0073462	320	-	-	0.0000	0.00
725.00	0.0118672	517	209	1,565	0.0048	8.49
726.00	0.0228008	993	964	7,213	0.0221	9.14
727.00	0.0441052	1,921	2,422	18,113	0.0556	9.76
728.00	0.1476749	6,433	6,598	49,357	0.1515	10.35

Exhibit 10-2 HEC-HMS Input Variables Feed F
Client: Ledgeview Farm
Date: 11/28/2017
By: TJS

Existing Feed Pad	FSA Existing & Proposed
Subbasin	
Area (mi^2)	0.004348528
Loss Method	SCS Curve Number
Transform Method	Kinematic Wave
Plane 1	
Length (feet)	350
Slope (FT/FT)	0.007
Roughness	0.015
Area (%)	100
Routing Steps	5
Loss 1	
Curve Number	98
Impervious (%)	0
Plane 2	
Length (feet)	na
Slope (FT/FT)	na
Roughness	na
Area (%)	na
Routing Steps	na
Loss 2	
Curve Number	na
Impervious (%)	na
Channel	
Route Upstream	No
Routing Method	Kinematic Wave
Length (feet)	200
Slope (FT/FT)	0.002
Subreaches	5
Shape	Triangle
Manning's n	0.015
Slope (xH:1V)	20

Exhibit 10-2: Equalization Basin, HEC-HMS Results

Client: Ledgeview Farm, LLC
Date: 11/29/2017
By: TJS




Figure 1. HEC-HMS Results, Equalization Basin, Volume Units - Inches




Figure 2. HEC-HMS Results, Equalization Basin, Volume Units – Acre-Feet

Exhibit 10-2: Feed Pad Runoff, HEC-HMS Results

Client: Ledgeview Farm, LLC
Date: 11/29/2017
By: TJS




Figure 1. HEC-HMS Results, Peak Discharge from Feed Pad, Volume Units – Inches




Figure 2. HEC-HMS Results, Peak Discharges, Volume Units – acre-feet

Exhibit 11

Emergency Response Contacts Summary

Farm Name: Ledgeview Dairy

Owner/Operator: Jason Pansier Phone: (920) 655-3875 Cell: _____

Owner/Operator: _____ Phone: _____ Cell: _____

Farm Address: 3875 Dickinson Road, DePere, WI 54115

Farm Location: T23N R21E Section 29 & 33 County: Brown

Driving Directions or Emergency Coordinates: From DePere travel East on Chicago Street/Dickinson Road in Ledgeview. Farm will be on left in approx. 4.7 miles.

In Case of Injury, Fire, or Rescue Emergency, Immediately Implement the Following:

1. Assess the condition of the victim, extent of the emergency (fire, rescue) and call for help.
2. Stabilize the victim, use on-site rescue equipment, evacuate buildings, or begin fire suppression as necessary.
3. Brief emergency responders upon arrival on current status of situation.

In Case of a Spill, Leak, or Failure at the Storage Facility, During Transport, or Land Application, Immediately Implement the Following:

1. Stop the source of the leak or spill.
2. Make appropriate calls for people, equipment, and materials. See contacts below.
   - Notify DNR spill hotline: 1-800-943-0003 (Spill reporting is mandatory by state law.)
   - Call sheriff's office if spilled on public roads or its right-of-ways for traffic control.
   - Clear the road and roadside of spilled material immediately.
3. Contain the spill
4. Prevent spillage from entering surface waters, tile intakes, or waterways.
5. Begin cleanup and land apply on approved cropland at appropriate rates.
6. Document your actions.

Emergency Contacts	Contact Person (or Company)	Phone Number
Fire/Rescue	Ledgeview Fire Department	911 or 920-336-3360
County Sheriff	Brown County Sheriff's Department	911 or 920-448-4200
Farm Emergency Coordinator	Jason Pansier	920-655-3875
DNR Hazardous Spill Line		1-800-943-0003
DNR Permit Contact/Warden	Heidi Schmitt-Marquez	
Veterinarian	Ken Foust	920-336-7233
Equipment/Supplies	**Contact Person (or Company)**	**Phone Number**
On-Farm Equipment Operator	Jason Pansier	920-655-3875
Excavation Contractor	Jason Pansier	920-655-3875
Manure Hauler	Jason Pansier	920-655-3875
Septic Tank Pumping Truck	Kiekhaefer Septic Service	920-864-7025
Mortality Disposal Contractor	Circle R Mink Ranch	920-434-0218
Local Government Contacts	**Contact Person**	**Phone Number**
Town Chairman Town of Ledgeview	Phil Danen	920-336-3360
LCD County Conservationist	Dave Wettencamp	920-391-4639
NRCS District Conservationist	John Malvitz	920-884-3910

Be prepared to provide the following information:

- Your name and contact information
- Farm address, location and other pertinent identification information.
- Nature of emergency (employee injury, fire, discharge of manure or hazardous materials).
- Emergency equipment and personnel that are needed.
- Potential for manure or hazardous materials to reach surface waters or major field drains.
- Current status of containment efforts.
- Location of hazardous/flammable materials, and fire suppression equipment
- Location of emergency cutoff switches or valves.

Exhibit 12

Exhibit 12 – List of Design Standards Referenced

NRCS Practice Standards

- NRCS Practice Standard 313 – Waste Storage Facility (10/17)
- NRCS Practice Standard 522 – Pond Sealing or Lining – Concrete (10/17)
- NRCS Practice Standard 634 – Waste Transfer (1/14)

Wisconsin Construction Specifications

- Wisconsin Construction Specification 4 – Concrete (10/17)
- Wisconsin Construction Specification 004 Embedded or Expansive Waterstop (10/17)
- Wisconsin Construction Specification 204 – Earthfill for Waste Storage Facilities (10/12)
- Wisconsin Construction Specification 300 – Clay Liner (3/16)
- Wisconsin Construction Specification -- 634 Waste Transfer Pipe (8/16)

Wisconsin Administrative Code

- NR 213 Lining of Industrial Lagoons and Design of Storage Structures

Exhibit 13

Authority of the Inspector - Memorandum of Understanding

This Authority of the Inspector - Memorandum of Understanding has been developed so that before the project begins the contractors performing work on the job site understand the role of the inspector as well as the authority level that the inspector has as it relates to the Areas to be Inspected in the Construction Documents.

The Inspector's role is to act as a third party and provide independent inspection and verification that the Areas to be Inspected have been constructed as they were designed in the construction plans.

The owner(s) of the project have asked the inspector to act on their behalf as it relates to ensuring that the Inspectable Components identified in the Areas to be Inspected are installed and constructed as they are shown and designed on the construction plans.

The Inspector will use all reasonable care in arriving at alternative solutions that meet the intent on the design plans when situations develop that make following the construction plans difficult or add additional cost to construction.

The contractor and owner(s) agree that the decision of the Inspector is final as it relates to certification of the Areas to be Inspected.

The Inspector will be asked to sign a document that certifies that, to the best of their knowledge and professional judgment, the Inspectable Components Listed in Section A have been constructed as designed in the construction plans.

Owner Date

Contractor Date

VEGETATION – Use scientific names of plants.

Sampling Point: 203B

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Herb Stratum (Plot size: 5')			
1. No vegetation present			
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
	0 = Total Cover		

Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 0 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes ____ No X

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 203B

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-10"	10YR 3/1	100					SiL	
10-12"	10YR 3/1	90	7.5YR 4/6	10	C	M	SiSaL	
12-22"	5YR 4/4	100					SiSa	
22-24"	5YR 4/4	100					Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes ____ No X

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 204B

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: MaA - Manawa sandy loam, 1-3% slopes NWI classification: Wetland Indicator Soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation X, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes _____ No X

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes _____	No X	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes X	No _____	
Wetland Hydrology Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants. Sampling Point: 204B

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Herb Stratum (Plot size: 5')			
1. No vegetation			
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
	0 = Total Cover		

Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 0 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes ____ No X

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 204B

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-2"	10YR 3/1	100					SiL	
2-13"	10YR 3/1	90	7.5YR 4/6	10	C	M	SiL	
13-24"	10YR 4/1	95	7.5YR 4/6	5	C	M	Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes X No ___

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 205B

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: AeA - Allendale fine sandy loam, 0-3% slopes NWI classification: Wetland Indicator Soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation X, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes _____ No X

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes _____	No X	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes X	No _____	
Wetland Hydrology Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants.

Sampling Point: 205B

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Herb Stratum (Plot size: 5')			
1. No vegetation			
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
	0 = Total Cover		

Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 0 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0 (A/B)

Prevalence Index worksheet:

Total % Cover of:		Multiply by:	
OBL species		x 1 =	
FACW species		x 2 =	
FAC species		x 3 =	
FACU species		x 4 =	
UPL species		x 5 =	
Column Totals:	(A)		(B)

Prevalence Index = B/A = _____

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes _____ No X

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 205B

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-13"	10YR 3/2	95	10YR 4/6	5	C	M	SiL	
13-24"	5YR 4/4	100						

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) (**LRR R, MLRA 149B**)
- ___ Polyvalue Below Surface (S8) (**LRR R, MLRA 149B**)
- ___ Thin Dark Surface (S9) (**LRR R, MLRA 149B**)
- ___ Loamy Mucky Mineral (F1) (**LRR K, L**)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) (**LRR K, L, MLRA 149B**)
- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ 5 cm Mucky Peat or Peat (S3) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L**)
- ___ Polyvalue Below Surface (S8) (**LRR K, L**)
- ___ Thin Dark Surface (S9) (**LRR K, L**)
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Piedmont Floodplain Soils (F19) (**MLRA 149B**)
- ___ Mesic Spodic (TA6) (**MLRA 144A, 145, 149B**)
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes X No ___

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 301C

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21N

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): concave Slope (%): 0-1%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: KhB - Kewaunee silt loam, 2-6% slopes NWI classification: Upland

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation X, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes _____ No X

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes _____	No X	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____
Wetland Hydrology Present?	Yes _____	No X	

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants.

Sampling Point: 301C

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Herb Stratum (Plot size: 5')			
1. No vegetation	0		
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
	0 = Total Cover		
Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 0 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0 (A/B)

Prevalence Index worksheet:

Total % Cover of:		Multiply by:	
OBL species		x 1 =	
FACW species		x 2 =	
FAC species		x 3 =	
FACU species		x 4 =	
UPL species		x 5 =	
Column Totals:	(A)		(B)

Prevalence Index = B/A = _____

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes _____ No X

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 301C

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-16"	10YR 3/2	100					SiL	
16-24"	5YR 4/4	100					Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. [2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes _____ No X

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 302C

Investigator(s): Rachel Ecker Section, Township, Range: Secion 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.49" Datum: Google Earth

Soil Map Unit Name: KhB - Kewaunee silt loam, 2-6% slopes NWI classification: Upland

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation X, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes _____ No X

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes _____	No X	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____
Wetland Hydrology Present?	Yes _____	No X	

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants.

Sampling Point: 302C

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Herb Stratum (Plot size: 5')			
1. No vegetation	0		
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
	0 = Total Cover		

Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 0 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0 (A/B)

Prevalence Index worksheet:

Total % Cover of:		Multiply by:	
OBL species		x 1 =	
FACW species		x 2 =	
FAC species		x 3 =	
FACU species		x 4 =	
UPL species		x 5 =	
Column Totals:	(A)		(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes ____ No X

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 302C

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-12"	10YR 3/2	100					SiL	
12-24"	5YR 4/4	100					Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes _____ No X

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 303C

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: KhB - Kewaunee silt loam, 2-6% slopes NWI classification: Upland

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation X, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes _____ No X

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes _____	No X	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____
Wetland Hydrology Present?	Yes _____	No X	

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants. Sampling Point: 303C

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Herb Stratum (Plot size: 5')			
1. No vegetation	0		
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
	0 = Total Cover		
Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 0 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes ____ No X

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 303C

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-7"	10YR 3/2	100					SiL	
7-24"	5YR 4/4	100					Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes _____ No X

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 401D

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): concave Slope (%): 0%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: MaA - Manawa sandy loam, 1-3% slopes NWI classification: Wetland Indicator soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes X No _____

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes X No _____	**Is the Sampled Area within a Wetland?** Yes X No _____
Hydric Soil Present?	Yes X No _____	
Wetland Hydrology Present?	Yes X No _____	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- X Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- X FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes ___	No X	Depth (inches): _____
Water Table Present?	Yes X	No ___	Depth (inches): 18"
Saturation Present? (includes capillary fringe)	Yes X	No ___	Depth (inches): surface

Wetland Hydrology Present? Yes X No _____

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants. Sampling Point: 401D

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Herb Stratum (Plot size: 5')			
1. Phragmites australis	85	Y	FacW
2. Impatiens capensis	20	N	FacW
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
.5 = 52.5 .2 = 21	105 = Total Cover		
Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across All Strata: 2 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 50 (A/B)

Prevalence Index worksheet:

Total % Cover of:		Multiply by:	
OBL species		x 1 =	
FACW species		x 2 =	
FAC species		x 3 =	
FACU species		x 4 =	
UPL species		x 5 =	
Column Totals:	(A)		(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

X 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes X No ____

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 401D

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-7"	10YR 3/1	90	10YR 4/6	10	C	M	SiL	
7-24"	5YR 5/2	100					SiL	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- X Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes X No ___

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 402D

Investigator(s): Rachel Ecker Section, Township, Range: Seecion 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: MaA - Manawa sandy loam, 1-3% slopes NWI classification: Wetland Indicator Soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation X, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes X No _____

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes X	No _____	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes _____	No X	
Wetland Hydrology Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants. Sampling Point: 402D

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		

Herb Stratum (Plot size: 5')			
1. Ambrosia trifida	50	Y	FacW
2. Phragmites australis	45	Y	Fac
3. Abutilon theophrasti	5	N	FacU
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
.5 = 50 .2 = 20	100 = Total Cover		

Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 2 (A)

Total Number of Dominant Species Across All Strata: 2 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 100 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes Y No ____

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 402D

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-14"	10YR 3/2	100					SiL	
14-24"	5YR 4/4	100					Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. [2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes ____ No X

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 403D

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): concave Slope (%): 0%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 88° 57' 52.49" Datum: Google Earth

Soil Map Unit Name: MaA - Manawa sandy loam, 1-3% slopes NWI classification: Wetland Indicator Soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes X No _____

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present? Yes X No _____	**Is the Sampled Area within a Wetland?** Yes X No _____
Hydric Soil Present? Yes X No _____	If yes, optional Wetland Site ID: _____
Wetland Hydrology Present? Yes X No _____	

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- X Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- X Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- X FAC-Neutral Test (D5)

Field Observations:

Surface Water Present? Yes ___ No X Depth (inches): _____

Water Table Present? Yes X No ___ Depth (inches): 17"

Saturation Present? (includes capillary fringe) Yes X No ___ Depth (inches): surface

Wetland Hydrology Present? Yes X No _____

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants. Sampling Point: 403D

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1. Fraxinus pennsylvanica	15	Y	FacW
2.			
3.			
4.			
5.			
6.			
7.			
.5 = 7.5 .2 = 3	15	= Total Cover	
Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0	= Total Cover	
Herb Stratum (Plot size: 5')			
1. Phalaris arundinacea	75	Y	FacW
2. Impatiens capensis	20	Y	FaW
3. Typha latifolia	5	N	Obl
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
.5 = 50 .2 = 20	100	= Total Cover	
Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0	= Total Cover	

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 3 (A)

Total Number of Dominant Species Across All Strata: 3 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 100 (A/B)

Prevalence Index worksheet:

Total % Cover of:		Multiply by:	
OBL species		x 1 =	
FACW species		x 2 =	
FAC species		x 3 =	
FACU species		x 4 =	
UPL species		x 5 =	
Column Totals:	(A)		(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

___ 1 - Rapid Test for Hydrophytic Vegetation

___ 2 - Dominance Test is >50%

___ 3 - Prevalence Index is ≤3.0[1]

___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)

___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes X No ___

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 403D

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-5"	10YR 3/2	100					SiL	
5-12"	10YR 3/1	80	10YR 4/6	20	C	M	L	
12-24"	10YR 5/2	80	10YR 4/6	20	D	M	L	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- X Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes X No ___

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 404D

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: MaA - Manawa sandy loam, 1-3% slopes NWI classification: Wetland Indicator Soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes X No _____

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes X	No _____	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes _____	No X	
Wetland Hydrology Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants. Sampling Point: 404D

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Herb Stratum (Plot size: 5')			
1. Bromus inermis	85	Y	FacU
2. Ambrosia trifida	15	N	Fac
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
.5 = 50 .2 = 20	100 = Total Cover		
Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across All Strata: 1 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 100 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

- ___ 1 - Rapid Test for Hydrophytic Vegetation
- X 2 - Dominance Test is >50%
- ___ 3 - Prevalence Index is ≤3.0[1]
- ___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)
- ___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes X No ___

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 404D

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-22"	10YR 3/2	100					SiL	
22-24"	10YR 3/2	90	10YR 4/6	10	C	M	Cl	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes ____ No X

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 405D

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): concave Slope (%): 0%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.49" Datum: Google Earth

Soil Map Unit Name: MaA - Manawa sandy loam, 1-3% slopes NWI classification: Wetland Indicator Soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes X No _____

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes X	No _____	**Is the Sampled Area within a Wetland?** Yes X No _____
Hydric Soil Present?	Yes X	No _____	If yes, optional Wetland Site ID: _____
Wetland Hydrology Present?	Yes X	No _____	

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- X FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes ___	No X	Depth (inches): _____
Water Table Present?	Yes ___	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes X	No ___	Depth (inches): surface

Wetland Hydrology Present? Yes ___ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants. Sampling Point: 405D

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Herb Stratum (Plot size: 5')			
1. Phragmites australis	90	Y	FacW
2. Impatiens capensis	15	N	FacW
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
.5 = 52.5 .2 = 21	105 = Total Cover		
Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across All Strata: 1 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 100 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

- ___ 1 - Rapid Test for Hydrophytic Vegetation
- X 2 - Dominance Test is >50%
- ___ 3 - Prevalence Index is ≤3.0[1]
- ___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)
- ___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes X No ___

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 405D

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-5"	10YR 3/1	100					SiL	
5-24"	5YR 5/2	90	7.5YR 4/6	10	D	M	L	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- X Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) (**LRR R, MLRA 149B**)
- ___ Polyvalue Below Surface (S8) (**LRR R, MLRA 149B**)
- ___ Thin Dark Surface (S9) (**LRR R, MLRA 149B**)
- ___ Loamy Mucky Mineral (F1) (**LRR K, L**)
- ___ Loamy Gleyed Matrix (F2)
- X Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) (**LRR K, L, MLRA 149B**)
- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ 5 cm Mucky Peat or Peat (S3) (**LRR K, L,** R)
- ___ Dark Surface (S7) (**LRR K, L**)
- ___ Polyvalue Below Surface (S8) (**LRR K, L**)
- ___ Thin Dark Surface (S9) (**LRR K, L**)
- ___ Iron-Manganese Masses (F12) (**LRR K, L,** R)
- ___ Piedmont Floodplain Soils (F19) (**MLRA 149B**)
- ___ Mesic Spodic (TA6) (**MLRA 144A, 145, 149B**)
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes X No ___

Remarks:

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project/Site: 3499 Lime Kiln Road City/County: Green Bay/Brown Sampling Date: 9-5-17

Applicant/Owner: Jason Pansier - Ledgeview Dairy State: WI Sampling Point: 406D

Investigator(s): Rachel Ecker Section, Township, Range: Section 28, T23N-R21E

Landform (hillslope, terrace, etc.): Local relief (concave, convex, none): convex Slope (%): 1-2%

Subregion (LRR or MLRA): LRR K Lat: 44° 25' 59.49" Long: 87° 57' 52.59" Datum: Google Earth

Soil Map Unit Name: MaA - Manawa sandy loam, 1-3% slopes NWI classification: Wetland Indicator Soils

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No _____ (If no, explain in Remarks.)

Are Vegetation _____, Soil _____, or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? Yes X No _____

Are Vegetation _____, Soil _____, or Hydrology _____ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present?	Yes X	No _____	**Is the Sampled Area within a Wetland?** Yes _____ No X
Hydric Soil Present?	Yes _____	No X	
Wetland Hydrology Present?	Yes _____	No X	If yes, optional Wetland Site ID: _____

Remarks: (Explain alternative procedures here or in a separate report.)

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ Marl Deposits (B15)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Moss Trim Lines (B16)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ Shallow Aquitard (D3)
- ___ Microtopographic Relief (D4)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface Water Present?	Yes _____	No X	Depth (inches): _____
Water Table Present?	Yes _____	No X	Depth (inches): _____
Saturation Present? (includes capillary fringe)	Yes _____	No X	Depth (inches): _____

Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

VEGETATION – Use scientific names of plants.

Sampling Point: 406D

Tree Stratum (Plot size: 30')	Absolute % Cover	Dominant Species?	Indicator Status
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Sapling/Shrub Stratum (Plot size: 15')			
1.			
2.			
3.			
4.			
5.			
6.			
7.			
	0 = Total Cover		
Herb Stratum (Plot size: 5')			
1. Ambrosia trifida	60	Y	Fac
2. Bromus inermis	30	Y	FacU
3. Abutilon theophrasti	20	N	FacU
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			
.5 = 55 .2 = 22	110 = Total Cover		
Woody Vine Stratum (Plot size: 30')			
1.			
2.			
3.			
4.			
	0 = Total Cover		

Dominance Test worksheet:

Number of Dominant Species That Are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across All Strata: 2 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 50 (A/B)

Prevalence Index worksheet:

Total % Cover of:	Multiply by:
OBL species	x 1 =
FACW species	x 2 =
FAC species	x 3 =
FACU species	x 4 =
UPL species	x 5 =
Column Totals: (A)	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

- ___ 1 - Rapid Test for Hydrophytic Vegetation
- X 2 - Dominance Test is >50%
- ___ 3 - Prevalence Index is ≤3.0[1]
- ___ 4 - Morphological Adaptations[1] (Provide supporting data in Remarks or on a separate sheet)
- ___ Problematic Hydrophytic Vegetation[1] (Explain)

[1]Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Definitions of Vegetation Strata:

Tree – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

Sapling/shrub – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

Woody vines – All woody vines greater than 3.28 ft in height.

Hydrophytic Vegetation Present? Yes X No ___

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: 406D

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type[1]	Loc[2]	Texture	Remarks
0-16"	10YR 3/2	100					SIL	
16-24"	5YR 4/4	100					CI	

[1]Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

[2]Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Dark Surface (S7) **(LRR R, MLRA 149B)**
- ___ Polyvalue Below Surface (S8) **(LRR R, MLRA 149B)**
- ___ Thin Dark Surface (S9) **(LRR R, MLRA 149B)**
- ___ Loamy Mucky Mineral (F1) **(LRR K, L)**
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils[3]:

- ___ 2 cm Muck (A10) **(LRR K, L, MLRA 149B)**
- ___ Coast Prairie Redox (A16) **(LRR K, L, R)**
- ___ 5 cm Mucky Peat or Peat (S3) **(LRR K, L, R)**
- ___ Dark Surface (S7) **(LRR K, L)**
- ___ Polyvalue Below Surface (S8) **(LRR K, L)**
- ___ Thin Dark Surface (S9) **(LRR K, L)**
- ___ Iron-Manganese Masses (F12) **(LRR K, L, R)**
- ___ Piedmont Floodplain Soils (F19) **(MLRA 149B)**
- ___ Mesic Spodic (TA6) **(MLRA 144A, 145, 149B)**
- ___ Red Parent Material (F21)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (Explain in Remarks)

[3]Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):

Type: N/A

Depth (inches): N/A

Hydric Soil Present? Yes ____ No X

Remarks:

Exhibit 7



PROJECT NO.	X	REVISIONS BY	DATE	DESCRIPTION OF REVISION	REVISIONS BY	DATE	DESCRIPTION OF REVISION	LEDGEVIEW DAIRY SATILITE FACILITY BROWN COUNTY, WISCONSIN	SCALE: 1" = 125'	WETLAND MAP	Roach & Associates, LLC Dairy Business and Management Consulting Environmental Engineering 856 North Main Street, Seymour, WI, 54165 PH: 920-833-6340 Fax: 920-833-9851	SHEET NO. 1 of 1
DATE:	09/19/2017											
DRAWN BY:	MHP											
CHECKED BY:	INITIALS											

State of Wisconsin
DEPARTMENT OF NATURAL RESOURCES
PO Box 7185
101 S. Webster Street
Madison WI 53707-7185

Scott Walker, Governor
Daniel L. Meyer, Secretary
Telephone 608-266-2621
FAX 608-267-3579
TTY Access via relay - 711

January 18, 2018

FILE REF: R-2017-0226
WPDES Permit #: WI-0065421

Jason Pansier
Ledgeview Farms, LLC
3875 Dickinson Rd.
DePere, WI 54115

Subject: Conditional Approval of Plans & Specifications for a Waste Storage Facilities and Transfer Systems and a Grant of Waiver for Well Setback at, Ledgeview Farms, LLC, (Heifer Farm) at Sec 28, T23N, R21E, Ledgeview Township, Brown County

Dear Mr. Pansier:

The Division of External Services conditionally approves the above referenced plans and specifications, submitted by Richard Seas, P.E., Roach & Associates, LLC and received on December 6, 2017. The evaluation was submitted because of a permit issuance. The review was conducted in accordance with s. 281.41 Wis. Stats., chs. NR 151 and NR 243, Wis. Adm. Code, and applicable NRCS Standards. Construction is approved to commence for a period of two years from the approval date. If work will commence later, or will occur over a longer period without continuous work (other than due to weather) a new written approval must be obtained. Questions may be directed to the regional office, or the review engineer Jeff Kreider, DNR Madison Office (contact information is at the end of this letter).

Proposed Project: The proposed project will construct a waste storage pond and detention basin that will collect manure and leachate runoff from an existing animal lot and feed storage areas. Final disposition of wastes will be land applied in accordance with an approved nutrient management plan (NMP).

Site Assessment: Geographical features of the site include soils that are Kewaunee silt loam. There are no streams or wetlands, other than what was identified at the farm, within proposed construction area. Clean runoff will be diverted around waste handling areas to existing waterways. No karst features are known to exist within 1,000 ft of the proposed facilities or systems. One ground water supply well is located within 250 feet of the proposed facilities or systems. A well waiver was submitted along with the proposed plans and specifications. A wetland delineation was conducted and concurred by the Department on November 7, 2017 at the construction site. Wetlands were outlined and the construction sites will not be located within these designated areas.

Fifteen test pits were collected with soils analysis finding the percent passing a 200 sieve ranges between 789% to 82.6% and plasticity index range between 17 to 28.9. Bedrock was not found. Saturated soils were found in one test pit at 9.2 feet below the bottom of the proposed waste storage pond 2.

Waste Storage: The proposed design was submitted to meet NRCS Standard 313 (10/17) and 522, Table 2 and 2A – Concrete Liner With Waterstop, Column 1 (10/17). The design is in compliance with ss. NR 213 and NR 243.15(3), Wis. Adm. Code. Below is a summary of what is proposed.

- The proposed irregular shaped waste storage designated as WSF2 will be 146-312 ft x 545 ft x 13.4 ft deep. Six inch PVC waterstop will be used at construction joints.
- The embankment walls and floor are designed with 5 inch and 7 inch thick steel reinforced concrete respectively. An 8-inch clay subliner will be constructed beneath the proposed concrete liner.
- The proposed storage will have a maximum operating level (MOL) volume of 14,749,062 gallons. This will provide the permittee a total of 291 days of storage.
- The floor elevation will be 706.6 ft and the MOL elevation will be 718.4 ft. Interior and exterior embankment slopes will be 2.5:1 and 4:1 respectively with a berm width of 20 ft.
- A core trench will be constructed along the western side and a portion of the northen side.

- The agitation pad and sump will be 30 ft x 20 ft x 1 ft deep. A 20 ft wide ramp will extend down the side of the proposed storage pond on the southeast corner to the sump. The MOL, MOS and elevation markers will be located along the ramp side.

Detention Basin: The proposed design was submitted to meet with NRCS Standard 313 (10/17) and 522, Table 2 and 2A – Concrete Liner With Waterstop, Column 1 (10/17). The design is in compliance with ss. NR 213 and NR 243.15(3), Wis. Adm. Code. Below is a summary of what is proposed.

- The proposed rectangular shaped detention basin will be 48 ft x 130 ft x 3.5 ft deep.
- The embankment walls and floor are designed with 7-inch thick steel reinforced concrete. An 8-inch clay subliner will be constructed beneath the proposed concrete liner.
- The floor elevation will be 724.5 ft. Interior and exterior embankment slopes will be 3:1 and 20:1 respectively.
- The proposed basin will have a volume of 49,353 gallons and is designed to be empty. A 4 ft diameter x 6 ft deep manhole will be placed in the bottom of the basin. All runoff will flow into the manhole, which will be connected to a transfer pipe that gravity flows to WSF2.

Transfer Pipe: The proposed design was submitted to meet with NRCS Standard 634 (1/14). The design is in compliance with s. NR 243.15(4), Wis. Adm. Code.

- The proposed transfer pipes are approved, but have not been reviewed. The transfer pipes are still subject to the requirements of ch. NR 243, Wis. Adm. Code and all applicable technical standards.

Feed Storage Area Runoff Controls: The proposed design is in compliance with s. NR 243.15(2), Wis. Adm. Code. Below is a summary of what is proposed.

- The existing feed storage area is sloped towards the south. Runoff from the feed storage area will then flow into the proposed detention basin which is designed to detain up to a 25-year/24-hour storm event. A proposed 18-inch ASTM F679 PVC gravity pipe will transfer the runoff from the basin to the proposed WSF2.
- The existing animal lot is sloped towards the west. Runoff from the animal lot will flow into an existing collection tank which is designed to detain up to a 25-year/24-hour storm event. A proposed 15-inch SDR35 PVC gravity pipe will transfer the runoff from the collection tank to the proposed WSF2.

Days of Storage: When the proposed projects are constructed, the permittee will have 291 days of storage. Below is a summary of what was submitted in determining the days of storage.

- Waste storage pond #1 has an MOL volume of 5,006,618 gallons.
- Waste storage pond #2 has an MOL volume of 14,749,062 gallons.
- Manure and wastewater generated: 18,207,479 gallons.
- Leachate and runoff from the Head Quarters Farm: 110,042 gallons.
- Leachate and runoff from the Heifer Farm: 2,257,696 gallons.
- Animal lot runoff from the Head Quarters Farm: 110,869 gallons.
- Animal lot runoff from the Heifer Farm: 634,723 gallons.
- Runoff from animal lots and feed storage areas from a 25-year/24-hour storm event: 448,487 gallons.

Conditions of Approval: The plans and specifications for project number R-2017-0226 are hereby approved and subject to chs. NR 151 and NR 243, Wis. Adm. Code, and the conditions listed below:

1. Notification: Prior to construction and when construction is complete, notify the DNR regional contact and county contact provided a copy of the approval (contact information is at the end of this letter).
2. Inspection: During the construction of critical components, inspection shall be performed by a Wisconsin registered professional engineer or other qualified third party (excludes the owner and construction contractor and their employees).
3. Post-Construction Documentation: Within 60 days of completing construction, submit to the DNR's e-Permittting website (http://dnr.wi.gov/permits/water) the post-construction report and send one paper copy to the DNR's regional contact. The report shall include the requirements within s. NR 243.15(10) and ch. NR 108, Wis. Adm. Code.

Grant of Waiver: In accordance with s. NR 243.15(1)(c), Wis. Adm. Code, a waiver is hereby granted from s. NR 243.15(1)(a)2., Wis. Adm. Code, to allow a waste transfer pipe from the proposed detention basin to the proposed waste storage pond #2. to be located within 250 ft of a groundwater supply well, based on justifications set forth in the proposed plans and specifications.

Limitation of Approval: The DNR reserves the right to order changes or additions should conditions arise making this necessary. This approval is not to be construed as a DNR determination on the issuance of a Wisconsin Pollutant Discharge Elimination System Permit or opinion as to the ability of the proposed system to comply with effluent limitations in such a permit, approval of an Environmental Impact Statement that may be prepared, or approval for any activities requiring a permit under chs. 30 or 31, Wis. Stats. Where necessary, plans and specifications should be submitted to the Department of Safety and Professional Services (formerly Department of Commerce) or other state or local agencies to ensure conformance with applicable codes or regulations of such agencies.

Tax Treatment: Tangible personal property, that becomes part of a waste treatment of pollution abatement plant or equipment, may be exempt from sales tax under s. 77.45(26), Wis. Stats. Similarly, property purchased or constructed as a waste treatment facility and used for industrial waste treatment may be exempt from general property taxes under s. 70.11(21), Wis. Stats. A prerequisite to exemption is filing a statement on prescribed forms. To obtain the forms, and information about this sales tax exemption, please contact the Department of Revenue, P.O. Box 8933, Madison, WI 53708, or check their website http://www.revenue.wi.gov/.

Appeal Notice: If you believe that you have a right to challenge this decision, you should know that the Wisconsin Statutes and Administrative Rules establish time periods within which requests to review Department decisions must be filed. For judicial review of a decision pursuant to ss. 227.52 and 227.53, Wis. Stats., you have 30 days after the decision is mailed, or otherwise served by the Department, to file your petition with the appropriate circuit court and serve the petition on the Department. Such a petition for judicial review must name the Department of Natural Resources as the respondent. To request a contested case hearing pursuant to s. 227.42, Wis. Stats., you have 30 days after the decision is mailed, or otherwise served by the Department, to serve a petition for hearing on the Secretary of the Department of Natural Resources. All requests for contested case hearings must be made in accordance with s. NR 2.05(5), Wis. Adm. Code, and served on the Secretary in accordance with s. NR 2.03, Wis. Adm. Code. The filing of a request for a contested case hearing does not extend the 30-day period for filing a petition for judicial review.

STATE OF WISCONSIN
DEPARTMENT OF NATURAL RESOURCES
For the Secretary

Mary Anne Lowndes
Chief, Runoff Management Section
Bureau of Watershed Management

Jeff C. Kreider
Engineer, Runoff Management Section
Bureau of Watershed Management

email: Richard Seas, P.E.; Roach & Associated, LLC
(920) 833-6340; richard@jmroach.com

Mike Mushinski; Brown County Conservationist
(920) 391-4621; mushinski_ML@co.brown.wi.us

Matt Woodrow, P.E.; DATCP
(920) 427-8505; matthew.woodrow@wisconsin.gov

Heidi Schmitt Marquez; DNR, Northeast Region
(920) 662-5187; Heidi.SchmittMarquez@Wisconsin.gov

Jeff Kreider; DNR, Central Office
(608) 266-0856; jeff.kreider@wisconsin.gov

Charlotte Nagel

From: Schmitt Marquez, Heidi S - DNR <Heidi.SchmittMarquez@wisconsin.gov>
Sent: Monday, January 22, 2018 2:03 PM
To: Sarah Burdette (sburdette@ledgeviewwisconsin.com); Scott Brosteau (scott.brosteau@meadhunt.com)
Subject: FW: Ledgeview Dairy Conditional Approval Letter (R-2017-0226)
Attachments: Ledgeview Approval Letter (R-2017-0226).pdf

FYI – see the attached approval for the proposed storage facility for Ledgeview Farms LLC. Jeff is still working on completing the review for the evaluations submitted for the reviewable existing structures. He should be finished with that fairly soon. On page 2 under the "Days of Storage" section, waste storage pond #1 refers to the existing manure storage facility currently in use at the main farm site, and waste storage pond #2 refers to the proposed waste storage facility at the heifer farm site for which the letter provides approval.

Let me know if you have any questions, or would like to discuss anything further.

Thanks,

Heidi Schmitt Marquez
Phone: (920) 662-5187
Heidi.SchmittMarquez@Wisconsin.gov

We are committed to service excellence.
Visit our survey at http://dnr.wi.gov/customersurvey to evaluate how I did.

From: Kreider, Jeff C - DNR
Sent: Monday, January 22, 2018 1:40 PM
To: Rich Seas (Roach & Assoc) <richard@jmroach.com>
Cc: Schmitt Marquez, Heidi S - DNR <Heidi.SchmittMarquez@wisconsin.gov>; Mushinski, Michael L. <Mushinski_ML@co.brown.wi.us>; Woodrow, Matthew C - DATCP <Matthew.Woodrow@wisconsin.gov>
Subject: Ledgeview Dairy Conditional Approval Letter (R-2017-0226)

The Conditional Approval for the waste storage ponds and transfer systems is in effect immediately. The signed Approval will also be mailed to the owner by U.S. Mail.

In accordance with the CAFO WPDES permit and ss. NR 108(4) and (6), and 243.16, Wis. Adm. Code, and as noted in the Conditions of this Plan Approval, you are required to do the following:

> **Notification: Prior to construction and when construction is complete, notify the DNR Regional CAFO contact and County contact listed in the cc's at the end of the Conditional Approval letter.**
>
> **Inspection: The owner or their consultant shall ensure that a competent resident inspector is present during all construction of critical components.**
>
> **Post-Construction Documentation: Within 60 days of completing construction, submit via the DNR's e-Permitting system as required by the Conditional Construction Approval letter.**

Keep in mind, engineering oversight during construction is important to ensure the project is properly constructed in accordance with the Conditionally Approved Plans, and protect your capital investment.

This email and the attached approval is being sent on behalf of DNR Review Engineer, Jeff Kreider. If you have any questions, please contact Jeff, or the DNR Regional Staff.

We are committed to service excellence.
Visit our survey at http://dnr.wi.gov/customersurvey to evaluate how I did.

Jeff Kreider
Water Resources Engineer – Bureau of Watershed Management
Wisconsin Department of Natural Resources
Phone: (608) 266-0856
Cell Phone: (608) 212-6547
jeff.kreider@wisconsin.gov


dnr.wi.gov

Ledgeview
Set your sights high

January 19, 2018

Ledgeview Farm, LLC
c/o Jason Pansier
3875 Dickinson Road
De Pere, WI 54115

RE: Ledgeview Farm, LLC
ATCP-51 Application for Local Approval
New or Expanded Livestock Facility

Mr. Pansier,

Pursuant to your request and submittal dated December 6, 2017, the Town of Ledgeview has completed a detailed review of the Ledgeview Farm, LLC – ATCP 51 application for local approval for new or expanded livestock facility at 3499 Lime Kiln Road, Ledgeview, in Brown County, WI.

The purpose of this letter is to provide an assessment of completeness of the application. The following provisions are either incomplete or require additional information before a completeness determination can be finalized. Please review, and feel free to contact me with any questions.

Area and Site Maps
Maps #1 and #2

* Area Map and Site Map contour elevations as provided in Exhibit 1 are not clearly labeled.
* Area Map and Site Map not consistent with Plans for Heifer Site Structures - The Site Map shows proposed Waste Transfer Channel while the Site Plans show a proposed detention basin and transfer pipe from the feed storage area and a waste transfer pipe from the collection basin from the animal lot.
* Appears to be an existing Feed storage and Manure Storage (Pit1 & Pit2) at Headquarters and an unconfined stacking area at the end of barn at the Heifer Site in the 2017 Waste Storage Facility & Runoff Management System Report. These structures are not label in the Siting Application Site Map for the Headquarters Site. Please clarify and label.

Map #3
* Provide statement proposed structures meet setbacks for animal housing and waste storage and show setbacks on Site Map.

3700 Dickinson Road
De Pere WI 54115
P: 920/336/3360 F: 920/336/8517
www.ledgeviewwisconsin.com

Worksheet 2- Odor Management
#12
Headquarter Site Odor Score calculation

* Explain if a natural crust normally exists on W1 and provide bedding used and a management plans for maintaining a natural crust.
* L2 is listed as a bed pack barn in the 2017 Waste Storage Facility & Runoff Management System Report but in the odor score is listed as a free stall barn. Please clarify.

Heifer site Odor Score calculation.

* Explain if a natural crust would form from collection of runoff from the animal lot and Feed Storage Area. Provide a management plans for maintaining a natural crust.
* Is the gutter control practice for the animal lot existing or proposed? If existing are they in working condition and have capacity to divert roof runoff? If proposed provide plans and calculations consistent with ATCP 50.85.
* The detention basin for the feed area is not included in the odor score though it appears it will collect runoff from the proposed animal lot. Please clarify and provide management plan.

Worksheet 4
#25 and# 26

* The existing manure storages Pit 1 and Pit 2 at the Headquarters site are not identified in the Siting Application. The 2017 Waste Storage Facility & Runoff Management System Report explains these are not in use. If not in use, they are to be closed and closure plans are needed. If plans to use exist then Pit 1 and Pit2 should be included in Odor Management (Work Sheet 2) and Waste Structures.

Worksheet 5
#29

* No Runoff control plans and calculations for Y1 Animal Lot at Headquarters site and Y2 Animal lot at Heifer site. Please provide plans and containment calculations as well as transfer methods proposed.

#31

* No explanation of apparent feed storage at Headquarters and runoff controls.
* The drainage patterns at the Feed Storage Area at the Heifer site are unclear. Will runoff leave the Feed Storage Area from the west side? Please clarify.
* No explanation of Unconfined Stacking Area on east end of L1 at Heifer Site.

Completeness considerations
#35 and #36

* Please provide plans and calculation mentioned previously

Other information

* Please provide complete Nutrient Management Plan.
  Please provide a completed Town of Ledgeview Conditional Use Permit Application

Conclusion

It is the Town's determination that the Chapter ATCP 51 – Livestock Siting Application is incomplete and deficient for consideration of approval of a Conditional Use Permit application before the Town of Ledgeview. Please provide the information outlined in this correspondence to complete your application.

Sincerely,

Philip J. Danen, Chairman
Town of Ledgeview

Attachments: ATCP 51 Application Review Checklist Completeness Determination
Town of Ledgeview Conditional Use Permit Application (blank)

ATCP 51 Application Review Checklist
Completeness Determination

This review is confined to considerations related to completeness of the application, including selective checks for consistency. This completeness review does not include an evaluation of the underlying documentation submitted with the application (e.g. plans and specifications) to determine compliance with state standards. Review for compliance with the siting standards is the next step after the completeness determination.

Applicant (Livestock Facility Name): Ledgeview Dairy
Local unit of government: Town of Ledgeview

The application was provided by (e.g. applicant / consultant / political subdivision):
Date application and related documentation was submitted to DATCP:
Reviewed by (staff):
Date review completed:

Review of Application, Worksheets and Attachments
(numbers refer to sections of the referenced application materials)

Application Form pages 390-11 to 390-20

Completeness Considerations	Complete	Incomplete	Not submitted
1) Area map # 9 – legible, scaled properly, appropriately labeled	☐	☒	☐
2) Site map (plan) # 10 - legible, scaled properly, appropriately labeled	☐	☒	☐
3) Location of livestock structures # 11 - map or narrative	☐	☒	☐
4) Employee Training Plan # 12 - addresses required elements	☒	☐	☐
5) Environmental Incident Response Plan # 13 - addresses required elements.	☒	☐	☐
6) Optional Odor Management Plan # 14 - addresses required elements (only submitted if credit taken on Worksheet 2)	☒	☐	☐
7) Page 390-20 is signed (last page)	☒	☐	☐

Notes:

Worksheet 1 – Animal Units

Completeness Considerations	Complete	Incomplete	Not submitted
8) Animal units for each livestock type are calculated, and all types are summed for a total	☒	☐	☐
9) Total animal units calculated in Worksheet 1 is consistent with the maximum number of animal units listed in # 8 on p. 390-17	☒	☐	☐
10) Worksheet is signed	☒	☐	☐

Notes:

Worksheet 2 – Odor Management

Completeness Considerations	Complete	Incomplete	Not submitted
11) Facility is exempt and the appropriate box checked Note: Expanding facilities under 1000 AU, new facilities under 500 AU, and any facility greater than 2500 feet from nearest affected neighbor are exempt, but may voluntarily complete and comply with this standard	☒	☐	☐
12) Tables A and B are completed, or a copy of the spreadsheet printout is attached (skip this if exempt)	☒	☐	☐
13) Worksheet is signed	☒	☐	☐

Notes:

WPDES permit substitution for Worksheets 3, 4, and 5

(If completed, skip sections of this checklist for Worksheets 3, 4, and 5)

Completeness Considerations	Complete	Incomplete	Not applicable
14) A current WPDES permit is attached (at minimum includes a cover letter demonstrating the permit has not expired)	☐	☐	☒
15) The WPDES permit covers an equal or greater number of animal units housed in the same locations proposed in the siting application	☐	☐	☒

Notes:

Worksheet 3 – Waste and Nutrient Management

Completeness Considerations	Complete	Incomplete	Not submitted
16) Worksheet 3 Part A	☒	☐	☐
17) Worksheet 3 Part B, including maps required by # 2	☒	☐	☐
18) Worksheet 3 Part B - animal unit number in # 1 is consistent with the maximum animal unit number in Worksheet 1 and # 8 on p. 390-17	☒	☐	☐
19) Worksheet 3 Parts A and B are signed	☒	☐	☐
20) Worksheet 3 Part C (required when > 500 AU or less than the ratio in Worksheet 3 Part B # 6)	☒	☐	☐
21) Worksheet 3 Part C is signed by a Qualified Nutrient Management Planner	☒	☐	☐
22) The total acres of cropland available for land application listed in Worksheet 3 Part B # 4 is consistent with the total acres listed in Worksheet 3 Part C	☒	☐	☐
23) Worksheet 3 Part C is signed if required	☒	☐	☐

Notes:

Worksheet 4 – Waste Storage Facilities

Completeness Considerations	Complete	Incomplete	Not submitted
24) All new or substantially altered storage facilities are identified, and design specifications attached	☒	☐	☐
25) All existing storage facilities are identified, and the appropriate verification checkbox marked	☐	☒	☐
26) Closure specifications are attached (if applicable)	☐	☒	☐
27) Combined useable storage capacity is consistent with the total waste storage capacity on Worksheet 3 Part A (sum of numbers in column A)	☒	☐	☐
28) Signed by registered professional engineer (whose license number and seal are provided) or a certified agricultural engineering practitioner	☒	☐	☐

Notes:

Worksheet 5 – Runoff Management

Completeness Considerations	Complete	Incomplete	Not submitted
29) All the following are identified (map or narrative): new or substantially altered animal lots, existing animal lots, new or substantially altered feed storage, existing feed storage	☐	☒	☐
30) For each new and substantially altered animal lot (# 1), design specifications are attached	☐	☒	☐
31) An explanation is attached for any existing lots with minor alterations (# 2 and # 3)	☐	☒	☐
32) For each new and substantially altered feed storage for high moisture feed (# 3), design specifications are attached	☒	☐	☐
33) Signed by registered professional engineer (whose license number and seal are provided) or a certified agricultural engineering practitioner	☒	☐	☐
34) Worksheet is signed by applicant	☒	☐	☐

Notes:

If applicable, additional documentation for more stringent requirements (can only be required if the local government meets requirements for more stringent regulation)

Completeness Considerations	Complete	Incomplete	Not submitted
35) Required submissions are provided	☐	☒	☐
36) Design specifications are attached (if required)	☐	☒	☐

Notes:

I:\lw\LIVESTOCK FACILITY SITING\Information and Education\checklists\Completeness Review Checklist 4-2009.doc

Ledgeview
Set your sights high

CONDITIONAL USE PERMIT APPLICATION

Ledgeview Zoning & Planning Commission

Date Submitted:

This application form must be completed online at https://townofledgeview.zoninghub.com/
Hard copy applications will not be accepted.

Completed application must be submitted to the Town Clerk no less than fourteen (14) days prior to the first Monday of the month before 12:00pm (noon) to be included on that month's ZPC agenda Zoning and Planning Commission meets the second Wednesday after the first Monday of the month at 6:00 p.m. at the Ledgeview Municipal Building.
Click here for the ZPC meeting calendar.

A Conditional Use Permit application review fee of **$200.00** must be submitted with materials

---

1) Applicant Information

Name:

Business Name:

Street Address: City/State: Zip:

Telephone: Fax: Email:

Firm Preparing Plans: Contact:

Street Address: City/State: Zip:

Telephone: Fax: Email:

All correspondence on this application should be sent to: ☐ Property Owner, OR ☐ Agent

---

2) Property Owner Information *This section can be left blank if the same as above.*

Name:

Business Name

Street Address: City/State: Zip:

Telephone: Fax: Email:

---

3) Information regarding requested Conditional Use Permit

Address/Location:

Town and Range:

Parcel ID Number:

Zoning District:

Size of parcel in acres:

Sewer: ☐ Municipal ☐ Septic/Mound

Water: ☐ Municipal ☐ Private Water Trust ☐ Private Well

Briefly describe the Proposed Site Use:

Please provide a Legal Description below:

****Please see Sec 135 - 251 for additional information on Conditional Uses****

Notes

- Attendance by the applicant is strongly encouraged at both Zoning and Planning Commission and Town Board meetings where action/approval is to take place. It is the policy of the Zoning and Planning Commission to give applicants the opportunity to speak at such meetings. Contact the Town Clerk for the meeting schedule.
- The applicant/owner of the above parcel(s) hereby gives permission to the Town of Ledgeview, its staff/employees, agents and/or appointees to enter the property for the purpose of executing their duties associated with this request and following proper notification to applicant/owner.
- Upon approval of request, check with the Ledgeview Town Clerk for any necessary permits.

4) Applicant Declarations

- The signer attests that the application has been completed accurately and all required materials have been submitted.
- Please note that the application will NOT be accepted without the signature of the property owner.

I HEREBY CERTIFY THAT I HAVE READ AND FULLY UNDERSTAND THE CONDITIONAL USE PERMIT PROCEDURE AND FAILURE TO COMPLY WITH TOWN REQUIREMENTS WILL RESULT IN THIS APPLICATION BEING WITHHELD FROM CONSIDERATION.

Signature of the Property Owner (required):	*Signature of the Applicant ("Agent" for the owner):*
Print Name:	*Print Name:*
Date:	*Date:*

5) Submittal Requirements

Each submittal shall consist of the following materials. Please note that ALL digital files MUST be in PDF format with a minimum 300dpi resolution.

- A detailed statement by the applicant describing the intended use and how the proposed conditional use will conform to standards set forth in the respective zone districts, as per Section 250 of the Zoning code
- One (1) full set of building plans
- 11 x 17 property site plan
- Completed Conditional Use Permit Application

6) Submittal Checklists (completion required for application)

A. Written Description of the intended use describing in reasonable detail the:

- ☐ Full name and contact information of the petitioner and / or agent, and property owner, if different;
- ☐ Full name and contact information of petitioner's engineers / surveyors / architects, and other design professionals used in conditional use permit application preparation;
- ☐ Existing zoning district(s) and proposed zoning district(s) if different;
- ☐ Current land uses present on the subject property;
- ☐ Proposed land uses for the subject property;
- ☐ Land use designation(s) as depicted on the adopted Comprehensive Plan;
- ☐ Projected number of residents, employees, and / or daily customers;
- ☐ Description of existing environmental features;

- ☐ Proposed amount of dwelling units, floor area, Open Space area, and landscape surface area, expressed in square feet and acreage to the nearest one-hundredth of an acre;
- ☐ Resulting site density, Floor Area Ratio as calculated using the criteria established in Sec 135 – 8, Open Space Ratio, and Landscape Surface Area Ratio, as defined by Sec 135 – 8;
- ☐ Operational considerations relating to hours of operation, projected normal and peak water usage, sanitary sewer or septic loadings;
- ☐ Operational considerations relating to potential nuisance creation pertaining to the appropriate design of street access, traffic visibility, parking, loading, exterior storage, exterior lighting, vibration, noise, air pollution, odor, electromagnetic radiation, glare and heat, fire and explosion, toxic or noxious materials, waste materials, drainage, and hazardous materials;
- ☐ Traffic generation;
- ☐ Any other information pertinent to adequate understanding by the Plan Commission of the intended use and its relation to nearby properties;
- ☐ Possible future expansion and related implications, and;
- ☐ Material Safety Data Sheets (MSDS) for all materials anticipated to be used or stored on site; Exterior building and fencing materials;

B. Property Site Plan drawing which includes:

- ☐ A title block which provides all contact information for the petitioner and / or agent, and property owner if different;
- ☐ Full name and contact information of petitioner's engineers / surveyors / architects, and other design professionals used in conditional use application preparation;
- ☐ The date of the original plan and the latest date of revision to the plan;
- ☐ A north arrow and a graphic scale;
- ☐ All property lines and existing and proposed right-of-way lines with bearings and dimensions clearly labeled;
- ☐ All existing and proposed easement lines and dimensions with a key provided and explained on the margins of the plan as to ownership and purpose;
- ☐ All required building setback and offset lines, including dimensions from structures to property lines;
- ☐ All existing and proposed buildings, accessory structures, and paved areas, including building entrances, walks, drives, decks, patios, fences, walls;
- ☐ All existing and proposed utility and drainage systems, connections, and fixtures;
- ☐ The location and dimension of all access points onto public streets including cross-section drawings of the entry throat;
- ☐ The location, type, height, size and lighting of all signage on the subject property;
- ☐ The location of all outdoor storage and refuse disposal areas and the design of all screening devices;

- ☐ The location and dimension of all loading and service areas on the subject property and labels indicating the dimension of such areas;
- ☐ The location and dimension of all on-site parking (and off-site parking provisions if they are to be employed), including a summary of the number of parking stalls provided versus required by Sec 135 – 124;
- ☐ The location, height, design/type, illumination power and orientation of all exterior lighting on the subject property -- including the clear demonstration of compliance with a limit of 0.5 foot candles at all property lines;
- ☐ The location and type of any permanently protected green space areas;
- ☐ The location and delineation of all wetlands, escarpments, uplands, or other unique environmental features;
- ☐ The location of existing and proposed drainage facilities;
- ☐ In the legend, data for the subject property:
  a) Lot Area measured in square feet and acres to the nearest one-hundredth of an acre;
  b) Floor Area measured in square feet using the criteria in Sec 135 - 8;
  c) Open Space Area as defined in Section 8 and as calculated using the criteria of Sec 135 - 8;
  d) Building Height as defined and calculated using the Sec 135 - 8 of the Zoning Code

Submit all documents to:
https://townofledgeview.zoninghub.com/

Questions:
E: cnelson@ledgeviewwisconsin.com
P: (920) 336 – 3360
F: (920) 336 – 8517

For Office Use Only

Submittal Date: __/__/__ **Staff Signature:** _____

Fees Paid: Y / N